# Working in partnership with

# deconstructuk.com




Project N°: ZP21-0103 Status: Tender Estimate

Revision N°: 01

Issued: 25<sup>th</sup> November 2021

# Fitzrovia 247 Tottenham Court Rd



# Project Information

- Client Brief
- Project Drawings/Reports
- Design Information

#### **Client Brief**

Deconstruct UK have invited Conquip Engineering Group to submit an estimate for the supply of the Temporary Propping scheme to provide support in the temporary condition for the Fitzrovia, 247 Tottenham Court Rd project.

Proposal to be based on:

- Client's previous indicative design
- 4190-S-HSK-039\_Construction Sequence\_P3 by ATK2
- Top level of props to be mounted on RC corbels above the capping beam
- No loading information or piled wall design is available for use in this proposed scheme

## **Project Drawings/Report**

This propping scheme has been produced based on the following documentation / information provided:

- 4190-S-HSK-039 Construction Sequence P3
- Indicative sketches

## **Design Information**

This proposal is based on the information supplied by Deconstruct UK, and assumptions made by Conquip Engineering Group. This is an initial proposal which will be developed in conjunction with the clients/site design teams. This proposal will be reviewed once further information has been made available and our design has been finalised and approved by Deconstruct UK.

## **Propping Proposal Assumptions**

- Double level of propping.
- 1<sup>st</sup> Level of propping installed above the Ground floor on RC corbels to allow construction of the ground floor prior to propremoval
- Connection to RC Corbels uses standard cast in connection detail
- 2<sup>nd</sup> Level propping installed on to waling beam installed at ~+22.710m
- Waling beam installed on to gallows brackets post fixed to the piled wall
- See drawings on following pages for the assumed line loads considered.
- It has been assumed load and structural forces can be accommodated using our standard proprietary equipment, no bespoke elements have been allowed for

# **Assumed Construction Sequence**

1. To Be Advised

