

- KEY:**
- Denotes proposed structure
 - Denotes lightweight stud partitions
Refer to (22) Series for details
 - Denotes 110mm Rainwater Pipe (RWP) penetrating through slab
 - Denotes 110mm Soil Vent Pipe (SVP) / 110mm Soil Stubs (SS) penetrating through slab
 - Denotes 50mm Soil Stacks (SS) penetrating through slab
 - Denotes slab penetration for rising main. Refer to drawing for diameter
 - Denotes exposed S/S. Client to confirm boxing in requirement
 - Denotes exposed S/S. Service Specialist to confirm if still required based on latest FCU arrangement
 - Denotes within wardrobes. Design to be adjusted to suit concealment

- GENERAL NOTES:**
1. This drawing must not be scaled.
 2. This drawing is to be read in conjunction with all other project drawings, and read in conjunction with ERs & specifications.
 3. Furniture layouts shown to demonstrate compliance with Part M4(2) & (3) and are not fully coordinated with latest Lorenz designs. Bathroom layouts which have been adopted to enable services design to progress.
 4. Current building regulations & ICW Insurance requirements apply
 5. For SAP and Energy requirements - Please refer to SAP ASSESSOR documentation


- GENERAL STRUCTURAL NOTES:**
1. G&P drawings to be read in conjunction with Structural Engineer's drawings.
 2. All exposed steelwork to be provided with 60min fire protection.
 3. Cavity barriers to all Party Wall junctions.
 4. Flush threshold to front entrance.
 5. Proprietary fire collars to be provided to all pipes passing through compartment floors providing 60min fire resistance.

| Rev | Issue Date | Revision Notes | Drawn |
|-----|------------|---|-------|
| D | 28.07.2022 | Construction Issue - General Amendments | SP |
| C | 05.05.2022 | Construction Issue - Concierge desk removed | AB |
| B | 14.04.2022 | Construction Issue | SP |
| A | 01.12.2021 | Preliminary Issue | MB |

General Notes
 All dimensions to be checked on site prior to commencement of any works, and/or preparation of any shop drawings. Sizes of and dimensions to any structural and MEPH services elements are indicative only. See relevant consultants' drawings for actual sizes and dimensions. This drawing to be read in conjunction with all other Architect's drawings, specifications and other Consultants' information. All proprietary systems shown on this drawing are to be installed strictly in accordance with the Manufacturers/Suppliers recommended details. Any discrepancies between information shown on this drawing and any other contract information or manufacturers/suppliers recommendations is to be brought to the immediate attention of the Architect. All work must be carried out in accordance with the Building Regulations and to the satisfaction of the Local Authority. DO NOT SCALE FROM THIS DRAWING.

CONSTRUCTION

| | | | |
|---------------|--|----------|---------------------|
| Job Number | Drawing Number | Rev | Scale |
| 0921 | (72)501 | D | 1:50@A1 1:100@A3 |
| Drawing Title | GA Ground Floor Plan As Proposed | | |
| Project | Land Adjacent to No.1 St John's Wood Park | | |
| Client | GPF Lewis | | |
| Date | 01.12.2021 | drawn MB | checked - |



Scale in Metres @ 1:50

