



1 Seventh Floor - Proposed  
1:100

Proposed exposed ductwork double skin decorative ducts serving ceiling services voids on levels 1 - 7. Atrium glazing with service penetration

Remove raised access entire level 7 floor

Proposed adjustment to ramp reduced in length by approximately 1m

Proposed exposed ductwork double skin decorative ducts serving ceiling services voids on levels 1 - 7. Atrium glazing with service penetration

Removal of Raised Access Floors in Lab Enabled Areas

Removal / Retainment of Raised Access Floors in Write-up spaces dependent on local condition.

- Proposed Partition Locations
- Proposed flexible partition locations as consented under LBC 2019/62031.
- Proposed additional flexible partition locations
- Drainage Positions - Proposed drainage penetrations in slab
- Ramps - Proposed 'illustrative' location of transition in level from slab to raised access floor. Location dependent on final tenant fit out.

**Note**  
For all items being removed, please refer to demolition drawings 21593-0340 - 0356  
Existing services in modernised areas to be altered, refer to services consultant drawings and reports for details.

