

installed on adjacent structures and the highway. This should be agreed under the Party Wall Act and as part of any asset protection agreements required.

Appendix 1 Site Location and Exploratory Hole Plan

Figure 1 Site Location




Figure 2: Exploratory Hole Plan (over page)



1 Block Plan
Scale: 1:200




DSOTO ARCHITECTS 75 CANFIELD GARDENS LONDON NW6 3EA T: +44 020 7278 5100 EMAIL: info@dsoto.com


Job Title: Flat 2, 192 Goldhurst Terrace NW6

Drawing Title:	Date:	Drawn By:	Scale:
Block Plan	Feb 2022	DS169-02P	1/200@A3

Contractors must verify all dimensions on site before commencing any work. Do not scale from this drawing. The Copyright of this drawing is reserved. This drawing must not be disclosed without authority from **DSOTO**.




- Suspended timber floor
 - Solid floor
 - To be assessed
- TP Locations



No.	Date	Revision Notes
D.SOTO ARCHITECTS		
D.SOTO ARCHITECTS 71 CAMEFIELD GARDENS LONDON NW6 5JA Tel: 0203 591 5595 or 0203 591 5595 (toll free) Email: dsoto@dsoto.co.uk		
Project Title Flat 1, 192 Goddihurst Terrace London NW6		
Drawing Title	Ground Floor	88
Scale	May 2022	DS172A-100SK
1:50		
Corrections must only be made on the drawing after the drawing has been approved by the client. The drawing must be checked and approved by the client before any work is carried out. The drawing must be checked and approved by the client before any work is carried out. The drawing must be checked and approved by the client before any work is carried out.		


Appendix 2 Proposed Development Drawings




1 Block Plan
Scale: 1:200

D.SOTO ARCHITECTS 75 CANFIELD GARDENS LONDON NW6 3EA T: + 44 020 7278 5100 EMAIL: info@dsoto.com			
Job Title:	Ground Floor Flat, 192 Goldhurst Terrace NW6	Date:	July 2022
Drawing Title:	Block Plan	Drawn No:	DS172-A101P
		Scale:	1/200@A3
		Revision:	


Contractors must verify all dimensions on site before commencing any work. Do not scale from this drawing. The Copyright of this drawing is reserved. This drawing must not be disclosed without authority from **D.SOTO**.




2 Front Elevation
Scale: 1:100




3 Side Elevation
Scale: 1:100



1 Ground Floor
Scale: 1:100




4 Rear Elevation
Scale: 1:100




5 Side Elevation/Rear
Scale: 1:100


Revision Notes	
No.	Date
Revision Notes	
D'SOTO ARCHITECTS 75 CANFIELD GARDENS LONDON NW6 3JA T: 020 899 75100 F: 020 899 75101 EMAIL: INFO@DSOTO.COM	
Project Title	
Flat 1, 192 Goldhurst Terrace London NW6	
Drawing Title	
Drawing the Ground Floor and Elevations as Existing	
Date	July 2022
Drawn by	DS17Z-A103P
Scale	1:100
Sheet	1/1
Contractors must verify all dimensions on the before commencing any work. Do not scale from the drawing. The copyright of the drawing is reserved. This drawing shall not be released without written consent from DSOTO	



1 Section AA
Scale: 1/100



2 Section B-B
Scale: 1/100



3 Section C-C
Scale: 1/100

Revision Notes	
No.	Date








D'SOTO ARCHITECTS

D'SOTO ARCHITECTS 75 CANFIELD GARDENS LONDON NW6 3JA
T: 020 7312 5100 F: 020 7312 5100 EMAIL: INFO@DSO.AO

Project Title
**Flat 1, 192 Goldhurst Terrace
London NW6**

Drawing Title	
Sections	
88	
Existing	
Date	July 2022
Drawn by	DS17Z-A104P
Scale	1/100
Notes	

Contractors must verify all dimensions on site before commencing any work.
Do not scale from the drawing. The copyright of the drawing is reserved.
This drawing shall not be released without written consent from DSO.



No.	
Date	
Revision Address	

D'SOTO ARCHITECTS


D'SOTO ARCHITECTS 75 CANFIELD GARDENS LONDON NW6 3
 T: + 44 (0)20 7278 5300 F: + 44 (0)45 9677 8779 EMAIL: info@d'soto.com

Project Title
Flat 1, 192 Goldhurst Terrace
London NW6


Drawing Title
Ground Floor, Basement Elevations as Proposed

Date	July 2022	Drawing No.	DS172-105F
Scale	1:100	Revision	


Contractors must verify all dimensions on site before commencing any work. Do not scale from this drawing. The Copyright of this drawing is reserved. This drawing must not be disclosed without authority from DSR010.



1 Section A-A
Scale: 1:100



2 Section B-B
Scale: 1:100



3 Section C-C
Scale: 1:100

Revision Notes	
No.	Date

D'SOTO ARCHITECTS

D'SOTO ARCHITECTS 75 CANFIELD GARDENS LONDON NW6 5BA
t: 020 7317 5107 e: dsoto@dsoto.com dsoto.co.uk

Project Title
Flat 1, 192 Goldhurst Terrace
London NW6

Drawing Title	Sections
Date	July 2022
Scale	1:100
Drawn by	DS17Z-A106P
Checked by	DS17Z-A106P

Contractors must verify all dimensions on the before commencing any work.
Do not scale from the drawing. The copyright of the drawing is reserved.
This drawing shall not be released without written consent from DSOTO

UNIT 23 | CHILTERN TRADING ESTATE |
EARL HOWE ROAD | HIGH WYCOMBE | HP15 6QT
www.piledesigns.co.uk | 01494 216333



PILEDESIGNS

192 GOLDHURST TERRACE, LONDON NW6 3HN

CONSTRUCTION METHOD STATEMENT

22107_CMS



Document Control

Project:	192 Goldhurst Terrace
Site Address:	192 Goldhurst Terrace, London NW6 3HN
Document Title:	Construction Method Statement
Project No.	22107
Document produced for (Client):	DVP Structures/Piledesigns Ltd (internal use only)

Issue Register

Rev	Date	Issue Status / Description	Prepared By	Checked By
P0	15/07/2022	First Issue – For Planning	Val Pseneac MIStructE	Mike Johnson MIStructE CSSW

This document is prepared for the sole purpose / use by the client named above and is non-transferable to any other parties. No responsibility will be accepted where this submission is used, either in its entirety or in part, by any other party. This document is issued in commercial confidence and liability of Piledesigns Ltd in respect of the information contained is as per Piledesigns Ltd Terms & Conditions and will not extend to any third party.

Contents

1.0	Introduction	1
2.0	Existing Building Description.....	2
3.0	Proposed Works	3
4.0	Design Considerations	5
5.0	Water-Resisting Protection.....	7
6.0	Movement Monitoring and Control	9
7.0	Appendix 1	10
8.0	Appendix 2	11

1.0 Introduction

This report has been produced by DVP Structures in conjunction with Milvum Engineering Services Ltd and Piledesigns Ltd to summarise the structural and geotechnical aspects relating to the proposed basement redevelopment works at 192 Goldhurst Terrace, London NW6 3HN (hereafter referred to as the site); and to provide an overview of the new basement construction methodology and sequence.

It is noted that this document is only intended to be used for planning purposes. It should not be used for costing, procurement or construction purposes.

2.0 Existing Building Description

The existing property is a 3-storey end-of-terrace which benefits from a loft conversion and single storey extensions to the rear.

The site is bound by Goldhurst Terrace to the south; and neighbouring gardens and properties to the north, south and west.

It is noted that no. 192 and no. 190 Goldhurst Terrace share a party wall. It is understood that the owners of 190 also have the intention of constructing a single storey basement.

No. 192 has been constructed using traditional materials and techniques. The external walls are largely of loadbearing solid masonry of varying thickness (215-330mm) depending on location. Cavity wall construction has been used with the rear single storey extensions.

The ground floor structure primarily comprises suspended timber joists; there are limited areas which appear to comprise either a ground-bearing or suspended solid floor.

The upper floors construction comprise suspended timber joists with boarding on top.

The mansard roof is anticipated to comprise a combination of timber and steel construction, which transfer the loads down to internal and perimeter loadbearing masonry walls.

A site specific ground investigation has been undertaken. As part of the investigation, trial pits were dug at several locations to expose the existing foundations and establish the ground conditions. Boreholes previously sunk in the neighbouring site (i.e. 190 Goldhurst Terrace) have also been reviewed as part of the geotechnical assessment. Refer to Sections 6.0 and 7.0 of the main body of the BIA report for geotechnical information.

The trial pits confirmed that the existing wall foundations comprised either concrete strip footings or corbelled brick footings on concrete strip footings. The founding level varied between 950mm to 1,100mm bgl on-site.

3.0 Proposed Works

The redevelopment works include the construction of a single storey basement with lightwells to the front and rear elevation (Refer to the architect's dwgs; and Appendix 2 for structural dwgs)

Some internal remodelling is also proposed at ground level. The basement is proposed to be accessed via a set of stairs located to the west and set of steps to the rear, leading to the garden.

The level (SSL) of the new basement slab is proposed to be c. 3.0m below the existing ground level, whilst the basement formation level is anticipated to be no deeper than 3.5m bgl.

The basement walls are to be formed using reinforced concrete (RC) underpinning constructed in a non-consecutive sequence (i.e. traditional "hit and miss" sequence).

The basement slab is to be formed using RC construction. In addition to resisting vertical permanent and variable actions, the slab will act as a permanent prop to the basement walls.

The RC basement walls will be designed to resist the lateral forces arising from surcharge loadings, hydrostatic pressure and soil pressure. It is noted that the RC underpins will be dowelled in the existing perimeter wall foundations such that a robust shear connection is obtained.

The ground floor structure is to be modified such it comprises a grillage of steel beams with infill engineered timber joists. Steel beams will be provided to support any internal load-bearing masonry walls. The steel beams will be supported by the perimeter basement walls and several internal steel columns.

The ground floor structure is to be designed as a stiff diaphragm such that it can provide an effective propping force to the top of the basement walls. Therefore, the basement walls will be designed as propped at ground and basement levels.

The internal walls at basement level are generally anticipated to be of lightweight construction. However, masonry walls built off the basement slab may be required by the Architect at specific locations (e.g. around the stairwell).

Extensive temporary works, in addition to those required for the basement excavation, will be required to enable the construction of the ground floor. Appendix 1 presents indicatively an option for temporary works; which could enable the installation of steel beam to the underside of existing internal masonry walls at ground level. It is noted that these will be agreed on and designed in conjunction with the appointed contractor at a later date.

The lateral movement due to excavation and other basement construction works, will be minimised by adopting high stiffness temporary propping (refer to Appendix 1 for the proposed construction sequence).

A Ground Movement Assessment (GMA- see Section 9.0 of the BIA Report) has been undertaken to estimate likely movements during basement construction. The results indicate that horizontal and vertical movements in the region of 5 to 7 mm are anticipated during construction.

A movement monitoring regime will be implemented in order to monitor displacement during construction and limit any neighbouring building damage to Category 1 on the Burland Scale.

It is anticipated that partial backfilling will be undertaken as the RC underpinning works are completed in a non-consecutive sequence. Once the RC underpins are fully constructed, basement excavation can be undertaken, with the temporary propping in place.

Two levels of temporary propping (steel props and waling beams) are proposed to be installed during construction. The first level of propping will be set out below the level of the ground floor slab; the second level of propping will be installed above the basement RC slab level (c. 500-750mm above SSL).

The lightwells are to comprise RC retaining walls constructed in a “hit and miss” sequence, similar to the main basement wall construction. In the temporary condition, propping is to be adopted throughout; whilst in the permanent condition the wall will span horizontally between the returns and cantilever off the stem base.

Reference can be made to Appendix 1 for a diagrammatic construction sequence of a typical RC underpin and temporary works typically employed with such construction; as well as possible temporary works associated with steel beam installation to support existing internal loadbearing walls at ground level.

Reference can be made to Appendix 2 for drawings outlining the indicative basement layout and sequence of underpinning; and basement construction sequence.

4.0 Design Considerations

This chapter outlines the loading requirements which will need to be accounted for as part of the structural design of the basement.

The design and relevant loadings are generally established in line with the relevant Eurocode design standard, including:

- BS EN 1990 Basis of Design
- BS EN 1991 Actions on Structures
- BS EN 1992 Design of Concrete Structures
- BS EN 1993 Design of Steel Structures
- BS EN 1997 Geotechnical Design

The retaining wall and slabs will have to be designed giving consideration to the following forces (variable and permanent actions):

- Soil Pressure
- Surcharge Loading
- Hydrostatic Pressure
- Heave Forces
- Dead, superimposed and imposed loads on ground and basement slabs
- Dead, superimposed and imposed loads acting on the main house (applies to the underpins)

The basement slab will require design verification taking into account likely heave and hydrostatic pressures. Approximate calculations have been undertaken to determine likely forces acting on the basement slab below.

For the purposes of concept design, the level of the ground water table has been taken as 1.0m below ground level, resulting in an approximate hydrostatic pressure of 25kN/m² (c. 2.5m hydrostatic head).

London Clay formation has been assumed for the purposes of heave pressure estimate. The excavation of the basement could potentially result in a total maximum soil pressure of 61kN/m² (3.2m of soil @ 19kN/m³; assumed 300mm void below the existing suspended ground floor). It can be assumed that 50% of the soil pressure dissipates upon excavation, thus resulting in a potential long term soil pressure of 30.5kN/m².

Assuming that heave protection measures are not considered, the pressure on the basement slab may be expressed as an equation whereby:

$$\text{Slab pressure} = \text{water pressure} + \text{soil heave pressure} - \text{any pressure dissipated during slab deflection}$$

Given that the soil pressure exceeds the water pressure, the pressure dissipated equates to the water pressure plus a proportion of the excess heave pressure; the latter is dependent on the slab deflection.

It is noted that the slab deflection is a function of stiffness, with more flexible slabs allowing for more pressure dissipation compared to stiffer slabs.

Allowing for a relatively stiff slab, an “f” factor accounting for dissipation due deflection of 0.3 can be taken.

Assuming a soil pressure of 30.5kN/m², a hydrostatic pressure of 25kN/m² and a coefficient of slab stiffness of 0.3, the characteristic total pressure acting upwards on the basement slab will be approximately:

$$\text{Slab Pressure} = 30.5 + 25 - (25 + 0.3 * 5.5) = 28.9 \text{ kN/m}^2$$

The retaining wall design will need to give consideration to both lateral and vertical forces. The lateral forces arise from surcharge loads, soil and hydrostatic pressure; the vertical loads arise from the shear forces transferred by the ground floor slab and the vertical forces coming down the perimeter main house walls.

For the calculation of the soil pressure acting on the earth face, active pressure coefficients are appropriate for use.

With regards to the surcharge loadings, it is likely that a value of 2.5kPa - 5kPa will be used for retaining wall verification; considering the distance to the nearest structures and highway. Active pressure coefficients will be used to derive the lateral pressure acting on the wall from the vertical stresses acting at ground level.

Whilst a large proportion of the basement slab will contribute to the load transfer into the ground, it is anticipated that the RC underpin stem base will distribute most of the loads transferred from above. The ground bearing stresses will be limited to 100kPa, as advised by the geotechnical assessment report.

5.0 Water-Resisting Protection

The proposed basement will offer habitable space for the building occupants and is thus is considered to be grade 3 in accordance with BS 8102: Code of Practice for Protection of Structures Against Water from the Ground.

It is assumed that a dry environment with no leakage permitted (Tightness Class 3 in accordance with BS EN 1992-3) will be required for the project; and suitable waterproofing measures will need to be employed to achieve high levels of protection.

Three methods of protection against water ingress are typically considered for basement design (see Table 1 below and Figs. 1 to 3):

Table 1: Basement Waterproofing – Methods of Protection as per BS 8102

Type	Method of Protection	Operation
A	Barrier	A membrane is used to keep water physically outside the usable space
B	Structurally Integral	The basement walls and slabs are designed to specific crack width and/or special additives are used to obtain waterproof concrete
C	Drained Cavity	An inner cavity membrane lines the basement wall and slab; any water penetrating the wall and slab is directed behind the cavity membrane into a drainage channel and a sump chamber where water is removed by a pump.




Fig. 1 – Barrier Protection Waterproofing Options




Fig. 2 – Structurally Integral Waterproofing




Fig. 3 – Drained Cavity

Types A and B measures are often combined to achieve high levels of waterproofing resistance; Type C is also common with habitable basements.

The final waterproofing strategy will be decided collectively by the design team, client and a specialist waterproofing contractor. At this stage, it is assumed that a combination of structurally integral protection (RC wall/slab designed to 0.2-0.3mm crack width and/or adoption of water resistant concrete) and a drained cavity system will be implemented for this basement.

6.0 Movement Monitoring and Control

A competent contractor experienced with this type of works will be appointed to undertake the works. Early input from the contractor will be required in order to establish the optimal sequence of construction and co-ordination of temporary works.

Two levels of stiff temporary propping will be employed during the construction of the basement. The propping system is anticipated to comprise a waling beam (steel UB or UC sections) running horizontally along the basement walls. Props, consisting of proprietary sections or UC/UB steel elements, are to be installed such that these run the full width of the basement; and act in compression to resist the horizontal actions on the wall.

A movement monitoring regime with a traffic light system (“green” – no action; “amber” – increase frequency of readings and notify relevant parties; and “red” – implement agreed measures and/or stop work) will be employed during construction. The aim of the monitoring will be to establish the amount of vertical and horizontal structural movement such that any structural damage recorded can be no worse than Category 1.

Movement trigger levels are to be agreed with the Party Wall Surveyors and implemented accordingly.

Assuming high standards of workmanship, close co-ordination between the temporary and permanent works engineer and the correct implementation of movement monitoring, minimal ground and structural movement is anticipated during construction




PILEDESIGNS



Construction Method Statement
192 Goldhurst Terrace/22107

7.0 Appendix 1

Diagram of a typical RC Underpin Construction; Indicative Temporary Works



Proposed Basement Plan
1 : 50

**Proposed Ground Floor Showing
Basement Under**
1 : 50

NOTES

1. DO NOT SCALE THE DRAWING OR PRINT OR ELECTRONICALLY WORK FROM PLOTTED DIMENSIONS
2. NO DEVIATION FROM THE DETAILS ON THIS DRAWING IS ALLOWED WITHOUT THE WRITTEN PERMISSION OF THE DESIGNER
3. READ THE DRAWING WITH ALL ARCHITECT'S, SERVICE ENGINEERS AND DVP STRUCTURES RELEVANT DETAILS AND SPECIFICATIONS
4. ALL DIMENSIONS TO BE IN ACCORDANCE WITH THE RELEVANT SPECIFICATIONS ISSUED BY THE APPROPRIATE AUTHORITIES AND THE CONTRACT DOCUMENTS
5. **LOADINGS** - EXISTING LOADINGS OR EXISTING LOADINGS TO BE APPLIED, ETC.
6. **CONSTRUCTION** - RELEVANT INSTRUCTIONS FOR CONSTRUCTION TO BE APPLIED, ETC.
7. **REVISIONS** - RELEVANT INSTRUCTIONS FOR REVISIONS TO BE APPLIED, ETC.
8. REFER TO GENERAL NOTES DRAWINGS FOR MATERIAL SPECIFICATIONS AND NOTES

Construction Details & Materials

Standard Hazards:

We have assumed that competent contractors will be engaged with this project and that they will be aware of the hazards and how to deal with such hazards safely. Our drawings are intended to be used by a competent contractor or known to the designer.

(Residual risks to be added)


Key	
	Existing Structure
	Structure to be demolished
	Steelwork
	Reinforced Concrete
	Demolish R.C. underground bearing pile

Note:
This drawing has been prepared for planning purposes only


**not for
construction**




Client: Owner	
Project: Flat 1, 182 Godthrust Terrace, London NW6 3HN	
Title: Proposed Basement Plan	
Drawn by: M.A.V.	Checked by: V.P.
Scale: 1:50	As indicated
Drawn by: 22107	Drawn by: 001
Drawn by: 22107	Drawn by: 001
© DVP Structures Ltd. All rights reserved. No part of this publication may be reproduced without prior written permission from DVP Structures Ltd.	




3D View 1



3D View 2



3D View 3



3D View 4

NOTES

1. DO NOT SCALE THE DRAWING OR PRINT OR ELECTRONICALLY WORK FROM IT. DIMENSIONS SHALL BE TAKEN FROM THE DRAWING.
2. NO DEVIATION FROM THE DETAILS ON THIS DRAWING IS ALLOWED WITHOUT THE STRUCTURES ENGINEER'S APPROVAL.
3. READ THIS DRAWING WITH ALL ARCHITECT'S, SERVICE ENGINEERS AND DVP STRUCTURES RELEVANT DETAILS AND DRAWINGS.
4. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE RELEVANT SPECIFICATIONS ISSUED BY DVP, STATUTORY REQUIREMENTS AND THE CONTRACT DOCUMENTS.
5. EXCLUDED DETAILS:
 - P. RETAINMENT - EXISTING DRAWINGS OR SPECIFICATIONS.
 - C. CONSTRUCTION - REFER TO OTHER DRAWINGS FOR CONSTRUCTION DETAILS AND SPECIFICATIONS.
 - 6. REFER TO GENERAL NOTES DRAWINGS FOR MATERIAL SPECIFICATIONS AND NOTES.

REV	DATE	DESCRIPTION	BY
1	15/03/23	FOR APPROVAL	VP

not for
construction

PILEDESIGNS
GEOTECHNICAL EXPERTISE

dvp
structures







Client: Owner

Project: Flat 1, 182 Godthrust Terrace,
London NW6 3HN

Title: 3D Views Sheet 1

Drawn by	Checked by	Scale	Drawn by
M.A.	V.P.	1:1	VP
Project	Drawn by	Drawn by	Drawn by
22107	D	080	PI

© DVP Structures Ltd. Check all dimensions and verify on site.
Approved for construction by DVP Structures Ltd.



Note: Lightwall construction sequence not included. However, these are to be constructed using the methodology employed for the main basement.

Note: This drawing has been prepared for planning purposes only

[illegible]




PILEDESIGNS



Construction Method Statement
192 Goldhurst Terrace/22107


8.0 Appendix 2

Preliminary Structural Drawings




1. Excavation must be fully supported by props and shoring.
2. Edge protection to prevent falls into the excavation must be installed.
3. A temporary vertical prop or support may be placed under the wall to keep any loose bricks or masonry in place.
4. The main load from the existing wall will span onto the wall and foundations on either side of the excavation.

Stage 1. Excavation




1. Reinforcement is fixed into position.
2. Reinforcement details are given in the engineering design. It is critical that the reinforcement is installed as detailed in the design.
3. The design will usually require a shear connection between adjacent underpins. This is generally achieved using dowel bars between adjacent pins or by building shear keys in the concrete underpin walls.

Stage 2. Reinforcement



1. Concrete is placed in the toe first.
2. Once the toe is sufficiently cured the concrete wall is poured.
3. Shuttering, usually timber, is used to hold the concrete for the wall in place while it is placed.
4. Gap of approximately 75mm left between the top of the concrete and the underside of the existing foundation.


Stage 3. Concrete placement



1. After a minimum of 24 hours dry-pack is rammed into the 75mm void that has been left above the new underpin.
2. Dry-pack is a mix of sharp sand and cement. It is easy to handle and has a low shrink volume, minimising settlement of the wall onto the new underpin foundation.
3. The completed underpin must be supported horizontally either by horizontal propping or by backfilling the excavation until the ground slab and possibly other permanent works are constructed.

Stage 4. Dry packing

Typical underpin construction sequence



Indicative temporary works that allow the installation of steel beams to the underside of existing internal loadbearing walls at ground level

P1	16.07.22	Preliminary	VP
Rev	Date	Description	Issued

**not for
construction**



	Client	Owner
Flat 1, 192 Goldhurst Terrace, London NW6 3HN		
Project Indicative Temporary Works Options		
Drawn by M.A.	Prepared by V.P.	Scale 1 : 1
Pwg No. 22107	Date Type SK	Dwg No. 01
		Sheet Size A1
		Rev P1

© Dwyer Structures LTD Check all dimensions and notes are taken from drawings before construction