


PLANNING

KEY

- Existing structure, walls & other building fabric to be retained, made good and redecorated, unless otherwise noted
- New structure & walls
- New building elements

Schedule of Works Key:	
to be read in conjunction with schedule 383(SL) Listed Building Consent Schedule of Works, section 02, page 107	
01	02.107.01 - Existing dormer roofs to be repaired and refurbished as required
02	02.107.02 - Existing dormer roofs to be repaired and refurbished as required
03	02.107.03 - New mechanical fresh air supply duct to be installed up to roof level to serve ground and lower ground floor accommodation
04	02.107.04 - New mechanical kitchen extract duct to be installed up to roof level to serve ground and lower ground floor retail units
05	02.107.05 - Existing external fire escape stair to be retained, refurbished and redecorated
06	02.107.06 - New external plant installed at 7th floor level comprising metal grate flooring on raised steel frame structure to structural engineer specification
07	02.107.07 - Existing lift motor room to 21 Southampton Row to be retained
08	02.107.08 - Existing flat roof to 21 Southampton Row to be refurbished with new insulation and waterproofing, applied to new plywood deck sitting on top of existing retained timber joists / steel beams below
09	02.107.09 - New key clamp handrail to perimeter of new plant deck
10	02.107.10 - New insulated flat roof to Vernon / Sicilian House lift motor rooms
11	02.107.11 - New external mechanical ductwork to pass through lift motor room
12	02.107.12 - New maintenance stair to roof level in existing lift over run enclosure
13	02.107.13 - New brick roof-top riser cowl to be constructed at head of new riser
14	02.107.14 - Photovoltaic panels according M&E specification



All dimensions to be checked on site prior to commencement of any works, and/or preparation of any shop drawings.
 Sizes and dimensions to any structural or services elements are indicative only. See structural and service engineers drawings for actual sizes / dimensions.
 This drawing to be read in conjunction with all other Architect's drawings, specifications and other Consultants' information.
 All proprietary systems shown on this drawing are to be installed strictly in accordance with the Manufacturers/Suppliers recommended details.
 Any discrepancies between information shown on this drawing and any other contract information or manufacturers/suppliers recommendations is to be brought to the attention of the Architect.

Revision	Date	Amendment
PL-1	22/07/2022	Issued for Planning

Date	April 2022	Project	Vernon, Sicilian Hse/21 Southampton Row	Job Ref.	383
Scale	1:100 @A1	Drawn	HT	Check	AY
Status	PLANNING	Client Ref	383 (GA) 107	Drwg. no.	383 (GA) 107
Hale Brown Architects Ltd. Unit 1.04, Edinburgh House, 170 Kennington Lane, London, SE11 5DP		T: 020 3735 7442		E: mail@halebrown.com W: www.halebrown.com	

halebrown
architects