


Tank manufactured to tolerance of ± 10 mm on all dimensions.

Drawing to be ALL DIMENSIONS IN mm Rev. Rev. Rev. Rev. Rev. altered only by NHP DO NOT SCALE - IF IN DOUBT ASK This is the property of New Haden Pumps Ltd. and must not be passed on to any person not authorised by New Haden Pumps Ltd. or be copied or otherwise utilized by anybody without New Haden Pumps Ltd. expressed written permission.



NOTES:

- 1. Effective sump capacity to equal one minute of pump output minimum.
- 2. Float switches to be positioned away from obstructions and in area of least disturbance.
- 3. Cable ducts to be 100 nb min, complete with draw rope, direct route to panel location avoiding sharp bends.
- 4. All civil engineering by main contractor.
- 5. Reinforcing bars in concrete to be kept at least 75mm away from access opening in the vicinity of the top guide-rail bracket fixing holes.

NEW HADEN PUMPS PUMPING SOLUTIONS



Typical arrangement of Horizontal GRP Tank

Pump Type: For:

Client .				
Scale 1:25		Original Size A2	19.01.2009 Date	R/ Drawn
Drg.No. M	DXXXXXX—XX	She	eet 1 of	1