

					16 Noel Street Lo
					T : 0207 734 4466
P1	FIRST ISSUE FOR REVIEW	JPF	тс	09.06.22	W: http://www.mo
Rev	Revision	Ву	Ckd	Date	

GENERAL NOTES:

- 1. Refurbished external door
- 2. Existing lift refurbished
- 3. All doors to be retained and redecorated. Where appropriate and in accordance with fire consultant specification treat with envirograf fire coating.
- 4. New kitchenette
- 5. New electric radiators as indicated
- 6. New slate effect hearth
- 7. Existing stairs refurbished with new carpet.
- 8. Areas of damaged lath and plaster repaired, re-plastered and redecorated.
- Existing damaged and missing suspended ceiling to be carefully removed and replaced
- 10. All existing windows to be refurbished and to receive new ironmongery
- Existing WCs fully refurbished with new sanitary wear and finishes
- Any existing damaged or missing areas of plasterboard with skim finish repaired and redecorated
- Existing cast iron fireplace and wood surround retained and refurbished. Existing decorated wood surround stripped back and redecorated
- 14. New downlights in basement
- 15. Existing fireplace hearth and surround retained. Existing decorated surround stripped back and redecorated
- 16. All existing window boards and reveals retained, stripped back and redecorated
- 17. Existing stone surrounds retained and cleaned
- 18. Existing painted balustrade redecorated
- 19. New stair tread installed to match existing stairs
- 20. Existing stairs walls repaired ready for redecoration
- All existing wall and ceiling lights to be replaced. Existing locations to be utilised to avoid further intervention with historic building fabric.
- 22. All existing trunking and conduits to be retained
- 23. All previously infilled openings between 17 and 18 are to be reviewed and upgraded to provide 60min fire separation between buildings, from the no.18 side, to be confirmed by building control
- 24. All ceiling rose to be retained and redecorated
- All mouldings, skirtings, dado railing and paneling to be repainted and made good where damaged.
- 26. All areas of water ingress/damp to be properly inspected and repaired.
- 27. Replace All FCU's in existing locations.
- 28. Existing window and door to be fitted with automatic opener as AOV

- Intercom Access Control provided to primary entrance doors.

-New and smaller boxing/cabinetry to be provided. Rfert to finishes document for design intent to new housings.

All windows to receive new ironmongery as per finishes document.

- Proposed new hearth and fire grate required. Hearth to be as per finishes document.

	FOR PLANNING							
Client Hogarth Properties (Rothschild)	™ GROUND FLOOR GENERAL ARRANGEMENT							
Project PROJECT 04	Scale 1:50 @ A1	Date NOV.21	Designer/Drawn By TC / JPF	Checked E TC	3y / Date			
18 & 19 SOUTHAMPTON PLACE	Drawing Number							
	Project No.	Floor	Drawing No.		Rev			
	ML3953	00	706	F	21			

- Intercom Access Control provided to primary entrance doors.