

REPORT FOR LBC - ROOF STRUCTURE

Project name	4-6 Bedford Place, London		
Design note title	Structural Statement in Support of Listed Building Consent – Existing Roof		
Document reference	24973_BP_HYD_XX_RP_S_001		
Author	Jerry King (Director) MStructE, B.Eng (Hons) C.Eng		
Revision	P3		
Checked	Roger Bareham MICE MStructE, B.Eng (Hons) C.Eng (CARES registered engineer)		
Date	27th September 2022	Approved	✓

Introduction

Hydrock have been engaged by SAV Group Ltd as part of a wider design team, to undertake a survey of the existing roof structure at the above former hotel property in Bloomsbury with a view to;

- Assessing its current condition and safety
- Providing proposals for strengthening where the existing structure is shown to be inadequate for the current loadings
- Design of refurbishment works taking due consideration of all sensitive heritage fabric, its legibility and reversibility as far as possible

The building is grade 2 listed and is believed to date from the early 19th century. It consists of 3 former Georgian terraced houses constructed in traditional timber and masonry in a regular arrangement for that period. The buildings have been adapted and linked to form a 36-bed hotel that was last used in March 2020.

Description of Roof Structure

Minimal opening up works as shown in Appendix C have been carried out in order to understand the structure and its condition. These have been undertaken in as few locations as necessary and are reversible.

Hydrock inspected the opening up works and roof structure on 29th July and 8th August 2022.

The form of the structure is described on the enclosed sketch SK-S-104 and consists of;

- 100*50 Softwood rafters (at varying centres but typically 350mm average) spanning approximately 3.5m from the party walls onto a central valley beam
- Hip members to form the roof fall down to the front and rear gutter lines
- 160 wide x 250 deep valley beams located on the centre-line of each building - probably intended to span from front/rear walls onto the stair walls

Please note;

- We have assumed the valley beam is of good grade softwood for the purposes of this report and would highlight that it is suffering from wet rot in at least 2 locations above number 4 Bedford Place. In addition, the beam above 6 Bedford Place has been strengthened for part of its length with a modern 180x75PFC which possibly infers further decay somewhere along that particular member.

- The valleys collect all of the rainwater from the roofs before discharging down onto the flat roof above the main staircases. Both areas are prone to water ingress and we anticipate further extent of wet rot to the existing valley beams when fully opened-up.
- The valley-beams are partially aligned with timber stud partitions for part of their length although the head detail does not infer that continuous support is provided.
- The valley beam takes support at the stair walls but also appears to bear onto the modern stud corridor wall within number 6.
- A 15mm-20mm thick asphalt layer has been laid across the slate roof which represents a significant additional roof load that has been in place for a number of years across all three roofs
- There is localised strengthening to the rafters at the rear of number 4 with modern softwood rafters installed alongside the original timbers

Structural capacity of existing timber elements

Our calculations have shown that;

- The rafters are undersized for the current loading condition and are showing signs of significant deflection on a number of the roof planes. This potentially compromises the safety of the roof and the existing heritage features immediately below.
- Even with the asphalt removed the calculated deflection is 24mm which is greater than 2x the acceptable deflection according to modern building standards (and hence could cause disturbance of heritage features at lower levels).
- The valley beams are undersized for the larger span for both the current and original load condition. This manifests as further deflection onto the both new and original partitions below creating unintended load paths down through the rest of the building

Conclusions and Recommendations

The current situation is unsafe given the identified overstress and the lengths of decayed timber (both identified and expected in other locations) within the valley beams.

We would recommend the following course of action to protect and strengthen the original structure in-situ;

- Install temporary roof and complete soft strip works to expose full length of valley-beams
- Temporary prop valley beam to enable strengthening works
- Carefully remove asphalt, slates and sarking boards (safely storing any slates that can be reclaimed)
- Repair sections of decayed valley beam using a Rotafix based detail, refer to enclosed sketch SK-S-106, with the following method tbc by manufacturer and full extent of timber decay following soft strip works:
 - » Remove section of decayed timber
 - » Splice with new timber section
 - » Form slot to allow for Rotafix TRS stainless steel rebar rods and apply Rotafix P8 paste for the full extent of the new timber section and existing timber section either side to suit actual site conditions.

REPORT FOR LBC - ROOF STRUCTURE



- Cut existing valley beam to enable insertion of new trimming beam
- Install padstones as per enclosed sketch SK-S-106 to take strengthened valley beams and trimmer beams
- Install trimming beams to relieve load from unintended load-paths as per enclosed sketches SK-S-105 and SK-S-106.
- Install strengthening channels either side of valley beams as shown on enclosed sketches SK-S-105 and SK-S-106.
- Remove temporary propping
- Install new rafters and ceiling joists alongside existing rafters
- Replace roof build-up as per architectural proposals
- Remove temporary roof

This scope of works represents the minimum intervention that is required to make the roofs safe.

REPORT FOR LBC - ROOF STRUCTURE




Appendix 1; photographs



Photos 1- 4; No.6 Bedford Place – showing valley-beam and localised valley beam strengthening



Photos 5; typical flat roof and roof-light feature at 3rd floor level
Photo 6; typical sagging roof due to overstress of original rafters
Photos 7 and 8; asphalt covering across slates




Photos 9; hip beam and rafter arrangement


Photo 10; rear gutter showing hip on adjacent roof

Photo 11; party wall chimneys - typical arrangement

Photo 12; view showing cut-out for 3rd floor flat roof (note all rainwater drains into this section of roof)



Photos 13; modern (inadequate) sw rafter strengthening and ceiling hanger
Photo 14; wet-rot decay of valley beam above number 4 Bedford Place
Photo 15 and 16; adjacent roof-light showing source of water ingress








Photos 17-19; various additions typical of all 3 flat-roof areas
Photo 20; 4 Bedford Place valley beam showing rafter relationship

REPORT FOR LBC - ROOF STRUCTURE





Appendix 2; sketches SK-S-104 and SK-S-106

Legend








	- Solid Masonry Load Bearing Wall
	- Modern stud partition wall (50x100 studs @ 400 c/c typ.)
	- Lath and plaster timber stud partition wall (55x90 studs @ 400 c/c typ.)
	- 50x100 rafters @ 350 c/c typ.
	- Valley beam support locations

181780 N

Drawn: ML
Job: 4-6 Bedford Place
Title: Roof Mark-up
Sketch No.: SK-S-104-P1
Date: 18/08/22



Abbreviations			
AB	Air Brick	I/R	Iron Railings
AV	Air Valve	JB	Joint Box
BB	Belisha Beacon	KO	Kebs
BG	Break Glass Point	LB	Liter Bin
BK	BK	LP	Lamp Post
BO	Bolard	LP	Light Well
BS	Bus Stop	MH	Manhole
BT	British Telecom cover	MK	Marker
C	C Floor to Cill height	MT	Motor
CB	Close Board	MS	Misc
CL	Cover Level	OH	Overhead
CL	Chain Link	PM	Parking Meter
CO	Column	PP	Post Box
CONC	Concrete	P/R	Post & Rail
CP	Catch Pit	PT	Pot
CPL	Cable	PS	Post & Wire
CPS	Cable Paving Slabs	RE	Rodding Eye
CTV	Cable Television Cover	RET	Retaining
DK	Drop Kerb	RSS	Road Sign
DH	Door Height	RSS	Rollfed Steel Stansion
EP	Electricity Pole	RSS	Rollfed Steel Joist
FB	Flow Board	RSP	Road Water Pipe
FC	Flower Bed	SCP	Stop Cock
FB	False Ceiling	SV	Soft Vent Pipe
FR	Flag	TB	Telephone Box
FR	Fire Hydrant	TBM	Trench, Bench Mark
FHR	Fire Hose Reel	TP	Telegraph Pole
FL	Flag Level	TL	Traffic Light
FP	Flag Pole	Tk	Tank
GP	Gate Post	UTL	Unable To Lift
GU	Gully	V	Vent
GV	Gully Vent	V	Vent Pipe
H	Cill to Head height	WM	Water Meter
HT	Height	WP	Waste Pipe
IC	Inspection Cover	WSC	Water Stop Cock
IL	Invert Level	WW	Water Valve

Notes		
Ceiling Height	3050	Arch 
Level	+20.00	Radiator 
Floor Level	+20.00 FL	Station 
Ceiling Level	+20.00 CL	Hedge 
Soffit Level	+20.00 SL	Steep slope 
False Ceiling Level	+20.00 FCL	
Floor to cill height	c-1234	Fence 
Cill to head height	h-1234	Foul pipe 
Door height	DH 2000	Storm pipe 

Survey Coordinates and Grid

Please note that the grid shown on this drawing is as follows;

- ☐ Arbitrary
- ☐ Arbitrary but related to building line
- ☐ Arbitrary but approx. related to North
- ☐ Best fit to an Ordnance Survey Digital Sheet
- ☒ Related to the Ordnance Survey National Grid

Levels

Please note that the levels shown on this drawing are as follows;

- ☐ Arbitrary and related to a temporary bench mark
- ☐ Related to an Ordnance Survey Bench Mark
- ☒ Related to the Ordnance Survey National GPS Network

Level positions are indicated by a cross or the decimal point

Bench Mark	
Type	Ordinance Survey
Position	N/A
Value	N/A


Trees

All trees sizes are approximate and should be checked on site before using information. Where guaranteed tree species become important the services of a tree expert should be employed

Notation : diameter of trunk / Height / Spread

Drainage

Where drainage covers have been lifted data has been recorded for each individual manhole from the surface and connections to other manholes, pipes or gullies are assumed. Where information is required by accessing the manhole or tracing to other manholes then a services trace will be needed.

[illegible]


Client
Dexter Moren Associates

Project
4-6 Bedford Place
London
WC1B 5JD

Drawing Title

Third Floor Plan

Sheet/Scale A1@1:100	Date 16/06/22	Drawn P.R.	Checked C.S.D.
Project No. 13643	Drawing No. 05	Preliminary	Revision



Notes:

1. REFER TO HYDROCK REPORT 24973_BP_HYD_RP_S_001 FOR FURTHER INFORMATION

***** - INDICATES TEMPORARY PROPPING REQUIRED TO SUPPORT EXISTING ROOF STRUCTURES DURING VALLEY BEAM STRENGTHENING WORKS TO CONTRACTOR DESIGN

- DENOTES AREA AFFECTED BY WET ROT, SHOWN INDICATIVELY

- DENOTES EXISTING LOAD BEARING WALL

P02	27.09.22	STEEL BEAM POSITION UPDATED	FB	ML
P01	05.09.22	PRELIMINARY ISSUE	FB	ML
Rev	Date	Description	By	Ckd

Hydrock

Merchants' House North
Wapping Road
Bristol BS1 4RW
t: +44(0)117 945 9225
e: bristolcentral@hydrock.com
or visit www.hydrock.com

Client

SAV GROUP

Project

**4-6 BEDFORD PLACE,
LONDON**

Title

**ROOF STRENGTHENING
DETAILS**

Drawing Status

PRELIMINARY

Job No.

24973

Drawn	Checked	Scale at A3	Date	Issue Date
FB	ML	1:10	01.09.22	27.09.22

Drawing No.

BPL-HYD-XX-03-SK-S-106


Revision

P02

REPORT FOR LBC - ROOF STRUCTURE



Appendix C; Proposed opening-up works



GENERAL KEY

- AREAS NOT ACCESSED/OUTSIDE OF SCOPE
- TEXT APPROXIMATE LOCATION OF ASBESTOS SAMPLES
- TEXT APPROXIMATE LOCATION OF NON ASBESTOS SAMPLES

DETAIL KEY

- APPROXIMATE LOCATION OF ASBESTOS CONTAINING MATERIALS



32 Writtle Road
Chelmsford
Essex
CM1 3BX
Phone: 01245 690606

CLIENT

Sav Development Ltd

This drawing must be viewed and read in conjunction with the Asbestos Survey Report for:

PROPERTY TITLE
4-6 Bedford Place
London

Ref. No.	J025269	DRAWN DATED	10 Jun 2022
Nos.	1/5	UPDATED	10 Jun 2022

BASEMENT.


SK.01.

26.07.22.

■ TP1 → TP4 : Trial pits to determine exg. slab thickness + foundation detail/depth adjacent to the party walls.

— C1 → C4 : core drill to determine wall thickness and make-up (solid brick expected but TBC)

HYDROCK INVESTIGATION REQUIREMENTS



☐ F1 → F4; open-up flooring to establish joist sizes, centres and condition.

— CS → C6; core-drill to determine wall thickness and make-up (solid brick expected TBC).

GENERAL KEY

- AREAS NOT ACCESSED/OUTSIDE OF SCOPE
- TEXT** APPROXIMATE LOCATION OF ASBESTOS SAMPLES
- TEXT** APPROXIMATE LOCATION OF NON ASBESTOS SAMPLES

DETAIL KEY

- APPROXIMATE LOCATION OF ASBESTOS CONTAINING MATERIALS



32 Writtle Road
Chelmsford
Essex
CM1 3BX
Phone: 01245 690606

CLIENT

Sav Development Ltd

This drawing must be viewed and read in conjunction with the Asbestos Survey Report for:


PROPERTY TITLE
4-6 Bedford Place
London

Ref. No.	DRAWN DATED	
J025269		10 Jun 2022
Nos.	UPDATED	
2/5		10 Jun 2022

GROUND FLOOR

SK.02

HYDROCK INVESTIGATION REQUIREMENTS 26.07.22



☐ F6 → F12; open-up flooring to establish joist sizes, span/direction, centres and condition.

— C7 → C8; core drill to determine wall thickness and make-up. (solid brick expected TBC)

GENERAL KEY

- AREAS NOT ACCESSED/OUTSIDE OF SCOPE
- TEXT APPROXIMATE LOCATION OF ASBESTOS SAMPLES
- TEXT APPROXIMATE LOCATION OF NON ASBESTOS SAMPLES

DETAIL KEY

- APPROXIMATE LOCATION OF ASBESTOS CONTAINING MATERIALS



32 Writtle Road
Chelmsford
Essex
CM1 3BX
Phone: 01245 690606

CLIENT

Sav Development Ltd

This drawing must be viewed and read in conjunction with the Asbestos Survey Report for:


PROPERTY TITLE
4-6 Bedford Place
London

Ref. No.	DRAWN DATED	
J025269		10 Jun 2022
Nos.	UPDATED	
3/5		10 Jun 2022


1ST FLOOR

HYDROCK INVESTIGATION REQUIREMENTS


SK.03
26.07.22



GENERAL KEY

- | | |
|---|---|
|  | AREAS NOT
ACCESSED/OUTSIDE OF SCOPE |
| TEXT | APPROXIMATE LOCATION OF
ASBESTOS SAMPLES |
| TEXT | APPROXIMATE LOCATION OF
NON ASBESTOS SAMPLES |

DETAIL KEY

-  APPROXIMATE LOCATION OF
ASBESTOS CONTAINING
MATERIALS



32 Writtle Road
Chelmsford
Essex
CM1 3BX
Phone: 01245 690606

CLIENT

Sav Development Ltd

This drawing must be viewed and read in conjunction with the Asbestos Survey Report for:

PROPERTY TITLE
4-6 Bedford Place
London

Ref. No. 100

100

10 Jun 2022

Nos

UPDATED


10 Jun 2022

2ND FLOOR

SK. 04

26.07.22.

HYDROCK INVESTIGATIONS REQUIREMENTS



GENERAL KEY

- AREAS NOT ACCESSED/OUTSIDE OF SCOPE
- TEXT** APPROXIMATE LOCATION OF ASBESTOS SAMPLES
- TEXT** APPROXIMATE LOCATION OF NON ASBESTOS SAMPLES

DETAIL KEY

- APPROXIMATE LOCATION OF ASBESTOS CONTAINING MATERIALS

FULL CIRCLE COMPLIANCE
 32 Writtle Road
 Chelmsford
 Essex
 CM1 3BX
 Phone: 01245 690606

CLIENT
 Sav Development Ltd

This drawing must be viewed and read in conjunction with the Asbestos Survey Report for:

PROPERTY TITLE
 4-6 Bedford Place
 London

Ref. No.	J025269	DRAWN DATED	10 Jun 2022
Nos.	5/5	UPDATED	10 Jun 2022


3RD FLOOR

SK.05
26.07.22

☑ F20 → F27; open-up flooring to determine joist sizes, centres, span-direction + condition

— C12 → C16; core-drill to determine wall thickness and build-up.

HYDROCK INVESTIGATION REQUIREMENTS



GENERAL KEY

■ AREAS NOT ACCESSED/OUTSIDE OF SCOPE

TEXT APPROXIMATE LOCATION OF ASBESTOS SAMPLES

TEXT APPROXIMATE LOCATION OF NON ASBESTOS SAMPLES

DETAIL KEY

■ APPROXIMATE LOCATION OF ASBESTOS CONTAINING MATERIALS



32 Writtle Road
Chelmsford
Essex
CM1 3BX
Phone: 01245 690606

CLIENT

Sav Development Ltd

This drawing must be viewed and read in conjunction with the Asbestos Survey Report for:

PROPERTY TITLE
4-6 Bedford Place
London

Ref. No.	DRAWN DATED	10 Jun 2022
Nos.	UPDATED	10 Jun 2022

ROOF

SK.06

Expose upside roof and ceiling joists where permissible (to determine rafter, valley beam, and ceiling joist sizes, condition and centres).

HYDROCK INVESTIGATION REQUIREMENTS 26.7.22