

11 Chamberlain Street, NW1 8XD

Job Number: 8472

Date	Issue	Revision
01.07.22	1	

Document register

Drawing	Document	Revision
100	Lower Ground Floor Plan	P1
101	Ground Floor Plan	P1
102	First Floor Plan	P1
103	Second Floor Plan	P1
104	Third Floor Plan	P1
105	Roof plan	P1
200	Structural Details	P1
300	Structural Sections	P1

CO₂e History

Rev	Date	CO ₂ e Total
1	01.07.22	11,849

3D Model (Not to scale)



- = 25 kgCO₂e
1 Tree in a Year Absorbs
- = 69 Trees Per Year
1576kgCO₂e
1 Tonne of Steel
- = 14 Trees Per Year
332kgCO₂e
1 Cubic Meter of Concrete

ROO

Risks

These have potential to cause design changes which could lead to increased cost and/or build-time.


1. Site unknowns: Changes in floor span direction, or structural elements that have not been identified by investigative works.
2. Depth of existing foundations unknown. Lower floor level assumed to require RC underpinning works to accommodate without undermining existing wall.
3. Location of drainage / access requirements for drainage unknown. Existing drainage run is public.
4. Presence of existing steelwork bearing onto load bearing structure to be demolished. Additional structure needed to allow removal of structure. Or scheme reconfiguration. Exploratory works needed to confirm
5. Trial hole needed to confirm depth and soil conditions

Options

Alternative structural solutions which Blue Engineering have no strong preference over.

1. Opt for UB Sections instead of UC Sections. Lighter sections lead to cost savings.

Opportunities



19 Trees needed for carbon absorption over 25 years
 If you would like to plant these trees donate [here](#).

Materials	Kg	CO ₂ e	£
Steel	1901	3295	8458
Concrete	70560	8554	5232

Combined estimated CO₂e for these materials is: 11,849

Estimated cost of materials is: £13,691

Find out why we are doing this and how we got our numbers [here](#).

DO NOT SCALE FROM THIS DRAWING
 All dimensions to be verified on site before commencing work. All error and omissions are to be reported to the Engineer. This drawing is to be read in conjunction with all relevant Design Team drawings and specifications

Drawing History

Rev	Date	Description	Drawn	Checked
P1	01.07.22	For Comment	DB	JLA

All cutouts to be cleanly disc cut using non percussive hand tools. Beams and lintels to be tightly dry packed into position

Unhatched walls are non-load bearing and are to be constructed to Architect's specification

30x5mm mild steel restraint straps to be installed at 1200mm horizontal centres and 300mm vertical centres, and to be 1200mm long at all junctions between the floor plates and steelwork/masonry

U.N.O. All steelwork is to be grade S355, including plates and connections. Refer to Structural Specification

U.N.O. All bolts to be Grade 8.8

- Indicates line of structure under
- - - - - Indicates existing structure to be demolished
- ////// Indicates change in level

Proposed Steelwork Schedule	
Ref.	Serial Size
UC1	152 x 152 x 23 UC

All Pad foundations to be as dimensioned and formed with FND2 concrete mix or other approved by Building Control officer - depth of foundations to be minimum 1000mm below ground level on virgin ground and as agreed with Building Control

Foundation design is in abeyance and subject to results from trial holes recommended prior to works commencing to establish depth and form of existing foundations and to confirm ground conditions

Underpinning Specification

The underpinning has been designed so that the maximum bearing pressure is 150 KN/m² (SLS) based on medium dense sand and gravel indicated on borehole logs local to the site. Should the ground conditions found to be different the structural engineer must be informed prior to the casting of the underpinning.

The Contractor is to be responsible for the accurate construction of the works according to the true intent of the Engineer's drawings and this specification.

The Contractor is to consider the need for any temporary works required to ensure the stability of the walls underpinned and provide any needling, dead shoring, propping etc. as may be appropriate.

The underpinning legs are to be constructed in the stages indicated on the drawing. Should the contractor wish to undertake the works in different stages this must be agreed with the engineer prior to undertaking the works

The excavation works are to be undertaken carefully so that the existing footings are not disturbed. Excavations are to be temporarily supported as necessary

When excavating for an underpinning leg, if any deviation is found in the nature of the bearing strata, or if obstacles or obstructions are encountered, the facts are to be reported to the Engineer.

All underpinning legs should have keys formed in them for bonding into succeeding legs as indicated on the Engineer's drawing.

A minimum of 48 hours after concreting a leg of underpinning, the footings above may be pinned up.

The pinning concrete is to be driven into place using hand held hammer and a 75 mm square hardwood drift against a substantial timber, secured on far side of footing.

Concreting and pinning-up must be completed before starting to excavate the next section of underpinning in the sequence.

Underpinning legs should preferably be concreted on the same day as they are excavated. If it is necessary to leave them open overnight temporary works and timbering are to be used to ensure that all is secure. On no account are underpinning legs to be left open over the weekend.

Particular care is to be taken to clean off and if necessary hack or scabble side of previously cast legs to provide adequate bond before concreting subsequent legs.

If water is encountered in excavation the Contractor is to provide sumps, grips and pumps as necessary to keep the excavations free from water always.

Materials


The concrete used in underpinning legs shall be minimum grade RC40 in accordance with BS EN 206:2013, with a minimum cement content of 330 kg/m³ or a 1:1.5:3 prescribed mix using 20 mm maximum aggregate, subject to proper ganging facilities being available on site.

Pinning concrete shall be approximately 75 mm thick pea-shingle concrete 1:1.5:3 mixing using 5 mm - 10 mm coarse aggregate and "Cebex 100" expanding admixture by Messrs Fosroc UK Ltd in accordance with their instructions.

The water content in the pinning concrete is to be the minimum necessary to ensure hydration of the cement and the consistency should be such that the wetted mix will just bind under strong hand pressure.

Numbers in bay refer to a "possible" excavation and underpinning sequence to be undertaken by the contractor - Refer to Structural Specification for more Details

- ① ③ ⑤ ② ④



PRELIMINARY
 NOT FOR CONSTRUCTION

Title
 Lower Ground Floor Plan

Project
 11 Chamberlain Street, NW1 8XD

Client
 Jaakko Ahmala and Liisa Tornivaara
 Job No.
 8472

Drawing No.
 100

Revision
 P1 Scale
 1:50 at A2

DO NOT SCALE FROM THIS DRAWING
 All dimensions to be verified on site before commencing work. All error and omissions are to be reported to the Engineer. This drawing is to be read in conjunction with all relevant Design Team drawings and specifications

Drawing History

Rev	Date	Description	Drawn	Checked
P1	01.07.22	For Comment	DB	JLA

All cutouts to be cleanly disc cut using non percussive hand tools. Beams and lintels to be tightly dry packed into position

Unhatched walls are non-load bearing and are to be constructed to Architect's specification

30x5mm mild steel restraint straps to be installed at 1200mm horizontal centres and 300mm vertical centres, and to be 1200mm long at all junctions between the floor plates and steelwork/masonry

Where steelwork is supporting existing masonry or blockwork, minimum 25mm gap to be tightly dry packed between top flange of beam and structure over. Temporary works only to be removed once dry pack has hardened

U.N.O. All steelwork is to be grade S355, including plates and connections. Refer to Structural Specification

U.N.O. Steelwork to steelwork connections to be via 10mm thick end plates with 6mm full face fillet weld fixed into web of opposing beam using 4no. M16 bolts

U.N.O. All bolts to be Grade 8.8

Beams over openings are designed with a total deflection limited to span/325. Live load deflection has been limited to span/500. Manufacturer to confirm if acceptable


Existing timbers to be inspected for general condition, rot and decay. Contact Blue Engineering if poor condition found

----- Indicates line of structure under
 - - - - - Indicates existing structure to be demolished

Proposed Steelwork Schedule	
Ref.	Serial Size
UC4	203 x 203 x 46 UC
UC6	203 x 203 x 60 UC

Padstone Schedule:
 P1: 650x100x140mm Pre-Stressed Concrete Lintel
 P2: 950mm long Naylor R12 High Spec Lintel
 P3: 800mm long Naylor R12 High Spec Lintel

All padstones to be tightly dry packed into position



Beam OB2 to bear onto Column OC1 and to be connected via standard endplate connection - 10mm thick endplate to be welded to each beam via 6mm thick full face fillet weld and 4no. M16 bolts through plates and bottom flange of beam

Opening to be infilled with brickwork to match existing with class (iii) mortar. New brickwork to be toothed into existing

Beam may need to be cranked. Architect to provide section to determine levels

New balustrade design by others. Balustrade to be fixed to the walls. Architect to confirm

New 175mm thick RC suspended slab to be formed using RC40 concrete mix with A393 mesh mid-depth. Nominal cover to be 50mm to ends

Openings in slabs to be trimmed with 203x203x46 UC Beams

PRELIMINARY
 NOT FOR CONSTRUCTION

Title
 Ground Floor Plan

Project
 11 Chamberlain Street, NW1 8XD

Client
 Jaakko Ahmala and Liisa Tornivaara
 Job No.
 8472

Drawing No.
 101

Revision
 P1 Scale
 1:50 at A2

DO NOT SCALE FROM THIS DRAWING
 All dimensions to be verified on site before commencing work. All error and omissions are to be reported to the Engineer. This drawing is to be read in conjunction with all relevant Design Team drawings and specifications

Drawing History

Rev	Date	Description	Drawn	Checked
P1	01.07.22	For Comment	DB	JLA

All cutouts to be cleanly disc cut using non percussive hand tools. Beams and lintels to be tightly dry packed into position

Unhatched walls are non-load bearing and are to be constructed to Architect's specification

Existing timbers to be inspected for general condition, rot and decay. Contact Blue Engineering if poor condition found


Manthorpe G912 joist seal to be used for timber beams bearing into solid masonry walls - Refer to Manufactures Specification

Denotes junction between timber stud wall and masonry wall. Abutting stud to have M12 chemical anchors fixed to existing masonry at 400mm centres

All doubled and trebled timber members to be bolted together using M12 bolts and double sided tooth connectors at 500mm centres

DJ = 2no. 150x50mm C24 joists

- - - - - Indicates existing structure to be demolished



PRELIMINARY
 NOT FOR CONSTRUCTION

Title
 First Floor Plan

Project
 11 Chamberlain Street, NW1 8XD

Client
 Jaakko Ahmala and Liisa Tornivaara
 Job No.
 8472

Drawing No.
 102

Revision
 P1

Scale
 1:50 at A2

DO NOT SCALE FROM THIS DRAWING
 All dimensions to be verified on site before commencing work. All error and omissions are to be reported to the Engineer. This drawing is to be read in conjunction with all relevant Design Team drawings and specifications

Drawing History


Rev	Date	Description	Drawn	Checked
P1	01.07.22	For Comment	DB	JLA

All cutouts to be cleanly disc cut using non percussive hand tools. Beams and lintels to be tightly dry packed into position

Unhatched walls are non-load bearing and are to be constructed to Architect's specification

Existing timbers to be inspected for general condition, rot and decay. Contact Blue Engineering if poor condition found

- - - - - Indicates existing structure to be demolished



New staircase to Architect's specification.
 Design by others

PRELIMINARY
 NOT FOR CONSTRUCTION

Title
 Second Floor Plan

Project
 11 Chamberlain Street,
 NW1 8XD

Client
 Jaakko Ahmala and Liisa Tornivaara

Job No.
 8472

Drawing No.
 103

Revision
 P1

Scale
 1:50 at A2

DO NOT SCALE FROM THIS DRAWING
 All dimensions to be verified on site before commencing work. All error and omissions are to be reported to the Engineer. This drawing is to be read in conjunction with all relevant Design Team drawings and specifications

Drawing History

Rev	Date	Description	Drawn	Checked
P1	01.07.22	For Comment	DB	JLA

All cutouts to be cleanly disc cut using non percussive hand tools. Beams and lintels to be tightly dry packed into position

Unhatched walls are non-load bearing and are to be constructed to Architect's specification

30x5mm mild steel restraint straps to be installed at 1200mm horizontal centres, 1200mm long at all junctions between the floor plates and steelwork/masonry

U.N.O. All steelwork is to be grade S355, including plates and connections. Refer to Structural Specification

U.N.O. Steelwork to steelwork connections to be via 10mm thick end plates with 6mm full face fillet weld fixed into web of opposing beam using 4no. M16 bolts

U.N.O. All bolts to be Grade 8.8

Existing timbers to be inspected for general condition, rot and decay. Contact Blue Engineering if poor condition found

Manthorpe G912 joist seal to be used for timber beams bearing into solid masonry walls - Refer to Manufactures Specification

Air gap of minimum 25mm to be kept under new floor joists to allow for deflections unless plasterboard is directly affixed

Denotes junction between timber stud wall and masonry wall. Abutting stud to have M12 chemical anchors fixed to existing masonry at 400mm centres

All doubled and trebled timber members to be bolted together using M12 bolts and double sided tooth connectors at 500mm centres


TP = 2no. 150x50mm C24 timber post
 TJ = 3no. 150x50mm C24 joists

- Indicates line of structure under
- - - - - Indicates existing structure to be demolished
- Indicates location of Manthorpe G912 joist seal - Refer to Manufactures Specification

Proposed Steelwork Schedule	
Ref.	Serial Size
UB2	152 x 89 x 16 UB
UC3	152 x 152 x 37 UC
UC4	203 x 203 x 46 UC

Padstone Schedule:
 P4: 500x100x15mm thick steel plate
 P5: 400x100x10mm thick steel plate
 P6: 550x100x150mm deep mass concrete padstone
 P7: 500x100x15mm thick steel plate

All padstones to be tightly dry packed into position



PRELIMINARY
 NOT FOR CONSTRUCTION

Title
 Third Floor Plan

Project
 11 Chamberlain Street, NW1 8XD

Client
 Jaakko Ahmala and Liisa Tornivaara
 Job No.
 8472

Drawing No.
 104

Revision
 P1 Scale
 1:50 at A2

DO NOT SCALE FROM THIS DRAWING
 All dimensions to be verified on site before commencing work. All error and omissions are to be reported to the Engineer. This drawing is to be read in conjunction with all relevant Design Team drawings and specifications

Drawing History

Rev	Date	Description	Drawn	Checked
P1	01.07.22	For Comment	DB	JLA

All cutouts to be cleanly disc cut using non percussive hand tools. Beams and lintels to be tightly dry packed into position

30x5mm mild steel restraint straps to be installed at 1200mm horizontal centres, 1200mm long at all junctions between the floor plates and steelwork/masonry

U.N.O. All steelwork is to be grade S355, including plates and connections. Refer to Structural Specification

U.N.O. All bolts to be Grade 8.8

Beams over openings are designed with a total deflection limited to span/325. Live load deflection has been limited to span/500. Manufacturer to confirm if acceptable

Existing timbers to be inspected for general condition, rot and decay. Contact Blue Engineering if poor condition found

Manthorpe G912 joist seal to be used for timber beams bearing into solid masonry walls - Refer to Manufactures Specification

All doubled and trebled timber members to be bolted together using M12 bolts and double sided tooth connectors at 500mm centres

TP = 2no. 150x50mm C24 timber post

DJ = 2no. 150x50mm C24 joists


TJ = 3no. 150x50mm C24 joists

----- Indicates line of structure under

Proposed Steelwork Schedule	
Ref.	Serial Size
UC2	152 x 152 x 30 UC

Padstone Schedule:
 P8: 250x100x10mm thick steel plate

All padstones to be tightly dry packed into position



PRELIMINARY
 NOT FOR CONSTRUCTION

Title
 Roof Plan

Project
 11 Chamberlain Street, NW1 8XD

Client
 Jaakko Ahmala and Liisa Tornivaara

Job No.
 8472

Drawing No.
 105


Revision
 P1

Scale
 1:50 at A2


DO NOT SCALE FROM THIS DRAWING
 All dimensions to be verified on site before commencing work. All error and omissions are to be reported to the Engineer. This drawing is to be read in conjunction with all relevant Design Team drawings and specifications

Drawing History

Rev	Date	Description	Drawn	Checked
P1	01.07.22	For Comment	DB	JLA



Detail D1
 Scale 1:10



Detail D2
 Scale 1:20

PRELIMINARY
 NOT FOR CONSTRUCTION

Title
 Structural Details

Project
 11 Chamberlain Street,
 NW1 8XD

Client
 Jaakko Ahmala and Liisa Tornivaara
 Job No.
 8472

Drawing No.
 200


Revision
 P1

Scale
 Varies at A3

DO NOT SCALE FROM THIS DRAWING
 All dimensions to be verified on site before commencing work. All error and omissions are to be reported to the Engineer. This drawing is to be read in conjunction with all relevant Design Team drawings and specifications

Drawing History

Rev	Date	Description	Drawn	Checked
P1	01.07.22	For Comment	DB	JLA



Section S1
 Scale 1:50

PRELIMINARY
 NOT FOR CONSTRUCTION

Title
 Structural Section

Project
 11 Chamberlain Street,
 NW1 8XD

Client
 Jaakko Ahmala and Liisa Tornivaara
 Job No.
 8472

Drawing No.
 300

Revision
 P1

Scale
 1:50 at A3