





ROOF

- All new and existing sash windows overhauled to incorporate argon filled low e glass slimline double glazing with white painted timber.
- All new brickwork to match existing using second hand colour matched stock brick and colour matched mortar laid with skilled bricklayers.
- Lime render used to repair and replace all degraded decorative banding and projections. Exterior Keim or similar paints used to provide high quality topcoat.
- All visible rainwater goods to be in black painted cast iron.
  All handrails and guarding to be in minimally dimensioned black painted galvanised mild steel.
- 5.fireplaces, chimey breasts and chimney stacks to upper flat supported on steel work within the second floor depth.
- 6.Roof top photovoltaic panels mounted flush to roof with proprietary roofing system. All flashings in lead traditionally detailed.

