



NOTE

During restoration of existing fencing around the Green damage to root protection area (RPA) to be avoided. Use existing foundation footings to avoid damage to RPA.

Tree protection fencing not required. No heavy machinery to enter into RPA of retained trees, nor any extensive works to occur in proximity to retained trees.

Provision of power to green required to continue tradition of a Christmas tree each year

Tree Removal and Protection

Root Protection Areas: Within this area no excavation without prior agreement with Landscape Architect. Do not cut any roots larger than 15mm diameter.

Proposed works requiring excavation within root protection areas:

1. Refer to Arboriculturalists report
2. Refer to landscape details and topsoil plan for excavation depths.
3. Excavate by hand to prevent damage to roots larger than 25mm diameter.

Tree to be removed as per consented scheme

Use of an Airspade is required for digging trenches within root protection areas. The Air Spade will remove the soil revealing the tree roots without causing damage to the roots.



Airspade trench reference images. Display principles of method only. Excavation to be no wider than 400mm and no deeper than 450mm.

Rev	Comment	Date
P01	Planning condition discharge issue	02/11/2022

Tom Stuart-Smith Ltd
 The Dairy Studio
 Sergehill Ln, Abbots Langley WD5 0RZ
 Tel: +44 (0)207 253 2100

Status: For Planning

Project:
5 The Grove

Drawing:
**Front Garden and Green
 Tree Protection Plan**

Scale: 100 @ A1
 Dwg: 581-L-P-115 Rev: P01

Drawn: JT
 Date: 02/11/2022