

Job No: DFS221011 Design Engineer: AR Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain Secant Pile Retaining Wall & Segmental Underpinning Wall **Rev. 00** Page: 1 of 31

BROXWOOD VIEW, 29. ST. EDMUND'S TERRACE

LONDON NW8 7QH

Report on Detailed Design for Temporary Propping Scheme to Laterally Restrain Ø450
Secant Pile Retaining Wall & Segmental Underpinning Wall **Rev. 00**

Piling Contractor:

Arma Piling Limited
40 New Town Road
Bishop's Stortford
CM23 3SD
United Kingdom

Tel: 0207 313 4169
email:

Geotechnical/Temporary Works Design Engineers:

Deep Foundations Specialists Limited
**Foundations, Basements & Temporary Works
Specialist Consulting Geostructural
Engineers**
2nd Floor
The Porter Building
1 Brunel Way
Slough SL1 1FQ

Tel: 01753 396498
W: www.deep-foundations.co.uk

Project Structural Engineers:

Richard Tant Associates
Consulting Civil & Structural Engineers
54 Lisson Street
London
NW1 5DF

Tel: 020 7724 1002
email: info@richardtantassociates.com

Report Issued to:

Broxwood View Limited
62 St. Martins Lane
London
WC2N 4JS

Tel:
email:

DESIGN STATUS & ISSUE RECORD

Revision	Status	Description	Design		Check	
			Engineer	Date	Engineer	Date
/	For Review	Detailed design for temporary propping scheme to laterally restrain pile wall & segmental underpinning wall	Dr. Azeez Rotimi	15/10/22	Dr. Abid Adekunte	15/10/22



Job No: DFS221011

Design Engineer: AR

Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain
Secant Pile Retaining Wall & Segmental Underpinning Wall [Rev. 00](#)

Page: 2 of 31

BROXWOOD VIEW, 29. ST. EDMUND'S TERRACE LONDON NW8 7QH**REPORT ON DETAILED DESIGN FOR TEMPORARY PROPPING SCHEME TO LATERALLY RESTRAIN Ø450 SECANT
PILE RETAINING WALL & SEGMENTAL UNDERPINNING WALL****1.0 INTRODUCTION**

Deep Foundations Specialists (DFS) Limited have been appointed by Broxwood View Limited to carry out the detailed designs for the permanent perimeter secant pile retaining wall, associated temporary works and bearing piles for the proposed residential development on the above site in Northwest London.

The wider project is centred on the redevelopment of the site; this involves the complete demolition of the pre-existing 2 storey Porter's Lodge building on the site and the subsequent construction of a new 4 storey-extension adjacent to the northern wall of the existing Barrie House multi-storey block of residential apartments on the site, with an underlying single level-basement. The new 4 storey-structure would accommodate 9 No. residential apartments.

The approximate National Grid Reference for the approximately square-shaped 0.18 ha-site is 527495E, 183575N, while existing site topography generally slopes downwards from the northern boundary to the south, with an approximate gradient of 1:8. The site's reduced levels vary between (+48.600m OD) – (+42.000m OD). It is proposed to chiefly support the new structure on a 600mm thick reinforced concrete raft at lower ground floor level, while a number of bearing piles are also required as part of the proposed development.

A combination of secant bored pile retaining wall and segmental underpinning systems are required to support the deep excavation for the proposed subterranean components of the building, Maximum retained height is < 4.85m. The secant pile retaining wall and segmental underpinning systems would also function as permanent components of the new basement structure. In addition to lateral earth/groundwater retention, the secant bored pile retaining wall is also designed to support nominal service vertical compressive loading of up to 175 kN/m run and nominal service vertical tension loading of **-70 kN/m** run of wall.



Job No: DFS221011

Design Engineer: AR

Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain
Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00

Page: 3 of 31

The detailed designs for the secant pile retaining wall and segmental underpinning wall had already been completed and issued under separate covers by Deep Foundations Specialists (DFS) Limited and Richard Trant Associates Limited respectively. This particular report chiefly focuses on the detailed design for the temporary props that are required to provide temporary lateral restraint to the retaining walls during bulk excavation and prior to the completion of the basement's reinforced concrete shell.

The temporary propping systems are required to support service horizontal loading of up to 50 kN/m run of wall, as specified in Table 3 of Deep Foundations Specialists (DFS) Limited's Pile Wall Design Report No. DFS221011 Rev. 00 of 14/10/22.

The design calculations are presented under the following headings:

- INPUT DATA
- OUTLINE OF TEMPORARY WORKS DESIGN
- TYPICAL RETAINING WALL SECTION(S) CONSIDERED IN TEMPORARY WORKS DESIGN
- GROUND CONDITIONS
- TEMPORARY WORKS DESIGN
- PROPOSED STRUCTURAL MOVEMENT MONITORING SCHEME & CONTINGENCY MEASURES
- REFERENCES
- APPENDICES



Job No: DFS221011

Design Engineer: AR

Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain
Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00

Page: 4 of 31

2.0 INPUT DATA

Design is based on the following site-specific reference documents:

- (i) PARMARBROOK's Document No. 1805 of May 2018 – Basement Impact Assessment: Barrie House, 29 St. Edmunds Terrace.
- (ii) Card Geotechnics Limited's Geotechnical Report No. CG/28408 Rev. 2 of May 2018 – Barrie House Basement Impact Assessment Revision 2.
- (iii) Soil Consultants Limited's Geotechnical Report No. 9241/OT/JRCB of 07 November 2012 – Ground Investigation Report for Proposed Construction at Barrie House, 29 St. Edmund's Terrace, London NW8 7QH.
- (iv) PARMARBROOK's Drawing No. 1805-PAR-ZZ-LG-DR-S-0090-S2-P02 – General Arrangement Lower Ground Floor.
- (v) PARMARBROOK's Drawing No. 1805-PAR-ZZ-00-DR-S-0100-S2-P02 – General Arrangement Ground Floor.
- (vi) PARMARBROOK's Drawing No. 1805-PAR-ZZ-01-DR-S-0110-S2-P01 – General Arrangement First Floor.
- (vii) PARMARBROOK's Drawing No. 1805-PAR-ZZ-02-DR-S-0120 – General Arrangement Second Floor.
- (viii) PARMARBROOK's Drawing No. 1805-PAR-ZZ-03-DR-S-0130 – General Arrangement Third Floor.
- (ix) PARMARBROOK's Drawing No. 1805-PAR-ZZ-04-DR-S-0140 – General Arrangement Roof Plan.
- (x) Richard Tant Associates' Drawing No. 5295-P01 – Notes.
- (xi) Richard Tant Associates' Drawing No. 5295-P02 – Proposed Basement Floor Sheet 1/2.
- (xii) Richard Tant Associates' Drawing No. 5295-P03 – Proposed Basement Floor Sheet 2/2.
- (xiii) Richard Tant Associates' Drawing No. 5295-P04 – Proposed Ground Floor Sheet 1/2.
- (xiv) Richard Tant Associates' Drawing No. 5295-P05 – Proposed Ground Floor Sheet 2/2.



Job No: DFS221011

Design Engineer: AR

Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QHCalc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain
Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00

Page: 5 of 31

-
- (xv) Richard Tant Associates' Drawing No. 5295-P10 – Section 1-1.
 - (xvi) Richard Tant Associates' Drawing No. 5295-P11 – Section 2-2.
 - (xvii) Richard Tant Associates' Drawing No. 5295-P12 – Section 3-3.
 - (xviii) Richard Tant Associates' Drawing No. 5295-P13 – Section 4-4.
 - (xix) Richard Tant Associates' Drawing No. 5295-P14 – Sections 5-5 & 6-6.
 - (xx) Richard Tant Associates' Drawing No. 5295-P15 – Sections 7-7 & 8-8.
 - (xxi) Richard Tant Associates' Drawing No. 5295-P16 – Sections 9-9, 10-10 & 11-11.
 - (xxii) Richard Tant Associates' Drawing No. 5295-P17 – Section 12-12.
 - (xxiii) Richard Tant Associates' Drawing No. 5295-P18 – Section 13-13.
 - (xxiv) Richard Tant Associates' Drawing No. 5295-P19 – Section 14-14.
 - (xxv) Richard Tant Associates' Drawing No. 5295-P20 – Section 15-15.
 - (xxvi) Richard Tant Associates' Drawing No. 5295-PSM01 – Suggested Method of Works 1.
 - (xxvii) Richard Tant Associates' Drawing No. 5295-PSM02 – Suggested Method of Works 2.



Job No: DFS221011

Design Engineer: AR

Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain
Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00

Page: 6 of 31

3.0 OUTLINE OF TEMPORARY WORKS DESIGN

- The detailed design for the temporary propping scheme has been carried out in accordance with the recommendations of the BS5975 (2019) – Code of Practice for Temporary Works Procedures, ICE Specification for Piling & Embedded Retaining Walls (2016), BS8002 (1994), BS5950-1 (2002), BS EN 1997-1:2004 Eurocode 7, BS EN 1992-1-1: 2004 Eurocode 2, PD6687:2006 and the CIRIA Report No. C760 (2017).
- Proposed development comprises of a 4 storey-block of residential apartments, with an underlying basement, as an extension adjacent to the northern wall of the existing Barrie House multi-storey block of residential flats.
- The proposed earth/groundwater retention system for the deep excavation for the new basement on the site shall comprise of a combination of segmental underpinning retaining wall adjacent to the northern wall of the existing Barrie House and Ø450 perimeter secant pile retaining wall on all other sections of the proposed basement; 450mm dia. interlocking male and female piles, with male piles spaced @ 600mm c/c intervals.
- For serviceability reasons, whilst considering the existence of an underground Thames Water trunk outside the northern boundary of the proposed development, it is required to restrain all sections of the pile wall and segmental underpinning wall with a single row of temporary structural steel props in the temporary condition. The temporary props shall be fixed to the reinforced concrete capping beam on the pile wall and structural steel waling beam on the face of the segmental underpinning wall around crest level, such that there would be sufficient clearance above the props to allow for the safe construction of the reinforced concrete ground floor slab prior to the removal of the temporary props.
- In essence, all temporary props shall remain in-place until both the basement slab and the ground floor slab achieve sufficient/design structural strength.
- The above proposal would ensure that the pile wall lateral deflection at any section of the retaining walls and associated ground movements are restricted to tolerable levels during bulk excavation for new basement and therefore, it is expected that the serviceability of all underground assets (including the existing Thames Water trunk) and above-ground structures within the vicinity of the



Job No: DFS221011

Design Engineer: AR

Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain
Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00

Page: 7 of 31

propped retaining walls will not be compromised during and after the bulk excavation for the newly proposed basement.

- Maximum wall retained height is < 4.85m.
- The temporary props are generally subject to service horizontal loading of up to 50 kN/m run of wall; see table 3 of Deep Foundations Specialists Limited's pile wall design report No. DFS221011 Rev. 00 of 14/10/22.
- 10 kPa nominal traffic & services surcharge, as well as 50 kPa estimated potential surcharge from fire engines/appliances have been accounted for in the analysis of the retaining wall sections and associated temporary propping system design.
- The clay layers on the site are modelled as undrained materials, with total stress parameters in the temporary condition. All other soil layers are modelled with effective stress parameters.
- Anticipated perimeter pile wall lateral deflection in both temporary and permanent conditions is < 5.0mm.

Job No: DFS221011 Design Engineer: AR Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain
Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00 Page: 8 of 31

4.0 TYPICAL RETAINING WALL SECTION(S) CONSIDERED IN TEMPORARY WORKS DESIGN

The typical retaining wall section considered in temporary works design is described below. A set of construction drawings, which illustrate the layout of the retaining wall-stabilising temporary works, typical sections, connection details and associated construction sequencing are attached to the appendices of this report.

TYPICAL RETAINING WALL SECTION (PROPPED): Piling Platform Level \approx Existing Ground Level in the Area of Proposed Works = +45.500. Basement Formation Level \approx +40.650. Maximum Wall Retained Height < 4.85m. Wall Section is Designed to be Temporarily Restrained with a Row of Structural Steel Props at Capping Beam Level/Wall Crest Level in the Temporary Condition. In the Permanent Condition, the Retaining Wall shall be Restrained by the Lower Ground Floor Slab and the Ground Floor Slab. 10 kPa Nominal Traffic & Services Surcharge, as well as 50 kPa potential surcharge from fire engines/appliances are Accounted for in Wall Analysis & Design.

Proposed Sequence of Construction:

1. Install temporary guide wall prior to the commencement of secant pile wall construction.
2. Concurrently install $\varnothing 450$ interlocking male and female piles, with male piles spaced @ 600mm c/c, from piling platform level (+45.500) to depths specified by DFS, to form secant pile wall, as well as the $\varnothing 350$ bearing piles required for the proposed underpinning works underneath the existing northern wall of Barrie House; see DFS' pile wall construction schedule and bearing pile construction schedule for more detailed information.
3. Break down piles to 75mm above proposed soffit level of RC capping beam.
4. Construct RC capping beam on piles.
5. Carry out segmental underpinning of the existing pad footings and strip footings underneath the northern wall of the existing Barrie House building, as detailed by the Project Structural Engineer (see Richard Tant Associates' Drawing No's 5295-P02, 5295-P04, 5295-P13, 5295-P15, 5295-P17, 5295-P18, 5295-P19, 5295-PSM01 & 5295-PSM02).
6. Install temporary structural steel waling beam along the face of segmental underpinning retaining wall around crest level.



Job No: DFS221011

Design Engineer: AR

Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain
Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00

Page: 9 of 31

-
7. Install temporary props at capping beam level/waling beam level of pile wall and underpinning wall.
 8. Carry out bulk excavation down to basement formation level; 4.85m maximum dig.
 9. Place blinding of 50mm minimum thickness at formation level.
 10. Install/fix water-proof membrane on placed blinding, as well as face of pile retaining wall/segmental underpinning wall and around capping beam.
 11. Construct 600mm thick reinforced concrete raft/lower ground floor slab with water-proof concrete and dowel into pile retaining wall/segmental underpinning wall, whilst making allowance for cavity drain in front of retaining walls.
 12. Construct RC liner wall of 250mm minimum thickness with water-proof concrete, in front of pile retaining wall, from basement level, up to capping beam soffit level and connect same to capping beam.
 13. Construct ground floor slab and connect same to capping beam.
 14. Remove temporary props and structural steel walling beam.
 15. Construct superstructure.



Job No: DFS221011

Design Engineer: AR

Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain
Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00

Page: 10 of 31

5.0 GROUND CONDITIONS

Site stratigraphy at Broxwood View, 29 St. Edmund's Terrace London NW8 7QH may be generalised as shown in table 1 below:

DEPTH (m bgl)	DESCRIPTION	Representative N_{spt} Value
0.0 – 2.5	Made Ground	-
Below 2.5m bgl	Soft to Firm to Stiff to Very Stiff London Clay	6 - 16

* - Static groundwater level was observed to be approx. 0.8m bgl during site-specific monitoring.

Table 1 – Generalised Site Stratigraphy

Soil parameters used in design are presented in table 2 overleaf. In table 2;

ϕ' values for the cohesionless layers/made ground have been deduced from N_{spt} values (after Peck, Hanson & Thorburn (1974)).

ϕ' values for the cohesive layers are deduced from plasticity indices (after CIRIA Report No. 104, 1984 & CIRIA Report No. C580, 2003).

E' values for cohesionless materials/made ground are estimated with the correlation: $E' = 2000 - 3000 * N_{spt}$ in kPa (after CIRIA Report No. 143, 1995 & CIRIA Report No. C580, 2003).

E' values for cohesive layers are deduced from the expression $E' = 0.8 * E_u$, where $E_u = 800 * C_u$. (after Borin, 2012).



Job No: DFS221011

Design Engineer: AR

Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain
Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00

Page: 11 of 31

SOIL LAYER	N_{spt}	γ (kN/m ³)	ϕ' (°)	C' (kPa)	C_u (kPa)	E_u	E' (kPa)
Made Ground	-	18.0	28.0	0.0	-	-	15000
Soft to Firm to Stiff to Very Stiff London Clay	6 - 16	19.0	23.0	5.0	30 + 12z	24000 + 9600z	19200 + 7680z

Table 2 – Input soil parameters



Job No: DFS221011 Design Engineer: AR Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain
Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00 Page: 12 of 31

6.0 TEMPORARY WORKS DESIGN

(i) Structural Design

It is proposed to temporarily restrain the proposed secant bored pile retaining wall and segmental underpinning wall for the site at Broxwood View, 29 St. Edmund's Terrace London NW8 7QH with a single row of structural steel struts at capping beam level/crest level, in the temporary condition. The temporary struts shall remain in-place until both the basement slab and ground floor slab achieve sufficient/design structural strength.

The structural steel struts shall be fixed to the reinforced concrete capping beam on the pile wall and a structural steel waling beam around the crest level of the segmental underpinning wall, before bulk excavation for the proposed basement progresses below 1m depth. Copies of Deep Foundations Specialists (DFS) Limited's temporary works drawings are attached to the appendices of this report; these provide detailed technical information on perimeter retaining wall layout, struts, capping beam, waling beam, as well as all associated connection details.

Based on retaining wall serviceability analysis results, estimated maximum service prop load (perpendicular to wall line) = 50 kN/m run of wall (see CADS PWS 6.09 computer output files attached to the appendices of this report). In addition, based on the CADS PWS 6.09 computer output files, anticipated maximum wall lateral deflection < 5.0mm.

Prop Type A – RMD Kwikform Tubeshor 320 Hydraulic Corner Braces (45° Inclination Angle to Wall Centrelines)

Estimated service prop load at right angle to wall < 50 kN/m (see CADS PWS 6.09 computer output files attached to the appendices of this report). However, 50 kN/m service prop load is conservatively adopted in the current structural analysis & design calculations for the propping system.

The behaviour of these corner braces and capping beam under 50 kN/m service loading has been analysed with GoBeam Version 2015.1 structural modelling programme. Copies of the relevant computer output files are attached to the appendices of this report.



Job No: DFS221011 Design Engineer: AR Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain
Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00 Page: 13 of 31

The main highlights of the analysis are outlined below:

Maximum Service Bending Moment on Capping Beam/Waling Beam = 181.0 kNm

Maximum Service Shear Force on Capping Beam/Waling Beam = 167.0 kN

Maximum Capping Beam/Waling Beam Deflection = 0.5mm

Maximum Corner Brace Reaction = 306.0 kN (conservatively adopt 350 kN for design purpose)

Maximum effective length l of corner braces < 6.0m (conservatively adopt 8.0m for design purpose)

As corner braces are inclined at 45° angle to pile wall centreline, maximum service axial load P_s in any corner brace = $350 / (\sin 45^\circ) = 495$ kN/Corner Brace.

$\therefore P_s = 495$ kN/Corner Brace

\therefore Provide RMD Kwikform Tubeshor 320 Hydraulic Struts as Corner Braces

Allowable Compressive Resistance $P_c = 500$ kN > 495 kN (O.K.); see copies of manufacturer's datasheets attached to the appendices of this report.

The above specification duly accounts for potential load eccentricities and accidental lateral impact loading of up to 10 kN on the struts.

Load Eccentricity Check for Corner Braces:

N/A



Job No: DFS221011 Design Engineer: AR Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain
Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00 Page: 14 of 31

Prop Type B – RMD Kwikform Tubeshor 320 Hydraulic Flying Struts

Estimated service prop load at right angle to wall < 50 kN/m (see CADS PWS 6.09 computer output files attached to the appendices of this report). However, 50 kN/m service prop load is conservatively adopted in the current structural analysis & design calculations for the propping system.

The behaviour of these flying struts and capping beam under 50 kN/m service loading has been analysed with GoBeam Version 2015.1 structural modelling programme. Copies of the relevant computer output files are attached to the appendices of this report.

The main highlights of the analysis are outlined below:

Maximum Service Bending Moment on Capping Beam/Waling Beam = 181.0 kNm

Maximum Service Shear Force on Capping Beam/Waling Beam = 167.0 kN

Maximum Capping Beam/Waling Beam Deflection = 0.5mm

Maximum Flying Strut Reaction = 329.0 kN (conservatively adopt 400 kN for design purpose)

Maximum effective length l of flying struts < 11m (adopt 11m for design purpose)

Individual Service Prop Load P_s = 400 kN/flying strut (as already confirmed above)

∴ Provide RMD Kwikform Tubeshor 320 Hydraulic Struts as Flying Struts.

Allowable Compressive Resistance P_c = 410 kN > 400 kN (O.K.); see copies of manufacturer's datasheets attached to the appendices of this report.

Allowance for Accidental Impact Loading on Struts during Construction:

Accidental loading of up to 10 kN is accounted for in manufacturer's datasheets for the RMD Kwikform Tubeshor 320 hydraulic struts. Copies are attached to the appendices of this report.



Job No: DFS221011 Design Engineer: AR Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00 Page: 15 of 31

Capping Beam Design (7m Maximum Effective Span under 50 kN/m Service Horizontal Loading in the Temporary Condition):

To be completed and issued by the Project Structural Engineer under separate cover.

Structural Steel Waling Beam Design (7m Maximum Effective Span under 50 kN/m Service Horizontal Loading in the Temporary Condition):

Maximum Service Bending Moment M_s on Waling Beam/Capping Beam = 181.0 kNm (shown earlier).

∴ Provide RMD Kwikform GeoBrace 254

Allowable Service Bending Moment $M_{allowable} = 404 \text{ kNm} > 181.0 \text{ kNm}$ (O.K.); see copies of manufacturer's datasheets attached to the appendices of this report.

End Plates for Struts:

Provide end plates to manufacturer's standard details; 320mm x 290mm x 20mm thk. MSX10052 MEGASHOR Push Pull Prop Pivot or 490mm x 300mm x 20mm thk. GBX25404 GeoBrace 254 Inclined Prop Connector. See manufacturer's datasheets attached to the appendices of this report.

Bolt Connections:

(i) Shear Capacity:

Shear loading from flying struts would be negligible.

Ultimate horizontal shear from corner braces on end plates = $P_u \cos \theta$, where P_u is the ultimate axial load in strut and θ is the angle of inclination of strut to wall line.

∴ Ultimate horizontal shear on end plate = $(495 * 1.6) * \cos 45^\circ = 560 \text{ KN}$

Additional vertical shear on bolts due to self-weight of struts (70 kg/m, 11m worst-case length) < 10 KN



Job No: DFS221011 Design Engineer: AR Date: 15 October 2022
Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH
Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00 Page: 16 of 31

∴ Resultant shear load on a bearing plate = $\sqrt{[560^2 + 10^2]}$ KN \cong 570 KN

Assuming 8 No. M20 DEWALT SC-PRO Carbon Steel Threaded Rod (strength class 8.8) in S275 ply;

Ultimate shear capacity of 1 No. rod = 98 KN

Ultimate shear capacity of 8 No. bolts = $98 * 8 = 784$ KN > 570 KN **(O.K.)**.

(ii) Bearing Capacity:

Ultimate compressive loading on end plate $400 \text{ KN} * 1.6 = 640 \text{ KN}$

Assuming 20mm minimum ply/plate thickness, for a M20 DEWALT SC-PRO Carbon Steel Threaded Rod (strength class 8.8), ultimate bearing capacity = 196 KN/bolt

Estimated ultimate bearing load on each bolt = $640/8 = 80 \text{ KN} < 196 \text{ KN}$ **(O.K.)**.

∴ Provide 8 No's M20 DEWALT SC-PRO Carbon Steel Threaded Anchor Rods (strength class 8.8) between End Plates and RC Capping Beam at Every Strut Position. Provide Same between Waling Beam and Underpinning Wall at Every Struct Position.

Every M20 DEWALT SC-PRO Carbon Steel Threaded Anchor Rod shall be Vinylester-Fixed.

170mm Minimum Anchor Bolt Embedment

Provide 8 No's M20 Grade 4.6 Non-Preloaded Ordinary Bolts between End Plates and Steel Waling Beams.



Job No: DFS221011

Design Engineer: AR

Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain
Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00

Page: 17 of 31

7.0 PROPOSED STRUCTURAL MOVEMENT MONITORING SCHEME & CONTINGENCY MEASURES

In order to maintain an adequate level of safety and serviceability during the bulk excavation phase, it is imperative that the movement of the retaining walls, as well as the external walls of neighbouring structures be regularly monitored, while a suitable contingency scheme needs to be put in-place, in anticipation of measured wall deflections potentially exceeding the maximum threshold. The instrumentation and monitoring process shall generally follow the recommendations of the Project Structural Engineer; see Richard Trant Associates' drawing No. 5295-PM01 for detailed information.

Essentially, the structural movement monitoring scheme shall involve the following procedure:

- Carry out initial monitoring works 2 months before commencement of site operations in order to establish baseline readings and pre-construction movements, whilst following the reading frequencies stipulated in Richard Trant Associates' drawing No. 5295-PM01.
- At piling/groundworks stage, monitoring data recording shall be done on a weekly basis, until 1 month after ground floor slab construction, as specified in Richard Trant Associates' drawing No. 5295-PM01. However, during underpinning works, readings shall be taken on a daily basis until 1 week after the curing of the final dry pack.
- After the completion of ground floor construction, reading frequency may be limited to 1 No. reading per calendar month until structural works are completed on the site.

The monitoring process shall be based on a 'traffic light' system with green, amber and red response zones. Descriptions of the response zones are given below:

Green – continue site operations and monitoring as normal

Amber – continue site operations with caution, whilst preparing to implement contingency measures/action plan, as detailed in Richard Trant Associates' drawing No. 5295-PM01. Increase monitoring frequency.

Red – stop site operations, do everything possible to slow down deflection and implement contingency/red level action plan, as detailed in Richard Trant Associates' drawing No. 5295-PM01. Install additional temporary works and increase monitoring frequency.

Job No: DFS221011 Design Engineer: AR Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00 Page: 18 of 31

In the unlikely event of measured deflections reaching the amber zone/red zone threshold, the following contingency procedure shall be followed:

- Immediate back-filling of the excavation area up to ground level/capping beam level and immediate notification of project team members.
- Placed back-fill shall be left in place until such a time that monitoring results show no further wall movement.
- No further works shall be carried out on site until stabilisation/remedial works proposals are agreed with project team members.

At this stage, the following contingency/stabilisation measures are envisaged:

- Inspect the already installed temporary struts at capping beam level to confirm that there are no visible signs of distress, distortion, rotation, cracks, deflections or any other serviceability issues on the struts. If any serviceability issues are observed on the props, affected props shall be removed and replaced accordingly before bulk excavation resumes.
- Resume bulk excavation down to 3.0m depth.
- Install 2nd level of props at 2.5m depth, with associated steel waling beams.
- Complete bulk excavation down to basement formation level (4.85m depth).
- Construct basement slab
- Construct ground floor slab
- Remove 2nd level of temporary struts and waling beam at 2.5m depth
- Remove 1st level of temporary struts at capping beam level.

An illustration of the proposed trigger levels is presented in figure 1 below:



Figure 1 – Set Trigger Limits for Structural Movements within the Vicinity of Proposed Basement



Job No: DFS221011 Design Engineer: AR Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain
Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00 Page: 19 of 31

REFERENCES

Adekunte, Sheppard & Rotimi (2020), "Experience-Based Value Engineering of Foundations & Deep Excavation Support Systems". *Proceedings of the Deep Foundations Institute's 46th Annual International Conference on Deep Foundations*, Las Vegas, Nevada USA, October 13-16, 2021.

Adekunte, Greentree, Brunger & Munteanu (2018), "Non-Conventional Practice: Recent Case Histories of the use of Vertical Buttress Piles in Deep Excavation Support". *Paper Verbally Presented and Published in the Proceedings of the Deep Foundations Institute's 43rd Annual International Conference on Deep Foundations*, Anaheim California, USA, October 24-27, 2018.

Adekunte, Hilton & Greentree (2016), "An Alternative Approach for Estimating the Vertical Capacity of L-Shaped Segmental Underpinning Systems in Urban Basement Construction". *Proceedings of the Deep Foundations Institute's International Conference on Deep Foundations, Seepage Control and Remediation*, New York, USA, October 12-15, 2016.

Adekunte (2015), "Collaborative Development of Sustainable & Economical Solutions for Underground Structures". *Proceedings of the Deep Foundations Institute's 40th Annual International Conference on Deep Foundations*, Oakland California, USA, October 12-15, 2015.

Adekunte (2014), "Dealing with Complexities Associated with the Application of Bored Pile Retaining Walls in Urban Developments". *Proceedings of the Deep Foundations Institute's 39th Annual Conference on Deep Foundations*, Atlanta Georgia, USA, October 21-24, 2014.

Adekunte (2014), "An Investigation into the Vertical Axial Capacities & Groundwater Cut-off Capabilities of Secant Pile Walls". *Proceedings of the International Society for Soil Mechanics & Geotechnical Engineering (ISSMGE)'s TC207 International Conference on Soil-Structure Interaction – Underground Structures & Retaining Walls*, St. Petersburg, Russia, June 16-18, 2014.

Borin (2012), "The use of WALLAP in the context of Eurocode 7 (EN 1997-1, Eurocode 7: Geotechnical Design)". Geosolve, UK.

British Standards Institution (1986), "BS 8004 - Code of Practice for Foundations".

British Standards Institution (1997), "BS 8110 - Code of Practice for the Structural Use of Concrete".

British Standards Institution (1999), "BS 5930:1999+A2:2010 - Code of Practice for Site Investigations".



Job No: DFS221011 Design Engineer: AR Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00 Page: 20 of 31

British Standards Institution (2004), "BS EN 1997-1:2004 Eurocode 7 – Geotechnical Design. General Rules (+A1:2013)".

British Standards Institution (2004), "BS EN 1992-1-1:2004+A1:2014 Eurocode 2 – Design of Concrete Structures – General Rules and Rules for Buildings".

British Standards Institution (2006), "PD 6687: 2006 – Background Paper to the UK National Annexes to BS EN 1992-1".

Broms (1964a), "Lateral Resistance of Piles in Cohesionless Soils". *Journal of Soil Mechanics & Foundations Division*. Proceedings of the American Society of Civil Engineers, Vol. 90, pp. 123-156.

Broms (1964b), "Lateral Resistance of Piles in Cohesive Soils". *Journal of Soil Mechanics & Foundations Division*. Proceedings of the American Society of Civil Engineers, Vol. 90, No. SM2, pp. 27-63.

Chin (1970), "Estimation of the Ultimate Load of Piles not carried to Failure". *Proceedings of the 2nd Southeastern Asian Conference on Soil Engineering*, pp. 81-90.

Chin (1971), "Discussion, "Pile Tests. Arkansas River Project". *Journal of the American Society of Civil Engineers*, SMFD, Vol. 97, SM6, pp. 930-932.

CIRIA (1984), "Report No. 104; Design of Retaining Walls Embedded in Stiff Clay".

CIRIA (1999), "Report No. 181; Piled Foundations in Weak Rock".

CIRIA (2003), "Report No. C580; Embedded Retaining Walls - Guidance for Economic Design".

CIRIA (2017), "Report No. C760; Guidance on Embedded Retaining Wall Design".

CIRIA (1995), "Report No. 143 – The Standard Penetration Test (SPT): Methods and Use".

Davisson (1975), "Pile Load Capacity". *Design, Construction and Performance of Deep Foundations*, American Society of Civil Engineers, University of California, Berkeley, California, pp. 1-49.

Federation of Piling Specialists UK (2006), "Handbook on Pile Load Testing".



Job No: DFS221011 Design Engineer: AR Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00 Page: 21 of 31

Fellenius (1980), "The Analysis of Results from Routine Pile Load Tests". *Ground Engineering*, London, Vol. 13(6) pp 19-31.

Gardner (1975), "Considerations in the Design of Drilled Piers". *Design, Construction and Performance of Deep Foundations*, San Francisco, pp. 1-32.

Hassani, Whittaker & Scoble (1980), "Application of the Point Load Index Test to Strength Determination of Rock, Proposals for a New Size Correlation Chart". *Proceedings of the 21st U.S Symposium on Rock Mechanics*. Rolla, MO, 1980.

Institution of Civil Engineers (2016), "ICE Specification for Piling and Embedded Retaining Walls". 2nd Ed.

International Society for Rock Mechanics (1985), "Suggested Methods for Determining Point Load Strength". *International Journal of Rock Mechanics & Mining Sciences*, Vol. 22, pp 51-60.

Kondner (1963), "Hyperbolic Stress-Strain Response of Cohesive Soils". *Journal of the American Society of Civil Engineers*, SMFD, Vol. 89, SM1, pp. 115-143.

Kulhawy (1984), "Limiting Tip and Side Resistance". *Analysis and Design of Pile Foundations*, ASCE National Convention, American Society of Civil Engineers, New York, pp. 80-98.

Leonards & Lovell (1978), "Interpretation of Load Test on High-Capacity Driven Piles". *ASTM Symposium on Behaviour of Deep Foundations*, Special Technical Publication STP 670, pp 388-415.

Martin, Budden & Norman (2016), "Pile Tests to Justify Higher Adhesion Factors in London Clay". *Proceedings of the Institution of Civil Engineers*, Geotechnical Engineering 169, April 2016, Issue G2.

Mokwa & Duncan (2003), "Rotational Restraint of Pile Caps during Lateral Loading". *Journal of Geotechnical and Geoenvironmental Engineering*, American Society of Civil Engineers, September 2003.

O' Rourke (1988), "Rock Index Properties for Geoengineering Design in Underground Development. SME Preprint 88-48, 1988, 5 pp.

Peck, Hanson & Thorburn (1974), "Foundation Engineering". 2nd Ed.



Job No: DFS221011 Design Engineer: AR Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain Secant Pile Retaining Wall & Segmental Underpinning Wall [Rev. 00](#) Page: 22 of 31

Rowe & Armitage (1987a), "Theoretical Solutions for Axial Deformation of Drilled Shafts in Rock". *Canadian Geotechnical Journal*. Vol. 24(1).

Rowe & Armitage (1987b), "A Design Method for Drilled Piers in Soft Rock". *Canadian Geotechnical Journal*. Vol. 24(1).

Taylor, Rose & Gorasia (2013), "Pile and pile group capacity; some findings from centrifuge tests". *International Journal of Geo-Engineering*, 2013, 5(2), pp. 5-15.

Tomlinson (2001), "Foundation Design & Construction". 7th Ed. Pearson Education Limited, 2001.



CALCULATIONS

www.deep-foundations.co.uk

Job No: DFS221011

Design Engineer: AR

Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain
Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00

Page: 23 of 31

APPENDICES



CALCULATIONS

www.deep-foundations.co.uk

Job No: DFS221011

Design Engineer: AR

Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain
Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00

Page: 24 of 31

DFS' Temporary Prop Layout, Typical Sections & Connection Details

HEALTH, SAFETY AND ENVIRONMENT


1. THIS GEO-STRUCTURAL DESIGN HAS BEEN CARRIED OUT AND REVIEWED IN ACCORDANCE WITH THE CONSTRUCTION, DESIGN & MANAGEMENT (CDM) REGULATIONS 2015 AND DOES NOT INCLUDE ANY ABNORMAL RISK ITEM THAT A COMPETENT CONTRACTOR WOULD NOT BE AWARE OF WHEN UNDERTAKING CONSTRUCTION WORKS SHOWN.
2. DFS PILE WALL LAYOUT AND DESIGN ACCOUNT FOR 1:100 VERTICALITY TOLERANCE (WITH CFA DRILLING TECHNIQUE, USING HEAVY DUTY AUGERS), 25mm HORIZONTAL POSITIONAL TOLERANCE (WITH A TEMPORARY GUIDE WALL IN-PLACE) AND 30mm OVER-BREAK IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE ICE SPECIFICATION FOR PILING & EMBEDDED RETAINING WALLS (ICE SPERW, 2015). BASED ON THESE, THERE ARE POTENTIALS FOR PILES IN THE SECANT WALL TO ENCROACH INTO THE PROPOSED BASEMENT AREA BY MAGNITUDES OF UP TO 105mm. IT IS IMPERATIVE THAT THE ARCHITECT, PROJECT STRUCTURAL ENGINEER AND PRINCIPAL CONTRACTOR MAKE ALLOWANCE FOR THIS.
3. THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS MUST CARRY OUT INDEPENDENT RISK ASSESSMENTS THAT ARE APPLICABLE TO THEIR WORKS AND FULLY COMPLY WITH THE ABOVE STATED REGULATION.
4. THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS MUST REVIEW THE SITE-SPECIFIC AND HISTORICAL BOREHOLE LOGS OF THE SITE TO HAVE ADEQUATE KNOWLEDGE OF GROUND CONDITIONS ON THE SITE, PRIOR TO COMMENCEMENT OF WORKS.
5. DURING SITE OPERATIONS, IF OBSERVED GROUND CONDITIONS DIFFER FROM THE GENERALISED STRATIGRAPHY SHOWN IN THIS SET OF DRAWINGS, DFS MUST BE INFORMED IMMEDIATELY.
6. IT IS THE RESPONSIBILITY OF THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS TO ENSURE THAT SITE OPERATIVES ARE COMPETENT AND EXPERIENCED IN THE AREA OF WORKS TO BE UNDERTAKEN.
7. IN ADDITION TO THE RISK/HAZARD TYPICALLY ASSOCIATED WITH THE GROUND ENGINEERING WORKS DETAILED IN THIS DRAWING, ADDITIONAL SITE/WORK-SPECIFIC HAZARDS HAVE BEEN IDENTIFIED THROUGH DESIGN RISK ASSESSMENT. THESE ARE OUTLINED IN 7.1 – 7.4 BELOW. ALL SITE OPERATIONS MUST ACCOUNT FOR ALL USUAL AND SITE/WORK-SPECIFIC HAZARDS.
- 7.1. PILING PLATFORM LEVEL IS UNCONFIRMED AT THIS STAGE. HOWEVER, FOR DESIGN PURPOSE, THE PILING MAT LEVEL FOR THE PERIMETER SECANT PILE WALL AND BEARING PILES IS GENERALLY TAKEN TO BE THE EXISTING GROUND LEVEL IN THE AREA OF PROPOSED WORKS; APPROX. +45.500M OD. NONETHELESS, THE PRINCIPAL CONTRACTOR MUST CONFIRM ACTUAL PILING PLATFORM LEVEL(S) PRIOR TO THE COMMENCEMENT OF PILING WORKS ON THE SITE, SO THAT THE PILE WALL SCHEDULE & BEARING PILE SCHEDULE MAY BE AMENDED ACCORDINGLY.
- 7.2. A REINFORCED CONCRETE CAPPING BEAM MUST BE CONSTRUCTED ON THE PILE WALL, WHILE TEMPORARY PROPS MUST BE INSTALLED AGAINST THE CAPPING BEAM PRIOR TO THE COMMENCEMENT OF BULK EXCAVATION FOR THE NEW BASEMENT.
- 7.3. A TEMPORARY GUIDE WALL MUST BE PUT IN-PLACE PRIOR TO THE INSTALLATION OF SECANT PILE WALL.
- 7.4. IN ADDITION, IT IS IMPERATIVE THAT THE CONCRETE MIX DESIGN FOR THE MALE PILES IN THE SECANT WALL ACCOUNTS FOR 10MM MAXIMUM AGGREGATE SIZE AND SET-RETARDING ADMIXTURES IN ORDER TO EASE THE INSTALLATION OF REINFORCEMENT CAGES INTO CONCRETED DRILLHOLES. REINFORCEMENT CAGE VIBRATORS MAY ALSO BE REQUIRED TO FORCE THE STEEL CAGES DOWN TO THE DESIGN DEPTHS.

SUMMARY OF TEMPORARY PROPPING SCHEME

- * PROP TYPE A: 4 No's. RMD KWIKFORM TUBESHOR 320 x 7.0m MAXIMUM LENGTH CORNER BRACES (6.0m - 7.0m LENGTHS)
- * PROP TYPE B: 2 No's. RMD KWIKFORM TUBESHOR 320 x 12m MAXIMUM LENGTH FLYING STRUTS (10.5m - 12.0m LENGTHS)
- * 850mm WIDE x 650mm DEEP RC CAPPING BEAM ON PERIMETER SECANT PILE WALL (DESIGN BY OTHERS)

RC CAPPING BEAM SHALL BE DESIGNED TO SPAN OVER A MINIMUM LENGTH OF 7.0m UNDER SERVICE HORIZONTAL LOADING OF 50 KN/m IN THE TEMPORARY CONDITION.

RC CRADLES ON UNDERPINNING MINIPILES NOT SHOWN FOR CLARITY



GENERAL ARRANGEMENT OF TEMPORARY PROPPING SCHEME (SCALE 1:75)

IMPORTANT CONSTRUCTION NOTES

1. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS NOTED OTHERWISE.
2. ALL LEVELS ARE IN METRES UNLESS NOTED OTHERWISE.
3. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, ENGINEERS, AND SPECIALISTS LATEST DRAWINGS AND SPECIFICATIONS. ANY DISCREPANCIES MUST BE REPORTED TO DFS, ENGINEER AND ARCHITECT IMMEDIATELY.
4. ONLY FIGURED DIMENSIONS ARE TO BE USED. ANY QUERIES MUST BE REFERRED TO DFS.
5. 50mm COVER TO PILE REINFORCEMENT.
6. STRICT SUPERVISION OF BULK EARTH WORKS IS REQUIRED TO ENSURE THAT EXCAVATIONS DO NOT EXCEED THE DESIGN DEPTH SHOWN IN THESE DRAWINGS (4.85m).
7. SECANT PILE WALL SHALL BE INSTALLED IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE ICE SPECIFICATIONS FOR PILING AND EMBEDDED RETAINING WALLS (ICESPERW, 2016).
8. THE SECANT PILE WALL IS DESIGNED FOR BOTH TEMPORARY AND PERMANENT USE.



DEEP FOUNDATIONS SPECIALISTS LIMITED
2ND FLOOR, THE PORTER BUILDING 1 BRUNEL WAY
SLOUGH SL1 1FG.
TELEPHONE: 01753 396498

CLIENT			
BROXWOOD VIEW LIMITED			
JOB TITLE			
BROXWOOD VIEW, 29 ST. EDMUND'S TERRACE LONDON NW8 7QH			
DRAWING TITLE			
GENERAL ARRANGEMENT OF TEMPORARY PROPPING SCHEME			
DATE			
16 OCT 2022	DESIGNER	AR	AA
DRAWING No.			
DFS221011-07	REV	00	SCALE IS AS SHOWN @ A1

- HEALTH, SAFETY AND ENVIRONMENT
1. THIS GEO-STRUCTURAL DESIGN HAS BEEN CARRIED OUT AND REVIEWED IN ACCORDANCE WITH THE CONSTRUCTION, DESIGN & MANAGEMENT (CDM) REGULATIONS 2015 AND DOES NOT INCLUDE ANY ABNORMAL RISK ITEM THAT A COMPETENT CONTRACTOR WOULD NOT BE AWARE OF WHEN UNDERTAKING CONSTRUCTION WORKS SHOWN.

2. DFS PILE WALL LAYOUT AND DESIGN ACCOUNT FOR 1:100 VERTICALITY TOLERANCE (WITH CFA DRILLING TECHNIQUE, USING HEAVY DUTY AUGERS), 25mm HORIZONTAL POSITIONAL TOLERANCE (WITH A TEMPORARY GUIDE WALL IN-PLACE) AND 30mm OVER-BREAK IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE ICE SPECIFICATION FOR PILING & EMBEDDED RETAINING WALLS (ICE SPERW, 2015). BASED ON THESE, THERE ARE POTENTIALS FOR PILES IN THE SECANT WALL TO ENCROACH INTO THE PROPOSED BASEMENT AREA BY MAGNITUDES OF UP TO 105mm. IT IS IMPERATIVE THAT THE ARCHITECT, PROJECT STRUCTURAL ENGINEER AND PRINCIPAL CONTRACTOR MAKE ALLOWANCE FOR THIS.

3. THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS MUST CARRY OUT INDEPENDENT RISK ASSESSMENTS THAT ARE APPLICABLE TO THEIR WORKS AND FULLY COMPLY WITH THE ABOVE STATED REGULATION.

4. THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS MUST REVIEW THE SITE-SPECIFIC AND HISTORICAL BOREHOLE LOGS OF THE SITE TO HAVE ADEQUATE KNOWLEDGE OF GROUND CONDITIONS ON THE SITE, PRIOR TO COMMENCEMENT OF WORKS.

5. DURING SITE OPERATIONS, IF OBSERVED GROUND CONDITIONS DIFFER FROM THE GENERALISED STRATIGRAPHY SHOWN IN THIS SET OF DRAWINGS, DFS MUST BE INFORMED IMMEDIATELY.

6. IT IS THE RESPONSIBILITY OF THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS TO ENSURE THAT SITE OPERATIVES ARE COMPETENT AND EXPERIENCED IN THE AREA OF WORKS TO BE UNDERTAKEN.


7. IN ADDITION TO THE RISK/HAZARD TYPICALLY ASSOCIATED WITH THE GROUND ENGINEERING WORKS DETAILED IN THIS DRAWING, ADDITIONAL SITE/WORK-SPECIFIC HAZARDS HAVE BEEN IDENTIFIED THROUGH DESIGN RISK ASSESSMENT. THESE ARE OUTLINED IN 7.1 – 7.4 BELOW. ALL SITE OPERATIONS MUST ACCOUNT FOR ALL USUAL AND SITE/WORK-SPECIFIC HAZARDS.

7.1. PILING PLATFORM LEVEL IS UNCONFIRMED AT THIS STAGE. HOWEVER, FOR DESIGN PURPOSE, THE PILING MAT LEVEL FOR THE PERIMETER SECANT PILE WALL AND BEARING PILES IS GENERALLY TAKEN TO BE THE EXISTING GROUND LEVEL IN THE AREA OF PROPOSED WORKS; APPROX. +45.500M OD. NONETHELESS, THE PRINCIPAL CONTRACTOR MUST CONFIRM ACTUAL PILING PLATFORM LEVEL(S) PRIOR TO THE COMMENCEMENT OF PILING WORKS ON THE SITE, SO THAT THE PILE WALL SCHEDULE & BEARING PILE SCHEDULE MAY BE AMENDED ACCORDINGLY.

7.2. A REINFORCED CONCRETE CAPPING BEAM MUST BE CONSTRUCTED ON THE PILE WALL, WHILE TEMPORARY PROPS MUST BE INSTALLED AGAINST THE CAPPING BEAM PRIOR TO THE COMMENCEMENT OF BULK EXCAVATION FOR THE NEW BASEMENT.

7.3. A TEMPORARY GUIDE WALL MUST BE PUT IN-PLACE PRIOR TO THE INSTALLATION OF SECANT PILE WALL.

7.4. IN ADDITION, IT IS IMPERATIVE THAT THE CONCRETE MIX DESIGN FOR THE MALE PILES IN THE SECANT WALL ACCOUNTS FOR 10MM MAXIMUM AGGREGATE SIZE AND SET-RETARDING ADMIXTURES IN ORDER TO EASE THE INSTALLATION OF REINFORCEMENT CAGES INTO CONCRETED DRILLHOLES. REINFORCEMENT CAGE VIBRATORS MAY ALSO BE REQUIRED TO FORCE THE STEEL CAGES DOWN TO THE DESIGN DEPTHS.



DETAIL A: CAPPING BEAM - TEMPORARY PROP CONNECTION DETAILS

- IMPORTANT CONSTRUCTION NOTES
1. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS NOTED OTHERWISE.

2. ALL LEVELS ARE IN METRES UNLESS NOTED OTHERWISE.

3. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, ENGINEERS, AND SPECIALISTS LATEST DRAWINGS AND SPECIFICATIONS. ANY DISCREPANCIES MUST BE REPORTED TO DFS, ENGINEER AND ARCHITECT IMMEDIATELY.

4. ONLY FIGURED DIMENSIONS ARE TO BE USED. ANY QUERIES MUST BE REFERRED TO DFS.

5. 50mm COVER TO PILE REINFORCEMENT.

6. STRICT SUPERVISION OF BULK EARTH WORKS IS REQUIRED TO ENSURE THAT EXCAVATIONS DO NOT EXCEED THE DESIGN DEPTH SHOWN IN THESE DRAWINGS (4.85m).

7. SECANT PILE WALL SHALL BE INSTALLED IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE ICE SPECIFICATIONS FOR PILING AND EMBEDDED RETAINING WALLS (ICESPERW, 2016).

8. THE SECANT PILE WALL IS DESIGNED FOR BOTH TEMPORARY AND PERMANENT USE.

DFS

DEEP FOUNDATIONS SPECIALISTS LIMITED
2ND FLOOR, THE PORTER BUILDING 1 BRUNEL WAY
SLOUGH SL1 1FQ.
TELEPHONE: 01753 396498

CLIENT

BROXWOOD VIEW LIMITED

PROJECT

BROXWOOD VIEW, 29 ST. EDMUND'S TERRACE LONDON NW8 7QH

DRAWING TITLE

DETAIL A: CAPPING BEAM - TEMPORARY PROP CONNECTION DETAILS

DATE

16 OCT 2022

DESIGN

AR

CHECKED

AA

DRAWING No.

DFS221011-09

REV


00

SCALE

SCALE IS AS SHOWN @ A1

- HEALTH, SAFETY AND ENVIRONMENT
- THIS GEO-STRUCTURAL DESIGN HAS BEEN CARRIED OUT AND REVIEWED IN ACCORDANCE WITH THE CONSTRUCTION, DESIGN & MANAGEMENT (CDM) REGULATIONS 2015 AND DOES NOT INCLUDE ANY ABNORMAL RISK ITEM THAT A COMPETENT CONTRACTOR WOULD NOT BE AWARE OF WHEN UNDERTAKING CONSTRUCTION WORKS SHOWN.
 - DFS PILE WALL LAYOUT AND DESIGN ACCOUNT FOR 1:100 VERTICALITY TOLERANCE (WITH CFA DRILLING TECHNIQUE, USING HEAVY DUTY AUGERS), 25mm HORIZONTAL POSITIONAL TOLERANCE (WITH A TEMPORARY GUIDE WALL IN-PLACE) AND 30mm OVER-BREAK IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE ICE SPECIFICATION FOR PILING & EMBEDDED RETAINING WALLS (ICE SPERW, 2015). BASED ON THESE, THERE ARE POTENTIALS FOR PILES IN THE SECANT WALL TO ENCROACH INTO THE PROPOSED BASEMENT AREA BY MAGNITUDES OF UP TO 105mm. IT IS IMPERATIVE THAT THE ARCHITECT, PROJECT STRUCTURAL ENGINEER AND PRINCIPAL CONTRACTOR MAKE ALLOWANCE FOR THIS.
 - THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS MUST CARRY OUT INDEPENDENT RISK ASSESSMENTS THAT ARE APPLICABLE TO THEIR WORKS AND FULLY COMPLY WITH THE ABOVE STATED REGULATION.
 - THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS MUST REVIEW THE SITE-SPECIFIC AND HISTORICAL BOREHOLE LOGS OF THE SITE TO HAVE ADEQUATE KNOWLEDGE OF GROUND CONDITIONS ON THE SITE, PRIOR TO COMMENCEMENT OF WORKS.
 - DURING SITE OPERATIONS, IF OBSERVED GROUND CONDITIONS DIFFER FROM THE GENERALISED STRATIGRAPHY SHOWN IN THIS SET OF DRAWINGS, DFS MUST BE INFORMED IMMEDIATELY.
 - IT IS THE RESPONSIBILITY OF THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS TO ENSURE THAT SITE OPERATIVES ARE COMPETENT AND EXPERIENCED IN THE AREA OF WORKS TO BE UNDERTAKEN.
 - IN ADDITION TO THE RISK/HAZARD TYPICALLY ASSOCIATED WITH THE GROUND ENGINEERING WORKS DETAILED IN THIS DRAWING, ADDITIONAL SITE/WORK-SPECIFIC HAZARDS HAVE BEEN IDENTIFIED THROUGH DESIGN RISK ASSESSMENT. THESE ARE OUTLINED IN 7.1 – 7.4 BELOW. ALL SITE OPERATIONS MUST ACCOUNT FOR ALL USUAL AND SITE/WORK-SPECIFIC HAZARDS.
 1. PILING PLATFORM LEVEL IS UNCONFIRMED AT THIS STAGE. HOWEVER, FOR DESIGN PURPOSE, THE PILING MAT LEVEL FOR THE PERIMETER SECANT PILE WALL AND BEARING PILES IS GENERALLY TAKEN TO BE THE EXISTING GROUND LEVEL IN THE AREA OF PROPOSED WORKS; APPROX. +45.500M OD. NONETHELESS, THE PRINCIPAL CONTRACTOR MUST CONFIRM ACTUAL PILING PLATFORM LEVEL(S) PRIOR TO THE COMMENCEMENT OF PILING WORKS ON THE SITE, SO THAT THE PILE WALL SCHEDULE & BEARING PILE SCHEDULE MAY BE AMENDED ACCORDINGLY.
 2. A REINFORCED CONCRETE CAPPING BEAM MUST BE CONSTRUCTED ON THE PILE WALL, WHILE TEMPORARY PROPS MUST BE INSTALLED AGAINST THE CAPPING BEAM PRIOR TO THE COMMENCEMENT OF BULK EXCAVATION FOR THE NEW BASEMENT.
 3. A TEMPORARY GUIDE WALL MUST BE PUT IN-PLACE PRIOR TO THE INSTALLATION OF SECANT PILE WALL.
 4. IN ADDITION, IT IS IMPERATIVE THAT THE CONCRETE MIX DESIGN FOR THE MALE PILES IN THE SECANT WALL ACCOUNTS FOR 10MM MAXIMUM AGGREGATE SIZE AND SET-RETARDING ADMIXTURES IN ORDER TO EASE THE INSTALLATION OF REINFORCEMENT CAGES INTO CONCRETED DRILLHOLES. REINFORCEMENT CAGE VIBRATORS MAY ALSO BE REQUIRED TO FORCE THE STEEL CAGES DOWN TO THE DESIGN DEPTHS.

RC UNDERPINNING WALL



DETAIL B: RC SEGMENTAL UNDERPINNING WALL - WALING BEAM - ENDPLATE - TEMPORARY PROP CONNECTION DETAILS

IMPORTANT CONSTRUCTION NOTES

- ALL DIMENSIONS ARE IN MILLIMETERS UNLESS NOTED OTHERWISE.
- ALL LEVELS ARE IN METRES UNLESS NOTED OTHERWISE.
- THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, ENGINEERS, AND SPECIALISTS LATEST DRAWINGS AND SPECIFICATIONS. ANY DISCREPANCIES MUST BE REPORTED TO DFS, ENGINEER AND ARCHITECT IMMEDIATELY.
- ONLY FIGURED DIMENSIONS ARE TO BE USED. ANY QUERIES MUST BE REFERRED TO DFS.
- 50mm COVER TO PILE REINFORCEMENT.
- STRICT SUPERVISION OF BULK EARTH WORKS IS REQUIRED TO ENSURE THAT EXCAVATIONS DO NOT EXCEED THE DESIGN DEPTH SHOWN IN THESE DRAWINGS (4.85m).
- SECANT PILE WALL SHALL BE INSTALLED IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE ICE SPECIFICATIONS FOR PILING AND EMBEDDED RETAINING WALLS (ICESPERW, 2016).
- THE SECANT PILE WALL IS DESIGNED FOR BOTH TEMPORARY AND PERMANENT USE.



DEEP FOUNDATIONS SPECIALISTS LIMITED
2ND FLOOR, THE PORTER BUILDING 1 BRUNEL WAY
SLOUGH SL1 1FD.
TELEPHONE: 01753 396498

CLIENT			
BROXWOOD VIEW LIMITED			
PROJECT			
BROXWOOD VIEW, 29 ST. EDMUND'S TERRACE LONDON NW8 7QH			
DRAWING TITLE			
DETAIL B: RC UNDERPINNING - WALING BEAM - ENDPLATE - TEMPORARY PROP CONNECTION DETAILS			
DATE			
16 OCT 2022	DESIGN	AR	AA
DRAWING No.			
DFS221011-10	REV	00	SCALE IS AS SHOWN @ A1



CALCULATIONS

www.deep-foundations.co.uk

Job No: DFS221011

Design Engineer: AR

Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH


Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain
Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00

Page: 25 of 31


DFS' Construction Sequencing Drawings

HEALTH, SAFETY AND ENVIRONMENT


1. THIS GEO-STRUCTURAL DESIGN HAS BEEN CARRIED OUT AND REVIEWED IN ACCORDANCE WITH THE CONSTRUCTION, DESIGN & MANAGEMENT (CDM) REGULATIONS 2015 AND DOES NOT INCLUDE ANY ABNORMAL RISK ITEM THAT A COMPETENT CONTRACTOR WOULD NOT BE AWARE OF WHEN UNDERTAKING CONSTRUCTION WORKS SHOWN.
2. DFS PILE WALL LAYOUT AND DESIGN ACCOUNT FOR 1:100 VERTICALITY TOLERANCE (WITH CFA DRILLING TECHNIQUE, USING HEAVY DUTY AUGERS), 25mm HORIZONTAL POSITIONAL TOLERANCE (WITH A TEMPORARY GUIDE WALL IN-PLACE) AND 30mm OVER-BREAK IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE ICE SPECIFICATION FOR PILING & EMBEDDED RETAINING WALLS (ICE SPERW, 2015). BASED ON THESE, THERE ARE POTENTIALS FOR PILES IN THE SECANT WALL TO ENCROACH INTO THE PROPOSED BASEMENT AREA BY MAGNITUDES OF UP TO 105mm. IT IS IMPERATIVE THAT THE ARCHITECT, PROJECT STRUCTURAL ENGINEER AND PRINCIPAL CONTRACTOR MAKE ALLOWANCE FOR THIS.
3. THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS MUST CARRY OUT INDEPENDENT RISK ASSESSMENTS THAT ARE APPLICABLE TO THEIR WORKS AND FULLY COMPLY WITH THE ABOVE STATED REGULATION.
4. THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS MUST REVIEW THE SITE-SPECIFIC AND HISTORICAL BOREHOLE LOGS OF THE SITE TO HAVE ADEQUATE KNOWLEDGE OF GROUND CONDITIONS ON THE SITE, PRIOR TO COMMENCEMENT OF WORKS.
5. DURING SITE OPERATIONS, IF OBSERVED GROUND CONDITIONS DIFFER FROM THE GENERALISED STRATIGRAPHY SHOWN IN THIS SET OF DRAWINGS, DFS MUST BE INFORMED IMMEDIATELY.
6. IT IS THE RESPONSIBILITY OF THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS TO ENSURE THAT SITE OPERATIVES ARE COMPETENT AND EXPERIENCED IN THE AREA OF WORKS TO BE UNDERTAKEN.
7. IN ADDITION TO THE RISK/HAZARD TYPICALLY ASSOCIATED WITH THE GROUND ENGINEERING WORKS DETAILED IN THIS DRAWING, ADDITIONAL SITE/WORK-SPECIFIC HAZARDS HAVE BEEN IDENTIFIED THROUGH DESIGN RISK ASSESSMENT. THESE ARE OUTLINED IN 7.1 – 7.4 BELOW. ALL SITE OPERATIONS MUST ACCOUNT FOR ALL USUAL AND SITE/WORK-SPECIFIC HAZARDS.
- 7.1. PILING PLATFORM LEVEL IS UNCONFIRMED AT THIS STAGE. HOWEVER, FOR DESIGN PURPOSE, THE PILING MAT LEVEL FOR THE PERIMETER SECANT PILE WALL AND BEARING PILES IS GENERALLY TAKEN TO BE THE EXISTING GROUND LEVEL IN THE AREA OF PROPOSED WORKS; APPROX. +45.500M OD. NONETHELESS, THE PRINCIPAL CONTRACTOR MUST CONFIRM ACTUAL PILING PLATFORM LEVEL(S) PRIOR TO THE COMMENCEMENT OF PILING WORKS ON THE SITE, SO THAT THE PILE WALL SCHEDULE & BEARING PILE SCHEDULE MAY BE AMENDED ACCORDINGLY.
- 7.2. A REINFORCED CONCRETE CAPPING BEAM MUST BE CONSTRUCTED ON THE PILE WALL, WHILE TEMPORARY PROPS MUST BE INSTALLED AGAINST THE CAPPING BEAM PRIOR TO THE COMMENCEMENT OF BULK EXCAVATION FOR THE NEW BASEMENT.
- 7.3. A TEMPORARY GUIDE WALL MUST BE PUT IN-PLACE PRIOR TO THE INSTALLATION OF SECANT PILE WALL.
- 7.4. IN ADDITION, IT IS IMPERATIVE THAT THE CONCRETE MIX DESIGN FOR THE MALE PILES IN THE SECANT WALL ACCOUNTS FOR 10MM MAXIMUM AGGREGATE SIZE AND SET-RETARDING ADMIXTURES IN ORDER TO EASE THE INSTALLATION OF REINFORCEMENT CAGES INTO CONCRETED DRILLHOLES. REINFORCEMENT CAGE VIBRATORS MAY ALSO BE REQUIRED TO FORCE THE STEEL CAGES DOWN TO THE DESIGN DEPTHS.




STAGE 0:
PRE-PILING SITE CONDITIONS



STAGE 2:
CONCURRENTLY INSTALL Ø450 INTERLOCKING MALE AND FEMALE PILES BY CFA DRILLING TECHNIQUE, WITH MALE PILES SPACED @ 600MM C/C, FROM PILING PLATFORM LEVEL (+45.500) TO DEPTHS SPECIFIED BY DFS, TO FORM SECANT PILE WALL, AS WELL AS THE Ø350 BEARING PILES REQUIRED FOR THE PROPOSED UNDERPINNING WORKS UNDERNEATH THE EXISTING NORTHERN WALL OF BARRIE HOUSE.



STAGE 1:
STRIP THE EXISTING GROUND AND SUBSEQUENTLY PLACE AND COMPACT PILING MAT IN THE AREA OF PROPOSED PILING WORKS.



STAGE 3:
BREAK DOWN PILES TO 75MM ABOVE PROPOSED SOFFIT LEVEL OF RC CAPPING BEAM AND CONSTRUCT RC CAPPING BEAM ON PILES.

IMPORTANT CONSTRUCTION NOTES

1. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS NOTED OTHERWISE.
2. ALL LEVELS ARE IN METRES UNLESS NOTED OTHERWISE.
3. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, ENGINEERS, AND SPECIALISTS LATEST DRAWINGS AND SPECIFICATIONS. ANY DISCREPANCIES MUST BE REPORTED TO DFS, ENGINEER AND ARCHITECT IMMEDIATELY.
4. ONLY FIGURED DIMENSIONS ARE TO BE USED. ANY QUERIES MUST BE REFERRED TO DFS.
5. 50mm COVER TO PILE REINFORCEMENT.
6. STRICT SUPERVISION OF BULK EARTH WORKS IS REQUIRED TO ENSURE THAT EXCAVATIONS DO NOT EXCEED THE DESIGN DEPTH SHOWN IN THESE DRAWINGS (4.85m).
7. SECANT PILE WALL SHALL BE INSTALLED IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE ICE SPECIFICATIONS FOR PILING AND EMBEDDED RETAINING WALLS (ICESPERW, 2016).
8. THE SECANT PILE WALL IS DESIGNED FOR BOTH TEMPORARY AND PERMANENT USE.



DEEP FOUNDATIONS SPECIALISTS LIMITED
2nd FLOOR, THE PORTER BUILDING 1 BRUNEL WAY
SLOUGH SL1 1PQ.
TELEPHONE: 01753 396498

CLIENT	BROXWOOD VIEW LIMITED
JOB TITLE	BROXWOOD VIEW, 29 ST. EDMUND'S TERRACE LONDON NW8 7QH
DRAWING TITLE	


PROPOSED CONSTRUCTION SEQUENCE SHEET -1

DATE	16 OCT 2022	DRAWN	AR	CHECKED	AA
DRAWING No	DFS221011-03	REV	00	SCALE	SCALE IS AS SHOWN @ A1

HEALTH, SAFETY AND ENVIRONMENT


1. THIS GEO-STRUCTURAL DESIGN HAS BEEN CARRIED OUT AND REVIEWED IN ACCORDANCE WITH THE CONSTRUCTION, DESIGN & MANAGEMENT (CDM) REGULATIONS 2015 AND DOES NOT INCLUDE ANY ABNORMAL RISK ITEM THAT A COMPETENT CONTRACTOR WOULD NOT BE AWARE OF WHEN UNDERTAKING CONSTRUCTION WORKS SHOWN.
2. DFS PILE WALL LAYOUT AND DESIGN ACCOUNT FOR 1:100 VERTICALITY TOLERANCE (WITH CFA DRILLING TECHNIQUE, USING HEAVY DUTY AUGERS), 25mm HORIZONTAL POSITIONAL TOLERANCE (WITH A TEMPORARY GUIDE WALL IN-PLACE) AND 30mm OVER-BREAK IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE ICE SPECIFICATION FOR PILING & EMBEDDED RETAINING WALLS (ICE SPERW, 2015). BASED ON THESE, THERE ARE POTENTIALS FOR PILES IN THE SECANT WALL TO ENCROACH INTO THE PROPOSED BASEMENT AREA BY MAGNITUDES OF UP TO 105mm. IT IS IMPERATIVE THAT THE ARCHITECT, PROJECT STRUCTURAL ENGINEER AND PRINCIPAL CONTRACTOR MAKE ALLOWANCE FOR THIS.
3. THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS MUST CARRY OUT INDEPENDENT RISK ASSESSMENTS THAT ARE APPLICABLE TO THEIR WORKS AND FULLY COMPLY WITH THE ABOVE STATED REGULATION.
4. THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS MUST REVIEW THE SITE-SPECIFIC AND HISTORICAL BOREHOLE LOGS OF THE SITE TO HAVE ADEQUATE KNOWLEDGE OF GROUND CONDITIONS ON THE SITE, PRIOR TO COMMENCEMENT OF WORKS.
5. DURING SITE OPERATIONS, IF OBSERVED GROUND CONDITIONS DIFFER FROM THE GENERALISED STRATIGRAPHY SHOWN IN THIS SET OF DRAWINGS, DFS MUST BE INFORMED IMMEDIATELY.
6. IT IS THE RESPONSIBILITY OF THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS TO ENSURE THAT SITE OPERATIVES ARE COMPETENT AND EXPERIENCED IN THE AREA OF WORKS TO BE UNDERTAKEN.
7. IN ADDITION TO THE RISK/HAZARD TYPICALLY ASSOCIATED WITH THE GROUND ENGINEERING WORKS DETAILED IN THIS DRAWING, ADDITIONAL SITE/WORK-SPECIFIC HAZARDS HAVE BEEN IDENTIFIED THROUGH DESIGN RISK ASSESSMENT. THESE ARE OUTLINED IN 7.1 – 7.4 BELOW. ALL SITE OPERATIONS MUST ACCOUNT FOR ALL USUAL AND SITE/WORK-SPECIFIC HAZARDS.

- 7.1. PILING PLATFORM LEVEL IS UNCONFIRMED AT THIS STAGE. HOWEVER, FOR DESIGN PURPOSE, THE PILING MAT LEVEL FOR THE PERIMETER SECANT PILE WALL AND BEARING PILES IS GENERALLY TAKEN TO BE THE EXISTING GROUND LEVEL IN THE AREA OF PROPOSED WORKS; APPROX. +45.500M OD. NONETHELESS, THE PRINCIPAL CONTRACTOR MUST CONFIRM ACTUAL PILING PLATFORM LEVEL(S) PRIOR TO THE COMMENCEMENT OF PILING WORKS ON THE SITE, SO THAT THE PILE WALL SCHEDULE & BEARING PILE SCHEDULE MAY BE AMENDED ACCORDINGLY.
- 7.2. A REINFORCED CONCRETE CAPPING BEAM MUST BE CONSTRUCTED ON THE PILE WALL, WHILE TEMPORARY PROPS MUST BE INSTALLED AGAINST THE CAPPING BEAM PRIOR TO THE COMMENCEMENT OF BULK EXCAVATION FOR THE NEW BASEMENT.
- 7.3. A TEMPORARY GUIDE WALL MUST BE PUT IN-PLACE PRIOR TO THE INSTALLATION OF SECANT PILE WALL.
- 7.4. IN ADDITION, IT IS IMPERATIVE THAT THE CONCRETE MIX DESIGN FOR THE MALE PILES IN THE SECANT WALL ACCOUNTS FOR 10MM MAXIMUM AGGREGATE SIZE AND SET-RETARDING ADMIXTURES IN ORDER TO EASE THE INSTALLATION OF REINFORCEMENT CAGES INTO CONCRETED DRILLHOLES. REINFORCEMENT CAGE VIBRATORS MAY ALSO BE REQUIRED TO FORCE THE STEEL CAGES DOWN TO THE DESIGN DEPTHS.




STAGE 4:

CARRY OUT SEGMENTAL UNDERPINNING OF THE EXISTING PAD AND STRIP FOOTINGS UNDERNEATH THE NORTHERN WALL OF THE EXISTING BARRIE HOUSE BUILDING, AS DETAILED BY THE PROJECT STRUCTURAL ENGINEER (SEE RICHARD TANT ASSOCIATES' DRAWING NO'S 5295-P02, 5295-P04, 5295-P13, 5295-P15, 5295-P17, 5295-P18, 5295-P19, 5295-PSM01 & 5295-PSM02).




STAGE 5:

INSTALL TEMPORARY STRUCTURAL STEEL WALING BEAM & TEMPORARY PROPS ALONG THE FACE OF SEGMENTAL UNDERPINNING RETAINING WALL AROUND CREST LEVEL.



STAGE 6:

INSTALL TEMPORARY PROPS AT CAPPING BEAM LEVEL OF PILE WALL.



STAGE 7:

CARRY OUT BULK EXCAVATION DOWN TO BASEMENT FORMATION LEVEL; 4.85M MAXIMUM DIG.

IMPORTANT CONSTRUCTION NOTES

1. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS NOTED OTHERWISE.
2. ALL LEVELS ARE IN METRES UNLESS NOTED OTHERWISE.
3. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, ENGINEERS, AND SPECIALISTS LATEST DRAWINGS AND SPECIFICATIONS. ANY DISCREPANCIES MUST BE REPORTED TO DFS, ENGINEER AND ARCHITECT IMMEDIATELY.
4. ONLY FIGURED DIMENSIONS ARE TO BE USED. ANY QUERIES MUST BE REFERRED TO DFS.
5. 50mm COVER TO PILE REINFORCEMENT.
6. STRICT SUPERVISION OF BULK EARTH WORKS IS REQUIRED TO ENSURE THAT EXCAVATIONS DO NOT EXCEED THE DESIGN DEPTH SHOWN IN THESE DRAWINGS (4.85m).
7. SECANT PILE WALL SHALL BE INSTALLED IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE ICE SPECIFICATIONS FOR PILING AND EMBEDDED RETAINING WALLS (ICESPERW, 2016).
8. THE SECANT PILE WALL IS DESIGNED FOR BOTH TEMPORARY AND PERMANENT USE.



DEEP FOUNDATIONS SPECIALISTS LIMITED
2nd FLOOR, THE PORTER BUILDING 1 BRUNEL WAY
SLOUGH SL1 1PQ.
TELEPHONE: 01753 396498

CLIENT

BROXWOOD VIEW LIMITED

JOB TITLE

BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH


DRAWING TITLE

PROPOSED CONSTRUCTION SEQUENCE SHEET :2

DATE	16 OCT 2022	DRAWN	AR	CHECKED	AA
DRAWING NO	DFS221011-04	REV	00	SCALE	SCALE IS AS SHOWN @ A1


HEALTH, SAFETY AND ENVIRONMENT

1. THIS GEO-STRUCTURAL DESIGN HAS BEEN CARRIED OUT AND REVIEWED IN ACCORDANCE WITH THE CONSTRUCTION, DESIGN & MANAGEMENT (CDM) REGULATIONS 2015 AND DOES NOT INCLUDE ANY ABNORMAL RISK ITEM THAT A COMPETENT CONTRACTOR WOULD NOT BE AWARE OF WHEN UNDERTAKING CONSTRUCTION WORKS SHOWN.
2. DFS PILE WALL LAYOUT AND DESIGN ACCOUNT FOR 1:100 VERTICALITY TOLERANCE (WITH CFA DRILLING TECHNIQUE, USING HEAVY DUTY AUGERS), 25mm HORIZONTAL POSITIONAL TOLERANCE (WITH A TEMPORARY GUIDE WALL IN-PLACE) AND 30mm OVER-BREAK IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE ICE SPECIFICATION FOR PILING & EMBEDDED RETAINING WALLS (ICE SPERW, 2015). BASED ON THESE, THERE ARE POTENTIALS FOR PILES IN THE SECANT WALL TO ENCROACH INTO THE PROPOSED BASEMENT AREA BY MAGNITUDES OF UP TO 105mm. IT IS IMPERATIVE THAT THE ARCHITECT, PROJECT STRUCTURAL ENGINEER AND PRINCIPAL CONTRACTOR MAKE ALLOWANCE FOR THIS.
3. THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS MUST CARRY OUT INDEPENDENT RISK ASSESSMENTS THAT ARE APPLICABLE TO THEIR WORKS AND FULLY COMPLY WITH THE ABOVE STATED REGULATION.
4. THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS MUST REVIEW THE SITE-SPECIFIC AND HISTORICAL BOREHOLE LOGS OF THE SITE TO HAVE ADEQUATE KNOWLEDGE OF GROUND CONDITIONS ON THE SITE, PRIOR TO COMMENCEMENT OF WORKS.
5. DURING SITE OPERATIONS, IF OBSERVED GROUND CONDITIONS DIFFER FROM THE GENERALISED STRATIGRAPHY SHOWN IN THIS SET OF DRAWINGS, DFS MUST BE INFORMED IMMEDIATELY.
6. IT IS THE RESPONSIBILITY OF THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS TO ENSURE THAT SITE OPERATIVES ARE COMPETENT AND EXPERIENCED IN THE AREA OF WORKS TO BE UNDERTAKEN.
7. IN ADDITION TO THE RISK/HAZARD TYPICALLY ASSOCIATED WITH THE GROUND ENGINEERING WORKS DETAILED IN THIS DRAWING, ADDITIONAL SITE/WORK-SPECIFIC HAZARDS HAVE BEEN IDENTIFIED THROUGH DESIGN RISK ASSESSMENT. THESE ARE OUTLINED IN 7.1 – 7.4 BELOW. ALL SITE OPERATIONS MUST ACCOUNT FOR ALL USUAL AND SITE/WORK-SPECIFIC HAZARDS.
 - 7.1. PILING PLATFORM LEVEL IS UNCONFIRMED AT THIS STAGE. HOWEVER, FOR DESIGN PURPOSE, THE PILING MAT LEVEL FOR THE PERIMETER SECANT PILE WALL AND BEARING PILES IS GENERALLY TAKEN TO BE THE EXISTING GROUND LEVEL IN THE AREA OF PROPOSED WORKS; APPROX. +45.500M OD. NONETHELESS, THE PRINCIPAL CONTRACTOR MUST CONFIRM ACTUAL PILING PLATFORM LEVEL(S) PRIOR TO THE COMMENCEMENT OF PILING WORKS ON THE SITE, SO THAT THE PILE WALL SCHEDULE & BEARING PILE SCHEDULE MAY BE AMENDED ACCORDINGLY.
 - 7.2. A REINFORCED CONCRETE CAPPING BEAM MUST BE CONSTRUCTED ON THE PILE WALL, WHILE TEMPORARY PROPS MUST BE INSTALLED AGAINST THE CAPPING BEAM PRIOR TO THE COMMENCEMENT OF BULK EXCAVATION FOR THE NEW BASEMENT.
 - 7.3. A TEMPORARY GUIDE WALL MUST BE PUT IN-PLACE PRIOR TO THE INSTALLATION OF SECANT PILE WALL.
 - 7.4. IN ADDITION, IT IS IMPERATIVE THAT THE CONCRETE MIX DESIGN FOR THE MALE PILES IN THE SECANT WALL ACCOUNTS FOR 10MM MAXIMUM AGGREGATE SIZE AND SET-RETARDING ADMIXTURES IN ORDER TO EASE THE INSTALLATION OF REINFORCEMENT CAGES INTO CONCRETED DRILLHOLES. REINFORCEMENT CAGE VIBRATORS MAY ALSO BE REQUIRED TO FORCE THE STEEL CAGES DOWN TO THE DESIGN DEPTHS.




STAGE 8:

PLACE BLINDING OF 50mm MINIMUM THICKNESS AT FORMATION LEVEL
AND SHOTCRETE 105mm PILE INSTALLATION TOLERANCE ZONE, IN
PREPARATION FOR THE INSTALLATION OF WATER-PROOFING MEMBRANE.




STAGE 9:

INSTALL/FIX WATER-PROOF MEMBRANE ON PLACED BLINDING,
AS WELL AS FACE OF PILE RETAINING WALL/SEGMENTAL
UNDERPINNING WALL AND WRAP AROUND CAPPING BEAM.



STAGE 10:

CONSTRUCT 600MM THICK REINFORCED CONCRETE RAFT/LOWER
GROUND FLOOR SLAB WITH WATER-PROOF CONCRETE AND DOWEL INTO
PILE RETAINING WALL/SEGMENTAL UNDERPINNING WALL, WHILST MAKING
ALLOWANCE FOR CAVITY DRAIN IN FRONT OF RETAINING WALLS.



STAGE 11:

CONSTRUCT RC LINER WALL OF 250MM MINIMUM THICKNESS WITH
WATER-PROOF CONCRETE, IN FRONT OF PILE RETAINING WALL AND
SEGMENTAL UNDERPINNING WALL FROM BASEMENT LEVEL, UP TO
CAPPING BEAM SOFFIT LEVEL AND CONNECT SAME TO CAPPING BEAM.

IMPORTANT CONSTRUCTION
NOTES

1. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS NOTED OTHERWISE.
2. ALL LEVELS ARE IN METRES UNLESS NOTED OTHERWISE.
3. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, ENGINEERS, AND SPECIALISTS LATEST DRAWINGS AND SPECIFICATIONS. ANY DISCREPANCIES MUST BE REPORTED TO DFS, ENGINEER AND ARCHITECT IMMEDIATELY.
4. ONLY FIGURED DIMENSIONS ARE TO BE USED. ANY QUERIES MUST BE REFERRED TO DFS.
5. 50mm COVER TO PILE REINFORCEMENT.
6. STRICT SUPERVISION OF BULK EARTH WORKS IS REQUIRED TO ENSURE THAT EXCAVATIONS DO NOT EXCEED THE DESIGN DEPTH SHOWN IN THESE DRAWINGS (4.85m).
7. SECANT PILE WALL SHALL BE INSTALLED IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE ICE SPECIFICATIONS FOR PILING AND EMBEDDED RETAINING WALLS (ICESPERW, 2016).
8. THE SECANT PILE WALL IS DESIGNED FOR BOTH TEMPORARY AND PERMANENT USE.



DEEP FOUNDATIONS SPECIALISTS LIMITED
2nd FLOOR, THE PORTER BUILDING 1 BRUNEL WAY
SLOUGH SL1 1FQ.
TELEPHONE: 01753 396498

CLIENT

BROXWOOD VIEW LIMITED

JOB TITLE

BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH


DRAWING TITLE

PROPOSED CONSTRUCTION SEQUENCE SHEET 3


DATE	16 OCT 2022	DRAWN	AR	CHECKED	AA
DRAWING NO.	DFS221011-05	REV	00	SCALE	SCALE IS AS SHOWN @ A1

HEALTH, SAFETY AND ENVIRONMENT

1. THIS GEO-STRUCTURAL DESIGN HAS BEEN CARRIED OUT AND REVIEWED IN ACCORDANCE WITH THE CONSTRUCTION, DESIGN & MANAGEMENT (CDM) REGULATIONS 2015 AND DOES NOT INCLUDE ANY ABNORMAL RISK ITEM THAT A COMPETENT CONTRACTOR WOULD NOT BE AWARE OF WHEN UNDERTAKING CONSTRUCTION WORKS SHOWN.
2. DFS PILE WALL LAYOUT AND DESIGN ACCOUNT FOR 1:100 VERTICALITY TOLERANCE (WITH CFA DRILLING TECHNIQUE, USING HEAVY DUTY AUGERS), 25mm HORIZONTAL POSITIONAL TOLERANCE (WITH A TEMPORARY GUIDE WALL IN-PLACE) AND 30mm OVER-BREAK IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE ICE SPECIFICATION FOR PILING & EMBEDDED RETAINING WALLS (ICE SPERW, 2015). BASED ON THESE, THERE ARE POTENTIALS FOR PILES IN THE SECANT WALL TO ENCROACH INTO THE PROPOSED BASEMENT AREA BY MAGNITUDES OF UP TO 105mm. IT IS IMPERATIVE THAT THE ARCHITECT, PROJECT STRUCTURAL ENGINEER AND PRINCIPAL CONTRACTOR MAKE ALLOWANCE FOR THIS.
3. THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS MUST CARRY OUT INDEPENDENT RISK ASSESSMENTS THAT ARE APPLICABLE TO THEIR WORKS AND FULLY COMPLY WITH THE ABOVE STATED REGULATION.
4. THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS MUST REVIEW THE SITE-SPECIFIC AND HISTORICAL BOREHOLE LOGS OF THE SITE TO HAVE ADEQUATE KNOWLEDGE OF GROUND CONDITIONS ON THE SITE, PRIOR TO COMMENCEMENT OF WORKS.
5. DURING SITE OPERATIONS, IF OBSERVED GROUND CONDITIONS DIFFER FROM THE GENERALISED STRATIGRAPHY SHOWN IN THIS SET OF DRAWINGS, DFS MUST BE INFORMED IMMEDIATELY.
6. IT IS THE RESPONSIBILITY OF THE PRINCIPAL CONTRACTOR AND ASSOCIATED SUB-CONTRACTORS TO ENSURE THAT SITE OPERATIVES ARE COMPETENT AND EXPERIENCED IN THE AREA OF WORKS TO BE UNDERTAKEN.
7. IN ADDITION TO THE RISK/HAZARD TYPICALLY ASSOCIATED WITH THE GROUND ENGINEERING WORKS DETAILED IN THIS DRAWING, ADDITIONAL SITE/WORK-SPECIFIC HAZARDS HAVE BEEN IDENTIFIED THROUGH DESIGN RISK ASSESSMENT. THESE ARE OUTLINED IN 7.1 – 7.4 BELOW. ALL SITE OPERATIONS MUST ACCOUNT FOR ALL USUAL AND SITE/WORK-SPECIFIC HAZARDS.
- 7.1. PILING PLATFORM LEVEL IS UNCONFIRMED AT THIS STAGE. HOWEVER, FOR DESIGN PURPOSE, THE PILING MAT LEVEL FOR THE PERIMETER SECANT PILE WALL AND BEARING PILES IS GENERALLY TAKEN TO BE THE EXISTING GROUND LEVEL IN THE AREA OF PROPOSED WORKS; APPROX. +45.500M OD. NONETHELESS, THE PRINCIPAL CONTRACTOR MUST CONFIRM ACTUAL PILING PLATFORM LEVEL(S) PRIOR TO THE COMMENCEMENT OF PILING WORKS ON THE SITE, SO THAT THE PILE WALL SCHEDULE & BEARING PILE SCHEDULE MAY BE AMENDED ACCORDINGLY.
- 7.2. A REINFORCED CONCRETE CAPPING BEAM MUST BE CONSTRUCTED ON THE PILE WALL, WHILE TEMPORARY PROPS MUST BE INSTALLED AGAINST THE CAPPING BEAM PRIOR TO THE COMMENCEMENT OF BULK EXCAVATION FOR THE NEW BASEMENT.
- 7.3. A TEMPORARY GUIDE WALL MUST BE PUT IN-PLACE PRIOR TO THE INSTALLATION OF SECANT PILE WALL.
- 7.4. IN ADDITION, IT IS IMPERATIVE THAT THE CONCRETE MIX DESIGN FOR THE MALE PILES IN THE SECANT WALL ACCOUNTS FOR 10MM MAXIMUM AGGREGATE SIZE AND SET-RETARDING ADMIXTURES IN ORDER TO EASE THE INSTALLATION OF REINFORCEMENT CAGES INTO CONCRETED DRILLHOLES. REINFORCEMENT CAGE VIBRATORS MAY ALSO BE REQUIRED TO FORCE THE STEEL CAGES DOWN TO THE DESIGN DEPTHS.



STAGE 12:
CONSTRUCT GROUND FLOOR SLAB AND CONNECT SAME TO CAPPING BEAM



STAGE 13:
REMOVE TEMPORARY PROPS AND STRUCTURAL STEEL WALLING BEAM

IMPORTANT CONSTRUCTION NOTES

1. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS NOTED OTHERWISE.
2. ALL LEVELS ARE IN METRES UNLESS NOTED OTHERWISE.
3. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, ENGINEERS, AND SPECIALISTS LATEST DRAWINGS AND SPECIFICATIONS. ANY DISCREPANCIES MUST BE REPORTED TO DFS, ENGINEER AND ARCHITECT IMMEDIATELY.
4. ONLY FIGURED DIMENSIONS ARE TO BE USED. ANY QUERIES MUST BE REFERRED TO DFS.
5. 50mm COVER TO PILE REINFORCEMENT.
6. STRICT SUPERVISION OF BULK EARTH WORKS IS REQUIRED TO ENSURE THAT EXCAVATIONS DO NOT EXCEED THE DESIGN DEPTH SHOWN IN THESE DRAWINGS (4.85m).
7. SECANT PILE WALL SHALL BE INSTALLED IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE ICE SPECIFICATIONS FOR PILING AND EMBEDDED RETAINING WALLS (ICESPERW, 2016).
8. THE SECANT PILE WALL IS DESIGNED FOR BOTH TEMPORARY AND PERMANENT USE.



DEEP FOUNDATIONS SPECIALISTS LIMITED
2nd FLOOR, THE PORTER BUILDING 1 BRUNEL WAY
SLOUGH SL1 1PQ
TELEPHONE: 01753 396498

CLIENT
BROXWOOD VIEW LIMITED

JOB TITLE
BROXWOOD VIEW, 29 ST. EDMUND'S TERRACE LONDON NW8 7QH

DRAWING TITLE
PROPOSED CONSTRUCTION SEQUENCE SHEET -4

DATE
16 OCT 2022

DRAWN
AR

CHECKED
AA

DRAWING No
DFS221011-06

REV
00

SCALE
SCALE IS AS SHOWN @ A1



CALCULATIONS

www.deep-foundations.co.uk

Job No: DFS221011

Design Engineer: AR

Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH



Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain
Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00

Page: 26 of 31


GoBeam Version 2015.1 Structural Analysis Output Files

DEEP FOUNDATIONS SPECIALISTS LIMITED	Project: BROXWOOD VIEW, 29 ST. EDMUND'S TERRACE LONDON NW8 7QH	Engineer: AR Date: 14-Oct	Project #
GoBeam Version 2015.1	Subject: TEMPORARY PROPPING SCHEME - ELEVATION 1	Checker: AA Date: 44848	Page:


FORCE/DISPLACEMENTS DIAGRAMS DUE TO STATIC LOAD CASE: DL




Shear, kN	
Max =	166.5
Min =	-166.5




Moment, kN*m	
Max =	96.63
Min =	-180.34



Deflections, mm	
Max =	0.01
Min =	-0.51




Rotations, rad	
Max =	0.00023
Min =	-0.00023




Reactions, kN	
Max =	329.0
Min =	0.0
ΣR =	1425

DEEP FOUNDATIONS SPECIALISTS LIMITED	Project: BROXWOOD VIEW, 29 ST. EDMUND'S TERRACE LONDON NW8 7QH	Engineer: AR Date: 14-Oct	Project #
GoBeam Version 2015.1	Subject: TEMPORARY PROPPING SCHEME - ELEVATION 2	Checker: AA Date: 44848	Page:


FORCE/DISPLACEMENTS DIAGRAMS DUE TO STATIC LOAD CASE: DL




Shear, kN	
Max =	135.0
Min =	-135.0




Moment, kN*m	
Max =	80.68
Min =	-101.25



Deflections, mm	
Max =	0.02
Min =	-0.26



Rotations, rad	
Max =	0.00021
Min =	-0.00021



Reactions, kN	
Max =	247.5
Min =	0.0
ΣR =	675



Job No: DFS221011

Design Engineer: AR

Date: 15 October 2022

Job Name: BROXWOOD VIEW, 29 ST.
EDMUND'S TERRACE LONDON
NW8 7QH

Calc Title: Detailed Design – Temporary Propping Scheme to Laterally Restrain
Secant Pile Retaining Wall & Segmental Underpinning Wall Rev. 00

Page: 27 of 31

CADS PWS 6.09 Computer Output Files

Typical Section SLS Analysis	Page No 1 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Pile geometry

Pile top Level 0 m
Pile Length 8 m
Pile toe level -8 m

Soils and ground water initial data

(Soils data given for active and passive sides)

Initial Ground Water level -.5

Top Level m	Description	Bulk Dens kN/m3	Sat' Dens kN/m3	Young Mod kN/m2	Young Inc. kN/m3	Cu C' kN/m2	C Inc. kN/m3	Phi Deg	Wall Shear Ratio	Ka Kp	Kac Kpc
.00	Made Ground	18.00	18.00	15000	0			28 28	.67 .50	.30 4.15	
-2.50	S to F to Stiff	19.00	19.00	24000	9600	30 30	12.0 12.0		.67 .50	1.00 1.00	2.58 2.45

Construction sequence

Stage Ref	Stage Type	Level or Angle m/deg.	Load kN/(m)	Offset m	Width m	Length m
1 A	Active surcharge	0.00	10.0	.3		
2 A	Passive side excavation	-1.00				
3 A	Passive water level	-1.00				
4	Insert prop	-0.50				
5 A	Passive side excavation	-4.80				
6 A	Passive water level	-4.80				
7 A	Insert prop	-4.20				
8	Insert prop	-0.30				
9 A	Remove prop	-0.50				
10 A	Active water level	0.00				

Typical Section SLS Analysis	Page No 2 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Code of practice

Code of practice or reference document	
Application of pressures for stability	Not applicable for FOS=1 on moments
FOS on moments (stability check)	1.00
ULS factor on Tan(Phi) values	1.00
ULS fFactor on drained cohesion values	1.00
ULS factor on undrained cohesion values	1.00
ULS factor on active soil pressures	1.00
ULS factor on passive soil pressures	1.00
ULS factor on active water pressures	1.00
ULS factor on passive water pressures	1.00
ULS factor on loads applied to the soil	1.00
ULS factor on loads applied to the wall	1.00
FOS on embedment (stability check)	1.00
Correction factor on cantilever embedment	1.00

Wall analysis detail options

Nominal Phi for load distribution	30.0 Degrees
Depth of water filled tension cracks	.0 m
Density of water	9.8 kN/m3
Minimum equivalent fluid density	5.0 kN/m3
Depth of passive softened soil	.0 m
Continuity model for wall analysis	Pins at second and lower props

Deflection parameters

Wall moment of inertia	335482 cm4/m
Wall Youngs modulus	27000000 kN/m2
Properties for prop at -0.5	
Prop/Tie cross sectional area	3 cm2 each
Prop/Tie Youngs modulus	200000000 kN/m2
Prop/Tie length	1.0 m
Prop/Tie spacing	1.0 m
Waling moment of inertia	Waling deflection not included
Waling Youngs modulus	Waling deflection not included
Prop/Tie preload	0 kN
Initial lack of fit	0.0 mm
Properties for prop at -4.2	
Prop/Tie cross sectional area	72 cm2 each
Prop/Tie Youngs modulus	28000000 kN/m2
Prop/Tie length	1.0 m
Prop/Tie spacing	1.0 m
Waling moment of inertia	Waling deflection not included
Waling Youngs modulus	Waling deflection not included
Prop/Tie preload	0 kN
Initial lack of fit	0.0 mm

Typical Section SLS Analysis	Page No 3 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Deflection parameters - continued

Properties for prop at -0.3

Prop/Tie cross sectional area 72 cm2 each

Prop/Tie Youngs modulus 28000000 kN/m2

Prop/Tie length 1.0 m

Prop/Tie spacing 1.0 m

Waling moment of inertia Waling deflection not included

Waling Youngs modulus Waling deflection not included


Prop/Tie preload 0 kN

Initial lack of fit 0.0 mm

Typical Section SLS Analysis	Page No 4 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Stage ref.
Stage type

1
Active surcharge





Typical Section SLS Analysis	Page No 5 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Tabular results from analysis of stage ref 1

Calc Level m	Active Vert kN/m2	Active Earth kN/m2	Active Water kN/m2	Pas' Vert kN/m2	Pas' Earth kN/m2	Pas' Water kN/m2	Total Nett kN/m2	Bend. Moment kNm/m	Shear Force kN/m	Defl't mm	Prop Force kN/m	FOS
.00	.0	.0	.0	.0	.0	.0	0	0	0	0		.00
-.17	13.1	4.0	.0	3.1	12.9	.0	-9.0	0	0	0		>100.00
-.30	15.4	4.7	.0	5.4	22.4	.0	-17.7	0	0	0	.0	>100.00
-.30	15.4	4.7	.0	5.4	22.6	.0	-17.9	0	0	0		>100.00
-.50	19.0	5.8	.0	9.0	37.4	.0	-31.6	0	0	0	.0	>100.00
-.50	19.0	5.8	.0	9.0	37.4	.0	-31.6	0	0	0		>100.00
-1.00	23.1	7.0	4.9	13.1	54.3	4.9	-47.3	0	0	0		>100.00
-1.00	23.1	7.0	4.9	13.1	54.4	4.9	-47.3	0	0	0		>100.00
-2.00	31.3	9.5	14.7	21.3	88.4	14.7	-78.9	0	0	0		>100.00
-2.50	35.4	10.8	19.6	25.4	105.4	19.6	-94.7	0	0	0		>100.00
w-2.50	55.0	.0	19.6	45.0	118.5	.0	-98.9	0	0	0		>100.00
w-2.50	55.0	.0	19.6	45.0	118.6	.0	-99.0	0	0	0		>100.00
w-2.81	60.9	.0	22.6	50.9	133.5	.0	-110.8	0	0	0		>100.00
w-3.00	64.5	.0	24.5	54.5	142.7	.0	-118.2	0	0	0		>100.00
w-4.00	83.5	.0	34.3	73.5	191.1	.0	-156.8	0	0	0		>100.00
w-4.20	87.3	.0	36.3	77.3	200.8	.0	-164.5	0	0	0	.0	>100.00
w-4.20	87.3	.0	36.3	77.3	200.9	.0	-164.6	0	0	0		>100.00
w-4.80	98.7	.0	42.1	88.7	229.7	.0	-187.6	0	0	0		>100.00
w-4.80	98.7	.0	42.1	88.7	229.8	.0	-187.7	0	0	0		>100.00
w-4.90	100.7	.0	43.2	90.7	234.8	.0	-191.7	0	0	0		>100.00
w-4.91	100.8	.0	43.2	90.8	235.1	.0	-191.9	0	0	0		>100.00
w-4.93	101.1	.0	43.4	91.1	235.9	.0	-192.5	0	0	0		>100.00
w-5.00	102.5	.0	44.1	92.5	239.5	.0	-195.4	0	0	0		>100.00
w-5.35	109.2	.0	47.5	99.2	256.5	.0	-209.0	0	0	0		>100.00
w-6.00	121.5	.0	53.9	111.5	287.9	.0	-234.0	0	0	0		>100.00
w-7.00	140.5	.0	63.7	130.5	336.3	.0	-272.6	0	0	0		>100.00
w-8.00	159.5	.0	73.5	149.5	384.7	.0	-311.2	0	0	0		>100.00



Typical Section SLS Analysis	Page No 6 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Graphical results from analysis of stage ref 1



Typical Section SLS Analysis	Page No 7 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Cond'n.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022


Graphical results from analysis of stage ref 1 continued



Typical Section SLS Analysis	Page No 8 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Stage ref.
Stage type

2
Passive side excavation





Typical Section SLS Analysis	Page No 9 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Tabular results from analysis of stage ref 2

Calc Level m	Active Vert kN/m2	Active Earth kN/m2	Active Water kN/m2	Pas' Vert kN/m2	Pas' Earth kN/m2	Pas' Water kN/m2	Total Nett kN/m2	Bend. Moment kNm/m	Shear Force kN/m	Defl't mm	Prop Force kN/m	FOS
.00	.0	.0	.0	.0	.0	.0	0	0	0	.2		.00
-.17	13.1	4.0	.0	.0	.0	.0	4.0	0	-.3	.2		.00
-.30	15.4	4.7	.0	.0	.0	.0	4.7	.1	-.9	.2	.0	.00
-.30	15.4	4.7	.0	.0	.0	.0	4.7	.1	-.9	.2		.00
-.50	19.0	5.8	.0	.0	.0	.0	5.8	.4	-1.9	.2	.0	.00
-.50	19.0	5.8	.0	.0	.0	.0	5.8	.4	-2.0	.2		.00
-1.00	23.1	7.0	4.9	.0	.0	4.9	7.0	2.1	-5.1	.1		.00
-1.00	23.1	7.0	4.9	.0	.0	4.9	7.0	2.1	-5.1	.1		.00
-2.00	31.3	9.5	14.7	8.2	34.0	14.7	-24.5	5.5	3.6	.1		.51
-2.50	35.4	10.8	19.6	12.3	51.1	19.6	-40.3	0	19.8	0		1.00
w-2.50	55.0	.0	19.6	31.9	105.4	.0	-85.8	0	19.8	0		1.00
w-2.50	55.0	.0	19.6	31.9	105.5	.0	-85.9	0	20.0	0		1.00
w-2.81	60.9	.0	22.6	37.8	120.4	.0	-97.7	-.3	2.6	0		1.41
w-3.00	64.5	.0	24.5	41.4	129.6	.0	-105.1	0	0	0		1.69
w-4.00	83.5	.0	34.3	60.4	178.0	.0	-143.7	0	0	0		2.99
w-4.20	87.3	.0	36.3	64.2	187.7	.0	-151.4	0	0	0	.0	3.18
w-4.20	87.3	.0	36.3	64.2	187.8	.0	-151.5	0	0	0		3.18
w-4.80	98.7	.0	42.1	75.6	216.6	.0	-174.5	0	0	0		3.63
w-4.80	98.7	.0	42.1	75.6	216.7	.0	-174.6	0	0	0		3.63
w-4.90	100.7	.0	43.2	77.6	221.7	.0	-178.6	0	0	0		3.69
w-4.91	100.8	.0	43.2	77.7	222.0	.0	-178.8	0	0	0		3.69
w-4.93	101.1	.0	43.4	78.0	222.8	.0	-179.4	0	0	0		3.70
w-5.00	102.5	.0	44.1	79.4	226.4	.0	-182.3	0	0	0		3.75
w-5.35	109.2	.0	47.5	86.1	243.4	.0	-195.9	0	0	0		3.92
w-6.00	121.5	.0	53.9	98.4	274.8	.0	-220.9	0	0	0		4.18
w-7.00	140.5	.0	63.7	117.4	323.2	.0	-259.5	0	0	0		4.43
w-8.00	159.5	.0	73.5	136.4	371.6	.0	-298.1	0	0	0		4.59


Typical Section SLS Analysis	Page No 10 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Cond'n.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Graphical results from analysis of stage ref 2




Typical Section SLS Analysis	Page No 11 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Graphical results from analysis of stage ref 2 continued



Bending Moment Diagram (kNm/m)



Shear Force Diagram (kN/m)


Typical Section SLS Analysis	Page No 12 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Stage ref.

3

Stage type

Passive water level





Typical Section SLS Analysis	Page No 13 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Tabular results from analysis of stage ref 3

Calc Level m	Active Vert kN/m2	Active Earth kN/m2	Active Water kN/m2	Pas' Vert kN/m2	Pas' Earth kN/m2	Pas' Water kN/m2	Total Nett kN/m2	Bend. Moment kNm/m	Shear Force kN/m	Defl't mm	Prop Force kN/m	FOS
.00	.0	.0	.0	.0	.0	.0	0	0	0	.4		.00
-.17	13.1	4.0	.0	.0	.0	.0	4.0	0	-.3	.4		.00
-.30	15.4	4.7	.0	.0	.0	.0	4.7	.1	-.9	.3	.0	.00
-.30	15.4	4.7	.0	.0	.0	.0	4.7	.1	-.9	.3		.00
-.50	19.0	5.8	.0	.0	.0	.0	5.8	.4	-1.9	.3	.0	.00
-.50	19.0	5.8	.0	.0	.0	.0	5.8	.4	-2.0	.3		.00
-1.00	23.1	7.0	4.9	.0	.0	.0	11.9	2.3	-6.3	.2		.00
-1.00	23.1	7.0	4.9	.0	.0	.0	11.9	2.3	-6.4	.2		.00
-2.00	31.3	9.5	14.7	8.2	34.0	9.8	-19.6	9.4	-2.5	.1		.38
-2.50	35.4	10.8	19.6	12.3	51.1	14.7	-35.4	7.6	11.2	.1		.72
w-2.50	55.0	.0	19.6	27.0	100.5	.0	-80.9	7.5	11.2	.1		.72
w-2.50	55.0	.0	19.6	27.0	100.6	.0	-81.0	7.5	11.4	.1		.72
w-2.81	60.9	.0	22.6	32.9	115.5	.0	-92.8	0	38.2	.1		1.00
w-3.00	64.5	.0	24.5	36.5	124.7	.0	-100.2	-1.7	18.1	.1		1.21
w-4.00	83.5	.0	34.3	55.5	173.1	.0	-138.8	0	0	.1		2.29
w-4.20	87.3	.0	36.3	59.3	182.8	.0	-146.5	0	0	.1	.0	2.47
w-4.20	87.3	.0	36.3	59.3	182.9	.0	-146.6	0	0	.1		2.47
w-4.80	98.7	.0	42.1	70.7	211.7	.0	-169.6	0	0	0		2.93
w-4.80	98.7	.0	42.1	70.7	211.8	.0	-169.7	0	0	0		2.93
w-4.90	100.7	.0	43.2	72.7	216.8	.0	-173.7	0	0	0		3.00
w-4.91	100.8	.0	43.2	72.8	217.1	.0	-173.9	0	0	0		3.00
w-4.93	101.1	.0	43.4	73.1	217.9	.0	-174.5	0	0	0		3.02
w-5.00	102.5	.0	44.1	74.5	221.5	.0	-177.4	0	0	0		3.06
w-5.35	109.2	.0	47.5	81.2	238.5	.0	-191.0	0	0	0		3.27
w-6.00	121.5	.0	53.9	93.5	269.9	.0	-216.0	0	0	0		3.58
w-7.00	140.5	.0	63.7	112.5	318.3	.0	-254.6	0	0	0		3.92
w-8.00	159.5	.0	73.5	131.5	366.7	.0	-293.2	0	0	0		4.16


Typical Section SLS Analysis	Page No 14 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Cond.n.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Graphical results from analysis of stage ref 3




Typical Section SLS Analysis	Page No 15 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Graphical results from analysis of stage ref 3 continued



Bending Moment Diagram (kNm/m)




Shear Force Diagram (kN/m)

Typical Section SLS Analysis	Page No 16 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Stage ref.
Stage type

5
Passive side excavation





Typical Section SLS Analysis	Page No 17 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Tabular results from analysis of stage ref 5

Calc Level m	Active Vert kN/m2	Active Earth kN/m2	Active Water kN/m2	Pas' Vert kN/m2	Pas' Earth kN/m2	Pas' Water kN/m2	Total Nett kN/m2	Bend. Moment kNm/m	Shear Force kN/m	Defl't mm	Prop Force kN/m	FOS
.00	.0	.0	.0	.0	.0	.0	0	0	0	.7		.00
-.17	13.1	4.0	.0	.0	.0	.0	4.0	0	-.3	.7		.00
-.30	15.4	4.7	.0	.0	.0	.0	4.7	.1	-.9	.7	.0	.00
-.30	15.4	4.7	.0	.0	.0	.0	4.7	.1	-.9	.7		.00
-.50	19.0	5.8	.0	.0	.0	.0	5.8	.4	-1.9	.8	23.9	.00
-.50	19.0	5.8	.0	.0	.0	.0	5.8	.4	21.9	.8		.00
-1.00	23.1	7.0	4.9	.0	.0	.0	11.9	-9.5	17.5	.9		.00
-1.00	23.1	7.0	4.9	.0	.0	.0	11.9	-9.6	17.5	.9		.00
-2.00	31.3	9.5	14.7	.0	.0	9.8	14.4	-20.7	4.3	1.0		.00
-2.50	35.4	10.8	19.6	.0	.0	14.7	15.7	-21.0	-3.2	1.0		.00
w-2.50	55.0	.0	19.6	.0	.0	14.7	4.9	-21.0	-3.2	1.0		.00
w-2.50	55.0	.0	19.6	.0	.0	14.7	4.9	-21.0	-3.2	1.0		.00
w-2.81	60.9	.0	22.6	.0	.0	17.7	4.9	-19.8	-4.7	1.0		.00
w-3.00	64.5	.0	24.5	.0	.0	19.6	4.9	-18.8	-5.6	1.0		.00
w-4.00	83.5	.0	34.3	.0	.0	29.4	4.9	-10.7	-10.5	.8		.00
w-4.20	87.3	.0	36.3	.0	.0	31.4	4.9	-8.5	-11.5	.7	.0	.00
w-4.20	87.3	.0	36.3	.0	.0	31.4	4.9	-8.5	-11.5	.7		.00
w-4.80	98.7	.0	42.1	.0	.0	37.2	4.9	-.8	-14.4	.6		.00
w-4.80	98.7	.0	42.1	37.2	178.3	.0	-136.2	-.7	-14.3	.6		.01
w-4.90	100.7	.0	43.2	39.2	183.4	.0	-140.2	0	0	.6		.84
w-4.91	100.8	.0	43.2	39.3	183.7	.0	-140.4	0	0	.6		.89
w-4.93	101.1	.0	43.4	39.6	184.4	.0	-141.1	0	0	.6		1.01
w-5.00	102.5	.0	44.1	41.0	188.0	.0	-143.9	0	0	.6		1.60
w-5.35	109.2	.0	47.5	47.7	205.0	.0	-157.5	0	0	.5		2.72
w-6.00	121.5	.0	53.9	60.0	236.4	.0	-182.5	0	0	.4		3.54
w-7.00	140.5	.0	63.7	79.0	284.8	.0	-221.1	0	0	.2		3.99
w-8.00	159.5	.0	73.5	98.0	333.2	.0	-259.7	0	0	0		4.20


Typical Section SLS Analysis	Page No 18 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Cond'n.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Graphical results from analysis of stage ref 5




Typical Section SLS Analysis	Page No 19 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Cond'n.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Graphical results from analysis of stage ref 5 continued



Bending Moment Diagram (kNm/m)




Shear Force Diagram (kN/m)

Typical Section SLS Analysis	Page No 20 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Stage ref.
Stage type

6
Passive water level





Typical Section SLS Analysis	Page No 21 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Tabular results from analysis of stage ref 6

Calc Level m	Active Vert kN/m2	Active Earth kN/m2	Active Water kN/m2	Pas' Vert kN/m2	Pas' Earth kN/m2	Pas' Water kN/m2	Total Nett kN/m2	Bend. Moment kNm/m	Shear Force kN/m	Defl't mm	Prop Force kN/m	FOS
.00	.0	.0	.0	.0	.0	.0	0	0	0	.8		.00
-.17	13.1	4.0	.0	.0	.0	.0	4.0	0	-.3	.9		.00
-.30	15.4	4.7	.0	.0	.0	.0	4.7	.1	-.9	1.1	.0	.00
-.30	15.4	4.7	.0	.0	.0	.0	4.7	.1	-.9	1.1		.00
-.50	19.0	5.8	.0	.0	.0	.0	5.8	.4	-1.9	1.3	48.6	.00
-.50	19.0	5.8	.0	.0	.0	.0	5.8	.4	46.6	1.3		.00
-1.00	23.1	7.0	4.9	.0	.0	.0	11.9	-21.8	42.2	1.8		.00
-1.00	23.1	7.0	4.9	.0	.0	.0	11.9	-21.9	42.2	1.8		.00
-2.00	31.3	9.5	14.7	.0	.0	.0	24.2	-56.0	24.1	2.5		.00
-2.50	35.4	10.8	19.6	.0	.0	.0	30.4	-64.8	10.5	2.7		.00
w-2.50	55.0	.0	19.6	.0	.0	.0	19.6	-64.8	10.5	2.7		.00
w-2.50	55.0	.0	19.6	.0	.0	.0	19.6	-64.8	10.4	2.7		.00
w-2.81	60.9	.0	22.6	.0	.0	.0	22.6	-67.1	3.9	2.7		.00
w-3.00	64.5	.0	24.5	.0	.0	.0	24.5	-67.4	-.6	2.7		.00
w-4.00	83.5	.0	34.3	.0	.0	.0	34.3	-53.0	-30.0	2.2		.00
w-4.20	87.3	.0	36.3	.0	.0	.0	36.3	-46.3	-37.0	2.1	.0	.00
w-4.20	87.3	.0	36.3	.0	.0	.0	36.3	-46.2	-37.1	2.1		.00
w-4.80	98.7	.0	42.1	.0	.0	.0	42.1	-17.3	-60.4	1.8		.00
w-4.80	98.7	.0	42.1	.0	141.1	.0	-99.0	-17.2	-60.4	1.8		.00
w-4.90	100.7	.0	43.2	2.0	146.1	.0	-103.0	-11.4	-49.9	1.7		.22
w-4.91	100.8	.0	43.2	2.1	146.4	.0	-103.2	-11.2	-49.3	1.7		.23
w-4.93	101.1	.0	43.4	2.4	147.2	.0	-103.8	-10.5	-47.6	1.7		.26
w-5.00	102.5	.0	44.1	3.8	150.8	.0	-106.7	-7.1	-39.8	1.7		.41
w-5.35	109.2	.0	47.5	10.5	167.8	.0	-120.3	0	0	1.5		.99
w-6.00	121.5	.0	53.9	22.8	199.2	.0	-145.3	0	0	1.1		1.80
w-7.00	140.5	.0	63.7	41.8	247.6	.0	-183.9	0	0	.6		2.57
w-8.00	159.5	.0	73.5	60.8	296.0	.0	-222.5	0	0	.1		3.05


Typical Section SLS Analysis	Page No 22 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Cond.n.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Graphical results from analysis of stage ref 6




Typical Section SLS Analysis	Page No 23 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Cond'n.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Graphical results from analysis of stage ref 6 continued



Bending Moment Diagram (kNm/m)



Shear Force Diagram (kN/m)


Typical Section SLS Analysis	Page No 24 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Stage ref.

7

Stage type

Insert prop





Typical Section SLS Analysis	Page No 25 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Tabular results from analysis of stage ref 7

Calc Level m	Active Vert kN/m2	Active Earth kN/m2	Active Water kN/m2	Pas' Vert kN/m2	Pas' Earth kN/m2	Pas' Water kN/m2	Total Nett kN/m2	Bend. Moment kNm/m	Shear Force kN/m	Defl't mm	Prop Force kN/m	FOS
.00	.0	.0	.0	.0	.0	.0	0	0	0	.9		.00
-.17	13.1	4.0	.0	.0	.0	.0	4.0	0	-.3	1.0		.00
-.30	15.4	4.7	.0	.0	.0	.0	4.7	.1	-.9	1.1	.0	.00
-.30	15.4	4.7	.0	.0	.0	.0	4.7	.1	-.9	1.1		.00
-.50	19.0	5.8	.0	.0	.0	.0	5.8	.4	-1.9	1.3	36.1	.00
-.50	19.0	5.8	.0	.0	.0	.0	5.8	.4	34.1	1.3		.00
-1.00	23.1	7.0	4.9	.0	.0	.0	11.9	-15.6	29.7	1.7		.00
-1.00	23.1	7.0	4.9	.0	.0	.0	11.9	-15.6	29.7	1.7		.00
-2.00	31.3	9.5	14.7	.0	.0	.0	24.2	-37.3	11.6	2.3		.00
-2.50	35.4	10.8	19.6	.0	.0	.0	30.4	-39.9	-2.0	2.5		.00
w-2.50	55.0	.0	19.6	.0	.0	.0	19.6	-39.9	-2.0	2.5		.00
w-2.50	55.0	.0	19.6	.0	.0	.0	19.6	-39.9	-2.1	2.5		.00
w-2.81	60.9	.0	22.6	.0	.0	.0	22.6	-38.3	-8.6	2.6		.00
w-3.00	64.5	.0	24.5	.0	.0	.0	24.5	-36.2	-13.0	2.6		.00
w-4.00	83.5	.0	34.3	.0	.0	.0	34.3	-9.3	-42.4	2.4		.00
w-4.20	87.3	.0	36.3	.0	.0	.0	36.3	-.1	-49.5	2.4	62.0	.00
w-4.20	87.3	.0	36.3	.0	.0	.0	36.3	0	12.4	2.4		.00
w-4.80	98.7	.0	42.1	.0	.0	.0	42.1	-.6	-10.9	2.0		.00
w-4.80	98.7	.0	42.1	.0	141.1	.0	-99.0	-.6	-10.9	2.0		.01
w-4.90	100.7	.0	43.2	2.0	146.1	.0	-103.0	0	-.4	2.0		.97
w-4.91	100.8	.0	43.2	2.1	146.4	.0	-103.2	0	0	2.0		1.01
w-4.93	101.1	.0	43.4	2.4	147.2	.0	-103.8	0	0	1.9		1.10
w-5.00	102.5	.0	44.1	3.8	150.8	.0	-106.7	0	0	1.9		1.55
w-5.35	109.2	.0	47.5	10.5	167.8	.0	-120.3	0	0	1.7		2.60
w-6.00	121.5	.0	53.9	22.8	199.2	.0	-145.3	0	0	1.3		3.24
w-7.00	140.5	.0	63.7	41.8	247.6	.0	-183.9	0	0	.7		3.60
w-8.00	159.5	.0	73.5	60.8	296.0	.0	-222.5	0	0	.1		3.79


Typical Section SLS Analysis	Page No 26 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Cond.n.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Graphical results from analysis of stage ref 7




Typical Section SLS Analysis	Page No 27 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Graphical results from analysis of stage ref 7 continued



Bending Moment Diagram (kNm/m)



Shear Force Diagram (kN/m)


Typical Section SLS Analysis	Page No 28 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Stage ref.

9

Stage type

Remove prop





Typical Section SLS Analysis	Page No 29 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Tabular results from analysis of stage ref 9

Calc Level m	Active Vert kN/m2	Active Earth kN/m2	Active Water kN/m2	Pas' Vert kN/m2	Pas' Earth kN/m2	Pas' Water kN/m2	Total Nett kN/m2	Bend. Moment kNm/m	Shear Force kN/m	Defl't mm	Prop Force kN/m	FOS
.00	.0	.0	.0	.0	.0	.0	0	0	0	1.0		.00
-.17	13.1	4.0	.0	.0	.0	.0	4.0	0	-.3	1.2		.00
-.30	15.4	4.7	.0	.0	.0	.0	4.7	.1	-.9	1.3	34.2	.00
-.30	15.4	4.7	.0	.0	.0	.0	4.7	.1	33.3	1.3		.00
-.50	19.0	5.8	.0	.0	.0	.0	5.8	-6.4	32.3	1.5	.0	.00
-.50	19.0	5.8	.0	.0	.0	.0	5.8	-6.5	32.3	1.5		.00
-1.00	23.1	7.0	4.9	.0	.0	.0	11.9	-21.5	27.9	1.9		.00
-1.00	23.1	7.0	4.9	.0	.0	.0	11.9	-21.6	27.9	1.9		.00
-2.00	31.3	9.5	14.7	.0	.0	.0	24.2	-41.4	9.8	2.5		.00
-2.50	35.4	10.8	19.6	.0	.0	.0	30.4	-43.0	-3.9	2.6		.00
w-2.50	55.0	.0	19.6	.0	.0	.0	19.6	-43.0	-3.9	2.6		.00
w-2.50	55.0	.0	19.6	.0	.0	.0	19.6	-43.0	-3.9	2.6		.00
w-2.81	60.9	.0	22.6	.0	.0	.0	22.6	-40.8	-10.4	2.7		.00
w-3.00	64.5	.0	24.5	.0	.0	.0	24.5	-38.4	-14.9	2.7		.00
w-4.00	83.5	.0	34.3	.0	.0	.0	34.3	-9.7	-44.3	2.5		.00
w-4.20	87.3	.0	36.3	.0	.0	.0	36.3	-.1	-51.3	2.4	63.8	.00
w-4.20	87.3	.0	36.3	.0	.0	.0	36.3	0	12.4	2.4		.00
w-4.80	98.7	.0	42.1	.0	.0	.0	42.1	-.6	-10.9	2.0		.00
w-4.80	98.7	.0	42.1	.0	141.1	.0	-99.0	-.6	-10.9	2.0		.01
w-4.90	100.7	.0	43.2	2.0	146.1	.0	-103.0	0	-.4	2.0		.97
w-4.91	100.8	.0	43.2	2.1	146.4	.0	-103.2	0	0	2.0		1.01
w-4.93	101.1	.0	43.4	2.4	147.2	.0	-103.8	0	0	2.0		1.11
w-5.00	102.5	.0	44.1	3.8	150.8	.0	-106.7	0	0	1.9		1.55
w-5.35	109.2	.0	47.5	10.5	167.8	.0	-120.3	0	0	1.7		2.60
w-6.00	121.5	.0	53.9	22.8	199.2	.0	-145.3	0	0	1.3		3.24
w-7.00	140.5	.0	63.7	41.8	247.6	.0	-183.9	0	0	.7		3.60
w-8.00	159.5	.0	73.5	60.8	296.0	.0	-222.5	0	0	.1		3.79


Typical Section SLS Analysis	Page No 30 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Cond'n.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Graphical results from analysis of stage ref 9




Typical Section SLS Analysis	Page No 31 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Graphical results from analysis of stage ref 9 continued



Bending Moment Diagram (kNm/m)




Shear Force Diagram (kN/m)

Typical Section SLS Analysis	Page No 32 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Stage ref.
Stage type

10
Active water level





Typical Section SLS Analysis	Page No 33 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Tabular results from analysis of stage ref 10

Calc Level m	Active Vert kN/m2	Active Earth kN/m2	Active Water kN/m2	Pas' Vert kN/m2	Pas' Earth kN/m2	Pas' Water kN/m2	Total Nett kN/m2	Bend. Moment kNm/m	Shear Force kN/m	Defl't mm	Prop Force kN/m	FOS
.00	.0	.0	.0	.0	.0	.0	0	0	0	1.0		.00
-.17	11.4	3.5	1.7	.0	.0	.0	5.2	0	-4	1.2		.00
-.30	12.5	3.8	2.9	.0	.0	.0	6.7	.1	-1.2	1.3	41.6	.00
-.30	12.5	3.8	3.0	.0	.0	.0	6.8	.1	40.4	1.3		.00
-.50	14.1	4.3	4.9	.0	.0	.0	9.2	-7.7	38.8	1.5	.0	.00
-.50	14.1	4.3	4.9	.0	.0	.0	9.2	-7.8	38.8	1.5		.00
-1.00	18.2	5.5	9.8	.0	.0	.0	15.3	-25.7	32.7	2.0		.00
-1.00	18.2	5.5	9.8	.0	.0	.0	15.3	-25.7	32.7	2.0		.00
-2.00	26.4	8.0	19.6	.0	.0	.0	27.6	-48.7	11.2	2.7		.00
-2.50	30.5	9.3	24.5	.0	.0	.0	33.8	-50.6	-4.1	2.8		.00
w-2.50	55.0	.0	24.5	.0	.0	.0	24.5	-50.6	-4.1	2.8		.00
w-2.50	55.0	.0	24.5	.0	.0	.0	24.5	-50.6	-4.2	2.8		.00
w-2.81	60.9	.0	27.5	.0	.0	.0	27.5	-48.1	-12.2	2.8		.00
w-3.00	64.5	.0	29.4	.0	.0	.0	29.4	-45.3	-17.6	2.8		.00
w-4.00	83.5	.0	39.2	.0	.0	.0	39.2	-11.3	-51.9	2.5		.00
w-4.20	87.3	.0	41.2	.0	.0	.0	41.2	-.1	-60.0	2.5	74.2	.00
w-4.20	87.3	.0	41.2	.0	.0	.0	41.2	0	14.2	2.4		.00
w-4.80	98.7	.0	47.0	.0	.0	.0	47.0	-.8	-12.1	2.1		.00
w-4.80	98.7	.0	47.0	.0	141.1	.0	-94.1	-.8	-12.1	2.1		.01
w-4.90	100.7	.0	48.1	2.0	146.1	.0	-98.1	0	-2.1	2.0		.87
w-4.91	100.8	.0	48.1	2.1	146.4	.0	-98.3	0	-1.5	2.0		.91
w-4.93	101.1	.0	48.3	2.4	147.2	.0	-98.9	0	0	2.0		.99
w-5.00	102.5	.0	49.0	3.8	150.8	.0	-101.8	0	0	2.0		1.38
w-5.35	109.2	.0	52.4	10.5	167.8	.0	-115.4	0	0	1.7		2.34
w-6.00	121.5	.0	58.8	22.8	199.2	.0	-140.4	0	0	1.3		2.94
w-7.00	140.5	.0	68.6	41.8	247.6	.0	-179.0	0	0	.7		3.30
w-8.00	159.5	.0	78.4	60.8	296.0	.0	-217.6	0	0	.1		3.51


Typical Section SLS Analysis	Page No 34 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Graphical results from analysis of stage ref 10




Typical Section SLS Analysis	Page No 35 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Cond'n.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Graphical results from analysis of stage ref 10 continued





Bending Moment Diagram (kNm/m)



Shear Force Diagram (kN/m)

Typical Section SLS Analysis	Page No 36 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Graphical plot of envelope from selected construction stages



Typical Section SLS Analysis	Page No 37 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Table of envelope for wall forces

Calc Level m	Bending Minimum kNm/m	Bending Maximum kNm/m	Shear Minimum kN/m	Shear Maximum kN/m	Prop Force kN/m
.00	.0	.0	.0	.0	
-.17	.0	.0	-.4	.0	
-.30	.0	.1	-1.2	.0	41.6
-.30	.0	.1	-.9	40.4	
-.50	-7.7	.4	-1.9	38.8	48.6
-.50	-7.8	.4	-2.0	46.6	
-1.00	-25.7	2.3	-6.3	42.2	
-1.00	-25.7	2.3	-6.4	42.2	
-2.00	-56.0	9.4	-2.5	24.1	
-2.50	-64.8	7.6	-4.1	19.8	
-2.50	-64.8	7.5	-4.1	19.8	
-2.50	-64.8	7.5	-4.2	20.0	
-2.81	-67.1	.0	-12.2	38.2	
-3.00	-67.4	.0	-17.6	18.1	
-4.00	-53.0	.0	-51.9	.0	
-4.20	-46.3	.0	-60.0	.0	74.2
-4.20	-46.2	.0	-37.1	14.2	
-4.80	-17.3	.0	-60.4	.0	
-4.80	-17.2	.0	-60.4	.0	
-4.90	-11.4	.0	-49.9	.0	
-4.91	-11.2	.0	-49.3	.0	
-4.93	-10.5	.0	-47.6	.0	
-5.00	-7.1	.0	-39.8	.0	
-5.35	.0	.0	.0	.0	
-6.00	.0	.0	.0	.0	
-7.00	.0	.0	.0	.0	
-8.00	.0	.0	.0	.0	

Typical Section SLS Analysis	Page No 38 Analysis Temp Condition
CADS Piled Wall Suite Version 6.10 Design of embedded retaining walls and cofferdams	Project SLS Analysis File Name ...cal -Temp Condn.pws"
Broxwood View, 29 St. Edmund's Yerrace London NW8 450mm Dia. Secant Pile Retaining Wall	Engineer AA Date 13/10/2022

Structural design of wall

Wall section properties

Primary pile diameter	450 mm
Primary pile spacing	600 mm
Infill pile diameter	mm
Main rebar bar diameter	20 mm
Main rebar number of bars	6
Links/Helix bar diameter	10 mm
Links/Helix spacing/pitch	175 mm

Wall material properties

Concrete cube strength	35 N/mm2
Concrete cover	50 mm
Main rebar steel grade	500 N/mm2
Link rebar steel grade	500 N/mm2
Ultimate load factor	1.50

Wall structural design checks

Check description	Required or Limit	Provided or Actual	Units
Bending resistance. BS8110 plane strain analysis	61	118	kNm
Max longitudinal steel. BS8110 max 6% by area	9543	1885	mm2
Min longitudinal steel. BS8110 min 0.4% by area	636	1885	mm2
Shear resistance. BS8110	54	172	kN
Min link dia. BS8110 6mm or 0.25x bar dia	6	10	mm
Max link spacing. BS8110 12x main bar dia or 0.75d	192	175	mm
Min shear link area. BS8110 Clause 3.4.5	247	898	mm2/m