## 2 Biodiverse Substrate Depth:Typically from 100mm ~ 150mm 3 reservoir board 4 filter fleece 5 protection mat 6 capping sheet / membrane to secure the metal trim 7 edge / drainage trim 8 vegetagion barrier 9 waterproofing layer 10 insulation 11 vapour control layer 12 decking 13 rafters 14 insulated plasterboard Castellated timber kerb encapsulated within the waterproofing system WALL: 1 timber clading 2 counter batten 3 batten 4 breather membrane vent 5 shething 6 timber studs 13 7 insulation 8 insulated plasterboard 9 rafters outside 3 inside

ROOF:

1 Wildflower Vegetation

GREEN ROOF DETAIL



