

SITE INVESTIGATION FACTUAL REPORT


Report No: [REDACTED]
Client: Sedgwick International UK - Maidstone
Site: 43 Gondar Gardens
Client Ref: [REDACTED]
Date of Visit: 05/02/2020



Home Emergency Response - Subsidence Investigation - Drainage Services – Crack & Level Monitoring – Property Video Surveys



<h1>Investigation Layout Plan</h1>	Sheet: 1 of 1	Site: 43 Gondar Gardens NW6
	Job No: [REDACTED]	
(SI)	SA (Checked)	CFT (Drawn)
Weather: DRY		



GONDAR GARDENS

Water Supply : Inhouse - outside Tap
 Power : Internal - External - None
 Parking : Onsite - Road - red Route - Metered - Permit - Other
 Site Access : Good - Bad (explain)

FRONT OF PROPERTY
 ON SITE TREE IDENTIFICATION FOR GUIDANCE ONLY. NOT AUTHENTICATED.

Remarks: X 3 AT REAR ADDITION IS LOFT CONVERSION	Key:	Surface Water Drain		
	Combined Gully	RWWG	Foul Water Drain	
	Manhole	MH	Tree / Bush	
	Rain Water Pipe	RWP	(approx. ht in m)	
	Rain Water Gully	RWG	Trial Pit	
	Soil Vent Pipe	SVP	Borehole	
	Waste Gully	WG	O/D - Open Discharge	
	Waste Pipe	WP		

Scale: N.T.S.

TEST REPORT: Trial Pit

REPORT NUMBER: [REDACTED]

TRIAL PIT REF: [REDACTED]

CLIENT: Sedgwick International UK


JOB NO: [REDACTED]

EXCAVATION METHOD: Hand tools

DATE: 26/02/2020

SITE: 43 Gondar Gardens

WEATHER: Dry



For Strata below 1300mm see Bore Hole log

Water seepage at 750mm.

Key:
D Small disturbed sample J Jar sample
B Bulk disturbed sample V Pilcon vane (kPa)
W Water sample M Mackintosh probe
TDTD Too dense to drive

Remarks:
Test results reported relate only to the items tested.
This report shall not be reproduced in full without approval of the Laboratory.

For and on behalf of CET
Scott Alger - Lab

Report Format:

[REDACTED]

Approved Signatory
27-Feb-20

[REDACTED]

Borehole		1	Sheet:	1 of 1	Site:	43 Gondar Gardens			
Boring Method:		Hand Auger	Job No:		Client:				
Diameter (mm):		75	Date:	26/02/2020	Sedgwick International UK - Maidstone				
Weather:		Dry	Ground Level:						
Depth	Soil Description				Thickness	Legend	Samples and Tests		
(m)							Depth	Type	Result
0.00	See Trial Pit				1.30				
1.30	Stiff mid brown, grey veined silty CLAY with partings of orange silt and fine sand.				0.70	⊗	1.50	DV	118
						⊗			120
2.00	Very stiff mid brown, grey veined silty CLAY with partings of orange silt and fine sand.				1.00	⊗	2.00	DV	140+
						⊗			140+
						⊗	2.50	DV	140+
						⊗			140+
3.00	Very stiff mid brown, grey veined silty CLAY with partings of orange silt and fine sand and crystals.				2.00	⊗	3.00	DV	140+
						⊗			140+
						⊗	3.50	DV	140+
						⊗			140+
						⊗	4.00	DV	140+
						⊗			140+
						⊗	4.50	DV	140+
						⊗			140+
5.00	End of BH					⊗	5.00	DV	140+
Remarks:					Key:			To	Max
BH ends at 5.0m. BH dry and open on completion. No live roots observed below 1.7m. Dead and decomposing root fragments to 5.0m.					D - Disturbed Sample			Depth	Dia
					B - Bulk Sample			(m)	(mm)
					W - Water Sample			1.70	1
					J - Jar Sample				
					V - Pilcon Shear Vane (kPa)				
					M - Mackintosh Probe			4.90	
					TDTD - Too Dense To Drive				
Logged:	AC	SA	Checked:	Approved:	Version	V1.0 28/01/16		N.T.S.	

Laboratory Summary Results

Our Ref : [REDACTED]
 Location : 43, Gondar Gardens, London
 Client : [REDACTED]
 Address : [REDACTED]

Date Sampled: 26/02/2020
 Date Received : 27/02/2020
 Date Tested : 27/02/2020
 Date of Report : 06/03/2020

TP/BH No	Sample Ref Depth (m)	Type	Moisture Content (%) [11]	Soil Fraction > 0.425mm (%) [12]	Liquid Limit (%) [13]	Plastic Limit (%) [14]	Plasticity Index (%) [15]	Liquidity Index [16]	Modified Plasticity Index (%) [16]	Soil Class [17]	Filter Paper Contact Time (h.)	Soil Sample Suction (kPa) [18]	Oedometer Strain [19]	Estimated Heave Potential (DM) (mm) [10]	In situ Shear Vane Strength (kPa) [11]	Organic Content (%) [12]	pH Value [13]	Sulphate Content (g/l)		Class
																		SO3 [14]	SO4 [15]	
1	U/S 1.03	D	35	<5	69	21	48	0.29	48	CH	168	118			104					
	1.5	D	32	<5											119					
	2.0	D	31	<5	69	21	48	0.21	48	CH	168	271			> 140					
	2.5	D	31	<5											> 140					
	3.0	D	31	<5	72	26	46	0.12	46	CV	168	308			> 140					
	3.5	D	31	<5											> 140					
	4.0	D	31	<5								168	346		> 140					
	4.5	D	32	<5											> 140					
	5.0	D	32	<5								168	293		> 140					

Test Methods / Notes

[1] BS 1377: Part 2: 1990, Test No 3.2
 [2] Estimated ($\leq 5\%$, otherwise measured)
 [3] BS 1377: Part 2: 1990, Test No 4.4
 [4] BS 1377: Part 2: 1990, Test No 5.3
 [5] BS 1377: Part 2: 1990, Test No 5.4
 [6] BRE Digest 240: 1993
 [7] BS 5910: 2018: Figure 8: Plasticity Chart for the classification of fine soils

[8] In-house method SH adopted from BS EN 12754: 2006
 [9] In-house Test Procedure S17: One Dimensional Swell-Strain Test
 [10] Estimated Heave Potential (DM)
 [11] Values of shear strength were determined in-situ by CPT using a Pileon based vane or Geosir vane (GV).
 [12] BS 1377: Part 2: 1990, Test No 4
 [13] BS 1377: Part 2: 1990, Test No 9
 [14] BS 1377: Part 2: 1990, Test No 5.6
 [15] $SI_u = 1.2 \times SI$

[16] BS 1377: Part 2: 1990, Test No 10.2
 Note that if the SO4 content falls into the DS-4 or DS-5 class, it would be prudent to consider the sample as falling into the DS-4M or DS-5M class respectively unless water soluble magnesium testing is undertaken to prove otherwise.
 * These tests are not UKAS accredited
 Full reports can be provided upon request.

Key
 D Disturbed sample (small)
 B Disturbed sample (bulk)
 U Undisturbed sample
 W Groundwater sample
 ENP Essentially Non-Plastic by inspection
 US Underside of Foundation





Test results reported relate only to the items tested.
 This report shall not be reproduced except in full without approval of the laboratory.

Moisture Content Profiles

Our Ref: XXXXXXXXXX
 Location: 43, Conislar Gardens, London
 Work carried out for: Sedgwick International UK - Maidstone

Date Sampled: 26/02/2020
 Date Received: 27/02/2020
 Date Tested: 27/02/2020
 Date of Report: 06/03/2020




Notes:
 1. Equations 0.4 T1 and P1 - 2 (after Driscoll, 1983) should only be applied to London Clay (and similarly overconsolidated clay) at shallow depths.
 2. Unless specifically noted the profiles have not been related to a site datum.

Note:
 1. Unless otherwise stated, values of Shear Strength were determined in situ by CPT using a Pikeam Hand Vane the calibration of which is limited to a maximum reading of 140 kPa.
 2. Unless specifically noted the profiles have not been related to a site datum.

Moisture Content Profiles


Our Ref: [REDACTED]
 Location: 43, Goslar Gardens, London
 Work carried out for: Sedgwick International UK - Maidstone



Notes:
 1. Empirical, 0.4 I_L and PI - 2 (after Driscoll, 1983) should only be applied to London Clay (and similarly overconsolidated clay) at shallow depths.
 2. Unless specifically noted the profiles have not been related to a site datum.

Soil Suction Profiles

Date Sampled: 26/02/2020
 Date Received: 27/02/2020
 Date Tested: 27/02/2020
 Date of Report: 06/03/2020



Note:
 When shown, the theoretical equilibrium suction profiles are based on conventional assumptions associated with London Clay (and similarly overconsolidated clays) at shallow depths. Note that the sample disturbance component is dependent on the method of sampling and any subsequent recompaction. The above plots show this to be 100kPa which is the value suggested by the BSI on the basis of their limited number of tests on recompacted samples. This may or may not be appropriate in this instance and judgement should be exercised.

EPSL

European Plant Science Laboratory

Sheet: 1 of 1

Job No: [REDACTED]

Date: 28/02/2020

Site: 43 Gondar Gardens,

Work carried out for: Sedgwick International UK

Certificate of Analysis

The following work was commissioned by CET on behalf of their client. Root samples were obtained in sealed packets from the above site with no reference given as to the types of tree or shrub from which they may have originated.

The results were as follows -

<u>Trial pit/ Borehole number</u>	<u>Root diameter (mm)</u>	<u>Tree, shrub or climber from which root originates</u>	<u>Result of starch test</u>
TP1 (USF)	2 mm	Rosa spp.	Positive
TP1 (USF)	<1 mm	either Quercus spp. or Castanea spp. * 2 roots	Positive
BH1 (to 1.7m)	<1 mm	either Quercus spp. or Castanea spp. * 3 roots	Positive

* All rather juvenile.

Rosa spp. are roses.

Quercus spp. are oaks. Castanea spp. include sweet chestnut.

[REDACTED]
MDM

[REDACTED]
Head of Laboratory Services : M D Mitchell B.Sc. (Hons), M.Phil.

Plant Anatomist : Dr G S Turner B.Sc. (Hons), M.Sc., Ph.D

Plant Anatomist : Dr R J Shaw B.Sc. (Hons), Ph.D

Consultant: Dr M P Denne B.Sc. (Hons), M.Sc., Ph.D
[REDACTED]

To: Sedgwick International UK - Mialdstone



Date: 27-Feb-20

From: Michael Robinson

ESTIMATE

Site:- 43 Gondar Gardens


Item	Amount
No recommendations required to the private drainage surveyed.	

Notes

Repairs to shared runs and off boundary pipe-work may be the responsibility of the water authority.

Condition Grade

- A - Structurally sound with no leakage evident.
- B - Cracks and fractures observed.
- C - Structurally unsound



Quotation is binding only if accepted within 28 days from date of issue and is subject to our Standard Terms and Conditions
The price qualification notes, stated on the drainage solutions schedule of rates, apply to this quotation.
CET Structures Ltd undertakes to return to site free of charge to carry out remedial work to the drainage repairs set out above for a period of 2 months from the date of this invoice. The company standard charge rates will apply to the visit should the work requested be unrelated to the said repairs.

Coding Sheet		Sheet:		Site:	43 Gondar Gardens			
		Job No.:						
		Date:	#####	Client:	Sedgwick International UK - Maidstone			
Run:	1							
From:		MH1	Invert Level:	1400	Direction:	U/S		
To:		U/S	Invert Level:		Function:	S/W		
Pipe Material:		PVC	Pipe Dia:	100				
Water/Pressure Test:			Drain Break-In:	No	Gully Condition:	As Built		
Distance (m)	Code	Clock Ref at to	Dia mm	Intrusion % mm	Shared Run:	No		
					If Shared How:			
0.00	ST				Remarks	Surface Material	Length (m)	
0.00	WL			20	Water level	concrete	1.8	
0.10	LR				Line deviates right			
0.40	LR				Slight			
1.80	DE			100	Debris			
1.80	FH				Capped end			
Comments:								
Run:	2							
From:		MH2	Invert Level:	670	Direction:	U/S		
To:		U/S	Invert Level:		Function:	S/W		
Pipe Material:		PVC	Pipe Dia:	100				
Water/Pressure Test:			Drain Break-In:	No	Gully Condition:			
Distance (m)	Code	Clock Ref at to	Dia mm	Intrusion % mm	Shared Run:	No		
					If Shared How:			
0.00	ST				Remarks	Surface Material	Length (m)	
0.10	JN	9	100		Run 3	concrete	11.7	
0.40	LR				Line deviates right			
4.50	JN	2	100		RWP1			
6.00	WL			5	Water level			
6.00	DES			5	Debris silt			
6.50	LR				Line deviates right			
7.00	DES			10	Debris silt			
8.50	JN	3	100		YG1			
9.40	DES			10	Debris silt			
11.70	FH				Reached capped off run			
Comments:								
Pipework appears to have been slotted to take ground water								

Run:		3									
From:		JN in Run 2		Invert Level:				Direction:		U/S	
To:		SVP1		Invert Level:				Function:		Comb	
Pipe Material:		PVC		Pipe Dia:		100					
Water/Pressure Test:				Drain Break-In:		No		Gully Condition:			
Distance (m)	Code	Clock Ref at	to	Dia mm	Intrusion %	mm	Shared Run:			No	
							If Shared How:				
0.00	ST						Remarks	Surface Material	Length (m)		
0.40	LL						Line deviates left	concrete	3.1		
0.80	JN	3		100			YG2				
1.90	JN	10		100			RWG1				
2.40	LL						Line deviates left				
2.80	LU						Line deviates up				
3.10	FH						Reached SVP1				
Comments:											
Run:		4									
From:		JN in Run 3		Invert Level:				Direction:		U/S	
To:		RWG1		Invert Level:				Function:		S/W	
Pipe Material:		PVC		Pipe Dia:		100					
Water/Pressure Test:				Drain Break-In:		No		Gully Condition:		As Built	
Distance (m)	Code	Clock Ref at	to	Dia mm	Intrusion %	mm	Shared Run:			No	
							If Shared How:				
0.00	ST						Remarks	Surface Material	Length (m)		
0.00	LU						Line deviates up	concrete	0.2		
0.20	FH						Reached RWG1				
Comments:											
Run:		5									
From:		MH2		Invert Level:		670		Direction:		D/S	
To:		MH4		Invert Level:				Function:		Comb	
Pipe Material:		VC		Pipe Dia:		100					
Water/Pressure Test:				Drain Break-In:		No		Gully Condition:			
Distance (m)	Code	Clock Ref at	to	Dia mm	Intrusion %	mm	Shared Run:			No	
							If Shared How:				
0.00	ST						Remarks	Surface Material	Length (m)		
0.10	MC						to Liner	concrete	0.2		
3.90	MC						to Cast	under house			
4.00	LR						Line deviates right				
7.00	MC						to VC				
7.80	MC						to Cast				
9.80	MC						to VC				
9.90	MH						Manhole				
10.30	MC						to Liner				
15.00	FH						Reached MH4				
Comments:											

Run:	6							
From:	RWP1	Invert Level:		Direction:	D/S			
To:	Run 2	Invert Level:		Function:	S/W			
Pipe Material:	PVC	Pipe Dia:	100					
Water/Pressure Test:		Drain Break-In:	Yes	Gully Condition:				
Distance (m)	Code	Clock Ref at to	Dia mm	Intrusion % mm	Shared Run:	No		
					If Shared How:			
0.00	ST				Remarks	Surface Material	Length (m)	
0.00	LD				Line deviates down	concrete	1.1	
0.40	GO				line levels			
1.10	FH				Reached Run 2			
Comments:								

Manhole Details	Sheet:	1 of 1	Site:	43 Gondar Gardens
	Job No.:			
	Date:	26/02/20	Client:	Sedgwick International UK - Maidstone

MH:- Depth:- (mm)

Depths of run if different to invert level:-

Run	Depth (mm)
1	650

Manhole Condition:-

Reasons for poor condition.

Chamber Dimension:- / (mm)

MH:- Depth:- (mm)

Depths of run if different to invert level:-

Run	Depth (mm)

Manhole Condition:-

Reasons for poor condition.

Chamber Dimension:- / (mm)

MH:- Depth:- (mm)

Depths of run if different to invert level:-

Run	Depth (mm)

Manhole Condition:-

Reasons for poor condition.

Chamber Dimension:- / (mm)

Key

- Interceptor
- Internal Back Drop.
- External Back Drop.

Additional Comments for Poor Condition

MH1 has a pumping system, pumping into MH2 through a 30mm diameter pipe at 100mm below GL.