

Issue Date: 23 Jun 2022

Refurbishment Survey (with MA + PA)

London Borough of Camden 5 Pancras Square London N1C 4AG



Falcon Building
Old Gloucester Street
London
WC1N 3AA

Full Circle Compliance 32 Writtle Road Chelmsford Essex CM1 3BX

Email: info@fullcirclecompliance.co.uk

Tel: 01245 690606



Contents:



- Executive Summary [Conclusions and actions]
- 2. Contract Review
- 3. Introduction Purpose, Aims and Objectives
- 4. Desk Top Review and Survey Planning

Issue Date: 23 Jun 2022

- 5. Survey Method
- 6. Exclusions and Caveats
- 7. Sampling and Analysis
- 8. Survey Results Interpretation
- 9. Recommendations

APPENDICES - Survey Results

Appendix 1 - Asbestos Register - Results

Appendix 2 - Survey Data Sheets

Appendix 3 - Areas Surveyed

Appendix 4 - Analysis Certificates

Appendix 5 - Plans

1.0 Executive summary:

Issue Date: 23 Jun 2022



Asbestos containing materials have been identified during the Refurbishment Survey and the specific areas are categorized below in order according to the Total Risk Score, with a scoring range of up to 24, made by Full Circle Compliance.

HIGH RISK MATERIALS - Total Risk Score of 18-24

Asbestos in poor condition, or asbestos debris/contamination has been identified within the following areas listed in the table below. It is recommended that risk assessment (s) are undertaken to ensure that Regulation 4, Regulation 10, Regulation 11, and Regulation 16 of the Control of Asbestos Regulations 2012 are complied with.

Building	Floor	Room	Item		Risk assessment Score	Recommendations				
There wer	There were no results found.									

MEDIUM RISK MATERIALS - Total Risk Score of 12-17

Asbestos containing materials, which are unsealed or damaged, have been identified within the following areas listed in the table below. It is recommended that remedial work to seal or remove these materials is undertaken as a priority and that air monitoring is carried out within adjacent areas in order to assess airborne fibre levels.

Building	Floor	Room	Item		Risk assessment Score	Recommendations				
There wer	There were no results found.									

1.0 Executive summary:

Issue Date: 23 Jun 2022



LOW RISK MATERIALS - Total Risk Score of less than 11

Asbestos Containing Materials have been identified which are in good condition, A management policy and plan need to be implemented to manage these materials safely. The materials require labelling and the condition of these materials re-inspected at 12 monthly intervals.

Building	Floor	Room	Item	Material	Risk assessment Score	Recommendations
Falcon Building Basement.	Z- Sub Level 1	Cupboard 2	Flashguards	Flash Guard	LOW (9)	F - Remove under controlled conditions

1.0 Executive summary:

Issue Date: 23 Jun 2022



PRESUMED ASBESTOS/NO ACCESS AREAS

Asbestos Containing Materials have been presumed as being present to the following areas where access could not be gained. A management policy and plan needs to identify that these areas require inspection once access can be provided. These areas require re-inspection for accessibility at 12 monthly intervals.

Building	Floor	Room/Area	Description	Comments	Recommendation
Falcon Building Basement.	Z-Sub Level 1	Cupboard 1	Inaccessible	Door locked, Not FB. No locksmith on site	E - Carry out further investigation
Falcon Building Basement.	Z-Sub Level 1	Sheds 29 -42	Tenants sheds Inaccessible	Full of tenants belongings And locked with tenants padlocks	E - Carry out further investigation
Falcon Building Basement.	Z-Sub Level 1	Liftshafts	Liftshafts Inaccessible	Lift engineer required	E - Carry out further investigation
Falcon Building Basement.	Z-Sub Level 1	Electrical Intake Cupboard	Inaccessible	Steel doors Gerda key required	E - Carry out further investigation

Building Notes:

External notes: 1950s brick constructed building, brick walls, concrete to floor and ceiling, timber doors.

2.0 Contract Review:

Issue Date: 23 Jun 2022



Name and address of site:	Falcon Building, Old Gloucester Street, London								
Name and address of client:	London Borough of C	London Borough of Camden, 5 Pancras Square, London							
Client contact:	Shane Cole								
Type of survey:	Refurbishment Survey (with MA + PA)								
Date of survey:	20 Jun 2022 - 20 Jun 2022								
Report Revision Number:	1								
TEAMS internal job number:	J025213								
Lead surveyor[s]:	Steve Beak	Signature:	M						
Technically reviewed by:	Samantha Clark Signature:								
Report issue date:	23 Jun 2022								

3.0 Introduction/Objectives:

Issue Date: 23 Jun 2022



Full Circle Compliance received an order of confirmation to undertake a Refurbishment Survey from London Borough of Camden. This order has been accepted on the basis of the original quotation and our terms and conditions of business.

The order relates to a Refurbishment survey of:

Falcon Building Old Gloucester Street London WC1N 3AA

The survey was carried out by Steve Beak.

The Type of survey selected / requested by the client was a Refurbishment survey.

The reason for selecting this survey is to enable the client to identify asbestos in his premises so that it can be removed prior to major refurbishment.

The survey has included the completion of priority assessment in accordance with HSG227. This priority assessment was completed with input from the duty holder and his representatives.

This survey was carried out in accordance with documented in house procedures, which are based on the HSE Guidance document HSG 264.

3.1 Purpose of Survey

The purpose of this Major refurbishment Survey is to help the duty holder identify asbestos in these premises, prior to. It provides sufficient information to help the tendering process for removal works prior to any work starting. However it is strongly recommended that any asbestos removal should be undertaken against a detailed specification. We further recommend the appointed removal contractor should attend the site to confirm for themselves the quantities and location of asbestos to be removed, prior to costing.

3.2 Aim of Survey

The aim of the survey was to:

- 1. Locate and record the location, extent, and product type as far as reasonably practicable of known or presumed ACM's.
- 2. Inspect and record information on the accessibility, condition and surface treatment of know or presumed ACM's
- 3. Determine and record the asbestos type based on sampling or by making a presumption based on product type and appearance
- 4. Locate all ACM's within the fabric of the building prior to refurbishment.

3.0 Introduction/Objectives(Cont):Type of Survey

Issue Date: 23 Jun 2022



3.3 Type of Survey – Refurbishment Survey

The purpose of this major refurbishment survey is to identify ACM's to be removed prior to any major refurbishment work being carried out. This type of survey is used to locate and describe as far as is reasonably practicable all ACM's in the whole building if major refurbishment is planned.

Major refurbishment surveys are intended to locate all asbestos within the building. It is a disruptive, fully intrusive survey that involves destructive inspection techniques that penetrate the building structure extensively. This involves breaking into floors, through walls, into wall voids ceilings, cladding, boxing, as necessary to gain access to all areas, including the inner fabric of the building. A full sampling programme is undertaken to identify possible ACM's and estimate their quantities.

The survey is designed to be used to help the tendering process, and should be used to start generating a specification for tendering the removal of ACM's from the building prior to major refurbishment.

Whilst all asbestos materials have been identified as far as is reasonably practicable, some asbestos materials may remain unidentified buried within the fabric of the building during the survey. Asbestos shuttering buried within concrete slabs, asbestos hidden by structural supports, asbestos hidden behind other asbestos products, and building structures which are unsafe to fully access are potential locations.

It must be presumed that asbestos may remain unidentified to these type of areas and if suspect materials are uncovered during major refurbishment then samples should be taken for analysis.

4.0 Desk Top Review and Survey Planning:

Issue Date: 23 Jun 2022



Details of information requested from the Duty Holder by Full Circle Compliance in order to carry out a desk top review and plan the survey in accordance with HSG 264 were recorded on our pre-survey questionnaire, along with details of all the information that were provided by Shane Cole on behalf of the client.

The Information provided was assessed during the desktop review and a survey plan, and risk assessment was produced for the survey of:

Falcon Building Old Gloucester Street London WC1N 3AA

The Refurbishment Survey was carried out to Refurbishment survey to the basement areas.

The following areas were excluded from the Refurbishment Survey: All other areas

Where information was provided regarding the presence of known or presumed asbestos materials then this has been validated during the course of the survey, and recorded within this report.

Detailed drawings were not provided by the client at the time of the survey.

A decontamination unit was not needed onsite during the survey.

Utilities and services were still live at the time of the survey.

Access equipment for working at heights was not required.

The survey did not involve confined space working.

The client did not inform Full Circle Compliance of any chemical/biological hazards.

An appropriate exchange of information has occured between Shane Cole and Full Circle Compliance to enable survey planning in accordance with 'HSG264 Asbestos: The Survey Guide'.

5.0 Survey Method:

Issue Date: 23 Jun 2022



- <u>5.1</u> This survey has been undertaken in accordance with HSG264 and Full Circle Compliance in house procedures.
- <u>5.2</u> Clients of Full Circle Compliance that have signed our terms and conditions are deemed to have agreed, and accepted, our surveying approach, our sampling strategy, and our standard planning, surveying and reporting format unless they have made specific requests to the contrary.
- **5.3** The information provided by the client or their representative are recorded in the planning document and has been used to define the scope of the survey.
- <u>5.4</u> Photographs of suspected ACM's will be taken at the time of the survey unless the client expressly requests otherwise. Sampling points and suspected ACM's will not be identified with labels unless the client expressly requests otherwise.
- <u>5.5</u> All fibrous materials and item will be included in the survey unless, in the surveyors professional opinion, these items can be excluded (eg. Wood, wallpaper, man-made mineral fibre). Samples of all thermoplastic floor coverings will be taken unless, in the surveyors professional opinion, such items can be excluded. All textured coatings and novel bituminous will be sampled.
- <u>5.6</u> Areas that could not be accessed were presumed to have ACM's present until proven otherwise. Each area requiring further inspection is documented within the Executive summary (Inaccessible areas). Inaccessible areas are also shown on the plan drawings (Appendix 5)
- <u>5.7</u> Materials that could not be accessed and in the surveyors opinion can be dismissed will be presumed to be ACM unless proven otherwise. Materials that are not sampled but, in the surveyors opinion, have a similar appearance, location and function as a previously sampled material will be strongly presumed to be similar to the sampled material.
- <u>5.8</u> The quantity of samples taken may have been minimised by using 'strongly presumed' as defined above. Materials that are 'strongly presumed' to be similar to a material that has already been sampled will be recorded in the comments section of the survey and referenced against the original sampled material.
- <u>5.9</u> Our surveyor has made every attempt to avoid causing damage during the management surveys whilst attempting to identify possible ACM's. Minor repairs will be made and any areas accessed will be left in a safe condition.
- <u>5.10</u> Intrusive damage that is required to gain access to an area/location that is within the scope of the survey has been agreed with the client or the clients representative. Any remedial action will be put in place before such action is attempted. If remedial action cannot be arranged, no attempt to access the area will be made and the reasons recorded. The area/locationwill be presumed to have ACM's present until proven otherwise.
- <u>5.11</u> Non fibrous materials and item known not to contain asbestos (eg Breeze block, plaster, plasterboard plastics and non textured paints) will be excluded from the survey unless the surveyor suspects that these materials have been contaminated with asbestos from other sources or specifically requested by the client.
- **5.12** Older electrical equipment, which cannot be shown to contain ACM's, has been presumed to have ACM's present unless, in the surveyors professional opinion, such items can be excluded.

6.0 Exclusions and Caveats:

Issue Date: 23 Jun 2022



6.1 For safety reasons it is not possible to inspect internal areas of plant and machinery.

Access to internal wall linings and general cavities was restricted to avoid excessive damage to surface finishes.

Where areas have been designated as 'no access' or 'restricted access', unless further inspection/sampling proves otherwise, the presumption has been made that these structures/areas contain asbestos materials.

During the course of the survey it may not have been possible to access all areas of the site. Details of areas requiring further access are identified within the Data Sheets of this report. In accordance with HSG 264, asbestos is presumed to be present within these areas and should be treated accordingly until further inspection and analysis of building fabric and services proves otherwise.

It is recommended that further intrusive inspection and sampling be carried out where site refurbishment, maintenance, or similar may disturb Asbestos Containing Materials that have remained inaccessible during this survey, this should be a refurbishment/demolition survey as described in HSG 264.

Residual asbestos material may be present beneath re-lagged services and cannot be detected unless the relagging is systematically removed. Caution should therefore be taken when working on such materials for the potential presence of asbestos residue.

Textured Coatings such as "Artex" may contain a trace quantity of Chrysotile asbestos. Due to this low asbestos content, applications of this product may be non-homogenous and may elicit both positive and negative samples. Where both positive and negative samples are obtained the client should presume that the textured coating contains Chrysotile throughout even though a non-detected result has been obtained.

This report does not include investigations into land contamination associated with asbestos or any other contaminant.

6.2 Specific caveats

It was agreed with the client that access above or behind known ACM's was not required within the survey.

It was agreed with the client that core boring into the concrete slabs was not required within the survey.

London Borough of Camden has requested a less intrusive survey to existing doors and windows with no intrusive inspection to be carried out to, or within the immediate area of, these features.

Underground services were not included in the survey.

It has been agreed with London Borough of Camden that there was not any unsafe structures on site.

7.0 Sampling and Analysis:

Issue Date: 23 Jun 2022



- 7.1 The object of bulk sampling is to identify the nature and extent of any visible ACM.
- <u>7.2</u> Bulk sampling is undertaken inline with the recognised safe procedures in order to cause minimal possible nuisance and potential risk to health of the building occupants and visitors. Bulk samples are taken in accordance with documented in house procedures, following guidelines detailed in HSG264 'The Survey Guide' and HSG248 'The Analyst Guide'. The quantity of samples taken will be minimised by using 'strongly presumed'. Materials that are 'strongly presumed 'to be similar to a material that has already been sampled will be recorded in the comments section of the survey record and referenced against the original sampled material.
- <u>7.3</u> Bulk samples are returned to the appointed bulk analysis laboratory with the appropriate sample / report reference number. Where appropriate; a label will be left on site adjacent to the sample location.
- <u>7.4</u> The label will indicate the sample number and the date taken. This label can be used along with the report for cross reference purposes.
- <u>7.5</u> Bulk sample analysis is carried out in accordance with HSE document HSG 248 'The Analysts Guide' and Full Circle Compliance documented in-house methods. Samples are examined under a low magnification stereomicroscope and the fibres teased apart. The fibres are then mounted in liquids of known refractive indices and examined under high magnification using polarised light and dispersion staining in accordance with HSG 248 'The Analysts Guide'.
- <u>7.6</u> The bulk sample description and analysis results can be found in Appendix 4 of this report The analysis certificate.

Key to Analysis Results:

Chrysotile - White Asbestos

Amosite - Brown Asbestos

Crocidolite - Blue Asbestos

Tremolite - Rare Asbestos

Actinolite - Rare Asbestos

Anthophyllite - Rare Asbestos

8.0 Survey Results - Interpretation:

Issue Date: 23 Jun 2022



Survey Results

- **8.1** The results of the survey inspections and sampling undertaken are recorded on the enclosed Survey Data Sheets (appendix 2), Asbestos Register (appendix 1) and Non-Asbestos Material Register (appendix 3). Where asbestos containing material have been identified or presumed to be present then a Material Assessment Algorithm has been calculated as detailed in HSG 264 and reproduced in the table below:
- **8.2** Within the survey data sheets the individual scores in brackets, for each sample variable, are added together to form the final material/priority risk assessment algorithm score.

8.0 Survey Results - Interpretation (cont):

Issue Date: 23 Jun 2022



Material Risk Assessment Algorithm

Product type [or debris from product]

Froduct type for debits from products								
Score	Examples of scores							
1	Asbestos reinforced composites [plastics, resins, mastics, roofing felts, vinyl floor tiles, semi- rigid paint, decorative finishes and asbestos cement etc]							
2	Asbestos insulating board, mill boards, other low-density boards, textiles, gaskets, ropes and woven materials and asbestos paper.							
3	Thermal insulation [e.g. pipe and boiler lagging], sprayed asbestos, loose asbestos, asbestos mattresses and packing.							

Extent of damage/deterioration

Score	Examples of scores
0	Good condition: no visible damage
1	Low damage: a few scratches or surface marks, broken edges on boards or tiles, etc.
2	Moderate damage: significant breakage of materials or several small areas where material has been damaged exposing fibrous edges.
3	High damage or deterioration of materials, sprays and thermal insulation. Visible asbestos contamination by debris or residues.

Surface treatment

Score	Examples of scores
0	Composite materials containing asbestos, reinforced plastics, resins, vinyl tiles
1	Enclosed sprays or insulation, AIB [with exposed face encapsulated], cement sheets, etc.
2	Unsealed AIB, encapsulated insulation and sprays.
3	Unsealed insulation and sprays.

Asbestos Type

AGDUCTOR TYPE						
Score	Examples of scores					
1	Chrysotile					
2	Amphibole asbestos (excluding Crocidolite)					
3	Crocidolite					

Priority Risk Assessment Algorithm

Assessm	ent Factor	Score	Examples of score variables
Normal occupant activity	Main type of activity in area	0	Rare disturbance activity (e.g. little used store room)
		1	Low disturbance activities (e.g. office type activity)
		2	Periodic disturbance (e.g. industrial or vehicular activity which may
			contact ACMs)
		3	High levels of disturbance, (e.g. fire door with asbestos insulating
			board sheet in constant use)
	Secondary activities for	As above	As above
	area		
Likelihood of disturbance	Location	0	Outdoors
		1	Large rooms or well ventilated areas
		2	Rooms up to 100m2
		3	Confined spaces
	Accessibility	0	Usually inaccessible or unlikely to be disturbed
		1	Occasionally likely to be disturbed
		2	Easily disturbed
	_ ,	3	Routinely disturbed
	Extent/amount	0	Small amounts or items (e.g. strings, gaskets)
		1	≤10m2 or ≤10m pipe run
		2	>10m2 to ≤50m2 or >10m to ≤50m pipe run
		3	>50m2 or >50m pipe run
Human exposure potential	Number of occupants	0	None
		1	1 to 3
		2	4 to 10
	_ , ,	3	>10
	Frequency of use of area	0	Infrequent
		1	Monthly
		2	Weekly
	A	3	Daily
	Average time area is in use		<1 hour
		2	>1 to <3 hours >3 to <6 hours
		3	
Maintananaa aativity	Type of maintenance	0	>6 hours Minor disturbance (e.g. possibility of contact when gaining access)
Maintenance activity	Type of maintenance activity	1	Low disturbance (e.g. changing light bulbs in asbestos insulating
	activity	'	board ceiling)
		2	Medium disturbance (e.g. lifting one or two asbestos insulating board
		_	ceiling tiles to access a valve)
		3	High disturbance (e.g. removing a number of asbestos insulating
			board ceiling tiles to replace a valve or for re-cabling)
	Frequency of maintenance	0	ACM unlikely to be disturbed for maintenance
	activity	1	≤1 per year
	donvity	2	>1 per year
		3	>1 per year
		J	>1 por month

The combined Material Assessment + Priority Assessment produces the Total Risk Score

Risk Assessment Score

Issue Date: 23 Jun 2022



Risk Category	Risk	Score Range	Total Risk Score
А	HIGH	Material + Priority Score of 18-24	High risk with a high potential to release fibres if disturbed
В	MEDIUM	Material + Priority Score of 12-17	Medium risk with a medium potential to release fibres if disturbed
С	LOW	Material + Priority score of 9- 11	Low risk with and having low potential to release fibres if disturbed
D	VERY LOW	Material + Priority Score of less than 8	Very low risk with and having very low potential to release fibres if disturbed

9.0 Recommendations:

Issue Date: 23 Jun 2022



- 9.1 To comply with and ensure that the requirements of section 2 & 3 of the Health and Safety at Work Act (as amended) 1974, the Management of Health and Safety at Work Regulations 1999, the Control of Asbestos Regulations 2012 and the Control of Substances Hazardous to Health 2002 are met, the following recommendations should be implemented:
- 9.2 Undertake suitable and sufficient Risk Assessments of identified asbestos containing materials against normal occupation and maintenance operations, in compliance with Regulations 3 of the Management of Health & Safety at Work Regulations 1999 and Regulation 6 of the Control of Asbestos Regulations 2012.
- 9.3 The findings of the survey be brought to the attention of those persons who are likely to come in contact with asbestos, in compliance with Section 2 and 3 of the Health and Safety at Work Act (as amended) 1974 and Regulation 10 of the Control of Asbestos Regulations 2012.
- 9.4 Implement an Asbestos Management Policy, Plan and review process in compliance Regulation 4 of the Control of Asbestos Regulations 2012.
- 9.5 Instigate regular inspections, to record and update details of retained asbestos containing materials.
- 9.6 Review the arrangement under the management plan in accordance with regulation 4of the CAR 2012.
- 9.7 During the course of the survey it may not have been possible to access all areas of the site. Details of areas requiring further access are identified within the Data Sheets of this report. In accordance with HSG 264, asbestos has been presumed to be present within these areas and should be treated accordingly until further inspection and analysis of building fabric and services proves otherwise.
- 9.8 Where asbestos debris or asbestos in poor condition has been found it is recommended that access is restricted and or controlled to these areas in accordance with Regulation 11 and Regulation 16 of the Control of Asbestos Regulations 2012.
- 9.9 If we have identified asbestos materials in poor condition, it is recommended that air monitoring is carried out within a number of areas where asbestos materials have been identified in order to assess airborne fibre levels within adjacent occupied areas in relation to the clearance indicator, as documented by HSG 248 the Analyst Guide.
- 9.10 All identified asbestos to be appropriately identified and subject to risk assessment, management, and re-inspection.
- 9.11 Site specific recommendations in respect to the location and condition of asbestos materials identified during the course of this inspection are detailed in the Survey Data Sheets and Asbestos register. In considering the management of asbestos materials identified to date, these recommendations should be taken into consideration.
- 9.12 In accordance with the Control of Asbestos Regulations 2012 the removal of ACM's fall into one of the three categories below:

Licensed Asbestos Removal

Is defined as any work, which is undertaken on a friable asbestos product or which is likely to exceed the control limit of 0.1f/cm3. A licensed asbestos removal contractor must undertake this work and a 14-day notice must be given to the HSE prior to the commencement of the work.

Notifiable Non Licensed Works

If work on an ACM causes the deterioration of the matrix material in which the asbestos fibres are firmly linked, then these works are Notifiable Non Licensed Work (NNLW). Work of this type does not require an asbestos removal licence, but the company undertaking the work must have the following:

- -Notification of the work to the relevant enforcing authority prior to the work commencing.
- -Medical examinations to assess each worker's state of health to be carried out, before any possible exposure to asbestos. Then reexaminations every three years.
- -Insurance for working with asbestos containing materials.
- -A register of work to be kept by the employer for each employee exposed to asbestos.

Non Notifiable Non Licensed work

- -Non-Licensed Works Is defined as any work, which involves short, non-continuous maintenance activities, during which only nonfriable materials are removed. It can also involve the removal of non-friable materials for refurbishment purposes. However, work of this type is only applicable where the matrix material in which the asbestos fibres are firmly linked remains intact.
- -If a non-licensed contractor is appointed to undertake the removal works on the above materials, the following points must be adhered to:
- -All operatives undertaking work on the material must have asbestos awareness training and practical asbestos training.
- **9.13** It is recommended that further intrusive investigations and sampling be carried out in accordance with HSG.264, where any major refurbishment, maintenance, installation or similar activity may expose asbestos materials that have remained inaccessible during the survey. This should be as a refurbishment/demolition survey as documented in HSG264.
- 9.14 The findings of this report should not be solely relied upon in obtaining costs for proposed asbestos abatement work. Any proposed abatement/removal of the asbestos should be undertaken against a detailed specification.

Appendix 1 - Asbestos Register

Issue Date: 23 Jun 2022



Building	Floor	Location /Room	S,P,SP,AS Sample No	Product Type	Condition	Surface Treatment	Asbestos Type	Quantity	Accessibility	Material Score	Priority Score	Total PA risk assessment score	Recommendation
Falcon Building Basement.	Z-Sub Level 1	Cupboard 1, Inaccessible Next to stairs	P Visual	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	E - Carry out further investigation
Falcon Building Basement.	Z-Sub Level 1	Cupboard 2, Flashguards Within electrical box	S KW007265	Flash Guard	Good Condition	Unsealed	Chrysotile	2no.	Occasionally likely to be disturbed	5	4	9	F - Remove under controlled conditions
Falcon Building Basement.	Z-Sub Level 1	Sheds 29 -42, Tenants sheds Inaccessible Sheds 29-42	P Visual	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	E - Carry out further investigation
Falcon Building Basement.	Z-Sub Level 1	Liftshafts, Liftshafts Inaccessible Next to stairs	P Visual	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	E - Carry out further investigation
Falcon Building Basement.	Z-Sub Level 1	Electrical Intake Cupboard, Inaccessible Next to lift	P Visual	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	E - Carry out further investigation

KEY:

 $S-Sampled, P-Presumed, SP-Strongly\ Presumed,\ AS-Cross\ reference\ to\ former\ sample$

Page 18 of 36 Lift Surveys / J025213

Appendix 2 – Survey Data Sheets

Issue Date: 23 Jun 2022



Survey Type	Refurbishment Survey		
Report Revision Number	1	Surveyors	Steve Beak
TEAMS Job Number	J025213	Survey Date	20 Jun 2022 - 20 Jun 2022
Site Address:	Falcon Building Old Gloucester Street	Bulk Analysis Laboratory	Essex
	London WC1N 3AA	Sample Analysis Date	23 Jun 2022

Survey Data Sheets





Issue Date: 23 Jun 2022

									PLIAN
Survey Date:	Lead S	urveyor	Survey Ty	/pe	Floo	or		Analysis	
20 Jun 2022 to 20 Jun 2022	Steve E	Beak	Refurbish Survey	ment	Z-Sı	ıb Level 1		N/A	
Building	Room		Item					Quantity	
Falcon Building Basement.	Sheds '	1-6	No suspe	ct materials	foun	d		N/A	
Sample No (S,SP,P,As)	Produc	t Type	Surface T	reatment	Con	dition		Accessib	ility
Visual (NS)	N/A		N/A		N/A			N/A	
Normal Occupancy	Score	Likelihood of disturbance	Score	Exposure Potential		Score	Mai Acti	ntenance	Score
Main type of activity	N/A	Location	N/A	Number occupant		N/A		e of ntenance	N/A
Accessibility	N/A	Frequency of use	N/A	Frequence		N/A	•		
Amount	N/A	Average Time	N/A						
Average Score	N/A	Average Score	N/A	Average Score		N/A	Ave Sco	erage ere	N/A
Average of Priority	N/A						•		
Material Assessment Score	N/A								
Recommendation	No furthe	r action requir	ction required						

KEY:

 $S-Sampled,\ P-Presumed,\ SP-Strongly\ Presumed,\ AS-Cross\ reference\ to\ former\ sample,\ NS-No\ suspect\ materials\ found$

Page 20 of 36 Lift Surveys / J025213





Issue Date: 23 Jun 2022

								СОМ	PLIANCE	
Survey Date:	Lead S	urveyor	Survey Ty	/ре	Floc	or		Analysis		
20 Jun 2022 to 20 Jun 2022	Steve E	Beak	Refurbish Survey	ment	Z-Sı	ıb Level 1		N/A		
Building	Room		Item					Quantity		
Falcon Building Basement.	Sheds	7- 10	No suspe	ct materials	foun	d		N/A		
Sample No (S,SP,P,As)	Produc	t Туре	Surface T	reatment	Con	dition		Accessibility		
Visual (NS)	N/A		N/A		N/A			N/A		
Normal Occupancy	Score	Likelihood of disturbance	Score	Exposure Potential		Score		ntenance ivity	Score	
Main type of activity	N/A	Location	N/A	Number occupant		N/A		e of ntenance	N/A	
Accessibility	N/A	Frequency of use	N/A	Frequence maintena		N/A				
Amount	N/A	Average Time	N/A							
Average Score	N/A	Average Score	N/A	Average Score		N/A	Ave	erage ore	N/A	
Average of Priority	N/A									
Material Assessment Score	N/A									
Recommendation	No furthe	r action requir	ed							

KEY:

 $S-Sampled,\ P-Presumed,\ SP-Strongly\ Presumed,\ AS-Cross\ reference\ to\ former\ sample,\ NS-No\ suspect\ materials\ found$

Page 21 of 36 Lift Surveys / J025213





Issue Date: 23 Jun 2022

								СОМ	PLIANCE
Survey Date:	Lead Su	rveyor	Survey Ty	ре	Floc	or		Analysis	
20 Jun 2022 to 20 Jun 2022	Steve Be		Refurbishr Survey	nent	Z-Sı	ıb Level 1		N/A	
Building	Room		Item					Quantity	
Falcon Building Basement.	Sheds 1	I- 16	No suspec	t materials	foun	d		N/A	
Sample No (S,SP,P,As)	Product	Туре	Surface Tr	eatment	Con	dition		Accessib	ility
Visual (NS)	N/A		N/A		N/A			N/A	
Normal Occupancy	Score	Likelihood of disturbance	Score	Exposure Potential		Score		ntenance vity	Score
Main type of activity	N/A	Location	N/A	Number o		N/A		e of ntenance	N/A
Accessibility	N/A	Frequency of use	N/A	Frequenc maintena		N/A	•		
Amount	N/A	Average Time	N/A						
Average Score	N/A	Average Score	N/A	Average Score		N/A	Ave Sco	rage re	N/A
Average of Priority	N/A								
Material Assessment Score	N/A								
Recommendation	No further	action requir	ed						

KEY:

 $S-Sampled,\ P-Presumed,\ SP-Strongly\ Presumed,\ AS-Cross\ reference\ to\ former\ sample,\ NS-No\ suspect\ materials\ found$

Page 22 of 36 Lift Surveys / J025213





Issue Date: 23 Jun 2022

								COM	PLIANCE
Survey Date:	Lead	Surveyor	Survey T	уре	Floo	or		Analysis	
20 Jun 2022 to 20 Jun 2022	Steve	Beak	Refurbish Survey	nment	Z-Sı	ıb Level 1		N/A	
Building	Roon	1	Item					Quantity	
Falcon Building Basement.	Shed	s 17- 24	No suspe	ct materials	foun	ıd		N/A	
Sample No (S,SP,P,As)	Produ	ıct Type	Surface 1	Treatment	Con	dition		Accessib	oility
Visual (NS)	N/A		N/A		N/A			N/A	
Normal Occupancy	Score	Likelihood of disturbanc		Exposure Potential		Score		intenance	Score
Main type of activity	N/A	Location	N/A	Number occupant		N/A		e of intenance	N/A
Accessibility	N/A	Frequency of use	N/A	Frequenc		N/A			
Amount	N/A	Average Time	N/A						
Average Score	N/A	Average Score	N/A	Average Score		N/A	Ave	erage ore	N/A
Average of	N/A								

N/A Material Assessment

Priority

Score

Recommendation No further action required

KEY:

S - Sampled, P - Presumed, SP - Strongly Presumed, AS - Cross reference to former sample, NS - No suspect materials found

Page 23 of 36 Lift Surveys / J025213





Issue Date: 23 Jun 2022

								СОМ	PLIANCE	
Survey Date:	Lead Su	rveyor	Survey Ty	ре	Floc	or		Analysis		
20 Jun 2022 to 20 Jun 2022	Steve Be	eak	Refurbishr Survey	nent	Z-Sı	ıb Level 1		N/A		
Building	Room		Item					Quantity		
Falcon Building Basement.	Sheds 25	5- 28	No suspec	t materials	foun	ıd		N/A		
Sample No (S,SP,P,As)	Product	Туре	Surface Tr	eatment	Con	dition		Accessib	ility	
Visual (NS)	N/A		N/A		N/A			N/A		
Normal Occupancy	Score	Likelihood of disturbance	Score	Exposure Potential		Score	Mai Acti	ntenance vity	Score	
Main type of activity	N/A	Location	N/A	Number o		N/A		e of ntenance	N/A	
Accessibility	N/A	Frequency of use	N/A	Frequenc maintena		N/A				
Amount	N/A	Average Time	N/A							
Average Score	N/A	Average Score	N/A	Average Score		N/A	Ave Sco	rage re	N/A	
Average of Priority	N/A									
Material Assessment Score	N/A									
Recommendation	No further	action requir	red							

KEY:

 $S-Sampled,\ P-Presumed,\ SP-Strongly\ Presumed,\ AS-Cross\ reference\ to\ former\ sample,\ NS-No\ suspect\ materials\ found$

Page 24 of 36 Lift Surveys / J025213





Issue Date: 23 Jun 2022

								COM	PLIANCE
Survey Date:	Lead Su	ırveyor	Survey Ty	/ре	Floc	or		Analysis	
20 Jun 2022 to 20 Jun 2022	Steve B	eak	Refurbish Survey	ment	Z-Sı	ıb Level 1		N/A	
Building	Room		Item					Quantity	
Falcon Building Basement.	Class R	oom	No suspe	ct materials	foun	d		N/A	
Sample No (S,SP,P,As)	Product	Туре	Surface T	reatment	Con	dition		Accessib	ility
Visual (NS)	N/A		N/A		N/A			N/A	
Normal Occupancy	Score	Likelihood of disturbance	Score	Exposure Potential		Score		ntenance ivity	Score
Main type of activity	N/A	Location	N/A	Number occupant		N/A		e of ntenance	N/A
Accessibility	N/A	Frequency of use	N/A	Frequence		N/A			
Amount	N/A	Average Time	N/A						
Average Score	N/A	Average Score	N/A	Average Score		N/A	Ave Sco	erage ore	N/A
Average of Priority	N/A		-	•					

KEY:

 $S-Sampled,\ P-Presumed,\ SP-Strongly\ Presumed,\ AS-Cross\ reference\ to\ former\ sample,\ NS-No\ suspect\ materials\ found$

Page 25 of 36 Lift Surveys / J025213


Material Assessment Score

Recommendation

N/A

No further action required





Issue Date: 23 Jun 2022

	Survey Date:	Lead Sui	rveyor	Survey Typ	ре	Floc	or		Analysis	
	20 Jun 2022 to 20 Jun 2022	Steve Be	ak	Refurbishn Survey	nent	Z-Sı	ıb Level 1		N/A	
	Building	Room		Item					Quantity	
_	Falcon Building Basement.	Office an	d Toilets	No suspec	t materials	foun	d		N/A	
	Sample No (S,SP,P,As)	Product	Туре	Surface Tr	eatment	Con	dition		Accessib	ility
	Visual (NS)	N/A		N/A		N/A			N/A	
	Normal Occupancy	Score	Likelihood of disturbance	Score	Exposure Potential		Score	Maii Acti	ntenance vity	Score
	Main type of activity	N/A	Location	N/A	Number o		N/A	Typ Mai	e of ntenance	N/A
	Accessibility	N/A	Frequency of use	N/A	Frequenc maintena		N/A			
	Amount	N/A	Average Time	N/A						
	Average Score	N/A	Average Score	N/A	Average Score		N/A	Ave Sco	rage re	N/A
	Average of Priority	N/A								
	Material Assessment Score	N/A								
	Recommendation	No further	action requi	red						

KEY:

 $S-Sampled,\ P-Presumed,\ SP-Strongly\ Presumed,\ AS-Cross\ reference\ to\ former\ sample,\ NS-No\ suspect\ materials\ found$

Page 26 of 36 Lift Surveys / J025213





Issue Date: 23 Jun 2022

								СОМ	PLIANCE	
Survey Date:	Lead Su	rveyor	Survey Ty	ре	Floo	or		Analysis		
20 Jun 2022 to 20 Jun 2022	Steve Be	eak	Refurbishn Survey	nent	Z-Sı	ıb Level 1		N/A		
Building	Room		Item					Quantity		
Falcon Building Basement.	Cupboar	d 1	Inaccessib	le Next to	stairs	1		N/A		
Sample No (S,SP,P,As)	Product	Туре	Surface Tr	eatment	Con	dition		Accessib	ility	
Visual (P)	N/A		N/A		N/A			N/A		
Normal Occupancy	Score	Likelihood of disturbance	Score	Exposure Potential		Score	Maii Acti	ntenance vity	Score	
Main type of activity	N/A	Location	N/A	Number o		N/A	Typ Mai	e of ntenance	N/A	
Accessibility	N/A	Frequency of use	N/A	Frequence maintena		N/A				
Amount	N/A	Average Time	N/A							
Average Score	N/A	Average Score	N/A	Average Score		N/A	Ave Sco	rage re	N/A	
Average of Priority	N/A									
Material Assessment Score	N/A									
Recommendation	Inspection	Required								

KEY:

 $S-Sampled,\ P-Presumed,\ SP-Strongly\ Presumed,\ AS-Cross\ reference\ to\ former\ sample,\ NS-No\ suspect\ materials\ found$

Page 27 of 36 Lift Surveys / J025213





Issue Date: 23 Jun 2022

									CIRC	LE PLIANCE
Survey Date:	Le	ead Sur	veyor	Survey Typ	е	Floo	or		Analysis	
20 Jun 2022 to 20 Jun 2022	St	teve Be	ak	Refurbishn Survey	nent	Z-Sı	ıb Level 1		Chrysotil	e (1)
Building	R	oom		Item					Quantity	
Falcon Building Basement.	Cı	upboard	i 2	Flashguard	ls Within e	electr	ical box		2no.	
Sample No (S,SP,P,As)	Pr	roduct T	Гуре	Surface Tr	eatment	Con	dition		Accessib	ility
KW007265 (S)	FI	ash Gua	ard (2)	Unsealed (2)	Goo	d Condition	(0)		nally likely turbed (1)
Normal Occupancy	Sco	re	Likelihood of disturbance	Score	Exposure Potential		Score	Maii Acti	ntenance vity	Score
Main type of activity	1		Location	2	Number of occupant		0	Typ Mai	e of ntenance	1
Accessibility	1		Frequency of use	0	Frequenc maintena		2			
Amount	0		Average Time	0						
Average Score	1		Average Score	1	Average Score		0	Ave Sco	rage re	2
Average of Priority	4									

Material 5 Assessment Score


Remove under controlled conditions Recommendation

KEY:

S - Sampled, P - Presumed, SP - Strongly Presumed, AS - Cross reference to former sample, NS - No suspect materials found

Page 28 of 36 Lift Surveys / J025213





Issue Date: 23 Jun 2022


									СОМ	PLIANCE
	Survey Date:	Lead Su	rveyor	Survey Typ	ре	Floo	or		Analysis	
	20 Jun 2022 to 20 Jun 2022	Steve Be	eak	Refurbishn Survey	nent	Z-Sı	ıb Level 1		N/A	
	Building	Room		Item					Quantity	
	Falcon Building Basement.	Sheds 29	9 -42	Tenants sh	eds Inacc	essib	le Sheds 29-	·42	N/A	
?	Sample No (S,SP,P,As)	Product	Туре	Surface Tr	eatment	Con	dition		Accessib	ility
Ī	Visual (P)	N/A		N/A		N/A			N/A	
	Normal Occupancy	Score	Likelihood of disturbance	Score	Exposure Potential		Score	Mai Acti	ntenance vity	Score
	Main type of activity	N/A	Location	N/A	Number o		N/A		e of ntenance	N/A
	Accessibility	N/A	Frequency of use	N/A	Frequenc maintena		N/A			
	Amount	N/A	Average Time	N/A						
	Average Score	N/A	Average Score	N/A	Average Score		N/A	Ave Sco	rage re	N/A
	Average of Priority	N/A								
	Material Assessment Score	N/A								
	Recommendation	Inspection	Required							

KEY:

 $S-Sampled,\ P-Presumed,\ SP-Strongly\ Presumed,\ AS-Cross\ reference\ to\ former\ sample,\ NS-No\ suspect\ materials\ found$

Page 29 of 36 Lift Surveys / J025213





Issue Date: 23 Jun 2022

									COIVI	PLIAN
Survey Date:	Le	ad Sui	rveyor	Survey Ty	ре	Floc	or		Analysis	
20 Jun 2022 to 20 Jun 2022	St	eve Be		Refurbish Survey	ment	Z-Sı	ıb Level 1		N/A	
Building	Ro	oom		Item					Quantity	
Falcon Building Basement.	Lit	ftshafts	3	Liftshafts	Inaccessibl	le Nex	ct to stairs	i	2no.	
Sample No (S,SP,P,As)	Pr	oduct '	Туре	Surface T	reatment	Con	dition		Accessib	ility
Visual (P)	N/	Α		N/A			N/A		N/A	
Normal Occupancy	Sco	re	Likelihood of disturbance	Score	Exposure Potential		Score	Mai Acti	ntenance vity	Score
Main type of activity	N/A		Location	N/A	Number occupant		N/A		e of ntenance	N/A
Accessibility	N/A		Frequency of use	N/A	Frequenc		N/A	•		
Amount	N/A		Average Time	N/A						
Average Score	N/A		Average Score	N/A	Average Score		N/A	Ave Sco	rage re	N/A
Average of Priority	N/A	\								
Material Assessment Score	N/A	\								

KEY:


 $S-Sampled,\ P-Presumed,\ SP-Strongly\ Presumed,\ AS-Cross\ reference\ to\ former\ sample,\ NS-No\ suspect\ materials\ found$

Page 30 of 36 Lift Surveys / J025213

Recommendation

Inspection Required





Issue Date: 23 Jun 2022

									СОМ	PLIANCE
	Survey Date:	Lead Surveyor		Survey Type Flo		Floc	Floor		Analysis	
	20 Jun 2022 to 20 Jun 2022	Steve Beak		Refurbishment Z-Su Survey		Sub Level 1		N/A		
	Building	Room		Item				Quantity		
	Falcon Building Basement.	Electrical Intake Cupboard		Inaccessible Next to lift				2no.		
	Sample No (S,SP,P,As)	Product Type		Surface Treatment Cor		Condition		Accessibility		
	Visual (P)	N/A		N/A N		N/A	N/A		N/A	
	Normal Occupancy	Score	Likelihood of disturbance	Score	Exposure Potential		Score	Mai Acti	ntenance vity	Score
	Main type of activity	N/A	Location	N/A	Number o		N/A		e of ntenance	N/A
	Accessibility	N/A	Frequency of use	N/A		quency of N/A ntenance				
	Amount	N/A	Average Time	N/A						
	Average Score	N/A	Average Score	N/A	Average Score		N/A	Ave Sco	rage re	N/A
	Average of Priority	N/A								
Material Assessment Score										
	Recommendation	Inspection Required								

KEY:

 $S-Sampled,\ P-Presumed,\ SP-Strongly\ Presumed,\ AS-Cross\ reference\ to\ former\ sample,\ NS-No\ suspect\ materials\ found$

Page 31 of 36 Lift Surveys / J025213

Appendix 3 - Areas Surveyed

Issue Date: 23 Jun 2022



Building	Floor	Room No:	Room Type	Item
Falcon Building Basement.	Z-Sub Level 1		Class Room	Brick constructed building, brick walls, concrete to floor under modern lino,concrete ceiling, mmmf insulated steel pipework, no residues or flanges found, timber doors.
Falcon Building Basement.	Z-Sub Level 1		Cupboard 1	Brick constructed building, brick walls, concrete to floor and ceiling, mmmf insulated steel pipework, no residues or flanges found, timber doors.
Falcon Building Basement.	Z-Sub Level 1		Cupboard 2	Brick constructed building, brick walls, concrete to floor and ceiling, mmmf insulated steel pipework, no residues or flanges found, timber doors.
Falcon Building Basement.	Z-Sub Level 1		Electrical Intake Cupboard	No access
Falcon Z-Sub Liftshafts No access Building Level 1 Basement.		Liftshafts	No access	
Falcon Building Basement.	Z-Sub Level 1		Office and Toilets	Brick constructed building, brick walls, concrete to floor under modern lino,concrete ceiling, mmmf insulated steel pipework, no residues or flanges found, timber doors.
Falcon Building Basement.	Z-Sub Level 1		Sheds 11- 16	Brick constructed building, brick walls, concrete to floor and ceiling, mmmf insulated steel pipework, no residues or flanges found, timber doors.
Falcon Building Basement.	Z-Sub Level 1		Sheds 1- 6	Brick constructed building, brick walls, concrete to floor and ceiling, mmmf insulated steel pipework, no residues or flanges found, timber doors.
Falcon Building Basement.	Z-Sub Level 1		Sheds 17- 24	Brick constructed building, brick walls, concrete to floor and ceiling, mmmf insulated steel pipework, no residues or flanges found, timber doors.
Falcon Building Basement.	Z-Sub Level 1		Sheds 25- 28	Brick constructed building, brick walls, concrete to floor and ceiling, mmmf insulated steel pipework, no residues or flanges found, timber doors.
Falcon Building Basement. Z-Sub Level 1 Sheds 29 timber doors.			Brick constructed building, brick walls, concrete to floor and ceiling, timber doors.	
Falcon Building Basement.	Z-Sub Level 1		Sheds 7- 10	Brick constructed building, brick walls, concrete to floor and ceiling, mmmf insulated steel pipework, no residues or flanges found, timber doors.

Appendix 4 – Sample Certificates

Issue Date: 23 Jun 2022







32 Writtle Road, Chelmsford, Essex, CM1 3BX. Tel; 01245 690606. Email; info@fullcirclecompliance.co.uk Website; www.fullcirclecompliance.co.uk

CERTIFICATE FOR THE IDENTIFICATION OF ASBESTOS FIBRES

Client:	London Borough of Camden	Job Number:	J025213
Client Address:	5 Pancras Square, London, N1C 4AG	Report Date:	23/06/2022
Attention of:	on of: Shane Cole		23/06/2022
Site Address:	Falcon Building, Old Gloucester Street, London	Date Samples Analysed:	23/06/2022
Surveyor:	Steve Beak	Analysed By:	Laura Bell
Number of Samples: 1		Site Reference Number:	TBC

Method Statement

Samples of material, referenced below, have been examined to determine the presence of asbestos fibres, using Full Circle Compliance Ltd 'In House' documented technical method of transmitted/polarised light microscopy and dispersion staining, in accordance with our UKAS Accreditation, based on the HSG 248 Asbestos: The Analyst Guide. Calibration of equipment and general quality control procedures are in accordance with our in house quality control document. Sampling methods are in accordance with documented in-house procedures and UKAS Accreditation

Disclaimer If samples have been DELIVERED the site address and actual sample location or sample type is given by the client at the time of delivery. Full Circle Compliance Ltd are not responsible for the accuracy or competence of the sampling by third parties. Under these circumstances Full Circle Compliance Ltd cannot be held responsible for the interpretation of the results shown. When the test certificate indicates that bulk samples were taken by the client, they are outside the scope of our UKAS Accreditation for sampling. Full Circle Compliance Ltd takes responsibility of information reported, only when a staff member of Full Circle Compliance Ltd takes the sample(s). This report shall not be reproduced except in full without approval of the laboratory as to provide assurance that parts of the report are not taken out of context.

Sample Number	Client Ref	Sample Location / Sample Type	Fibre Type Detected
KW007265	9	Cupboard 2 - Within electrical box - Flashguards – Flash Guard	Chrysotile

Material type is a subjective opinion by the analyst based on asbestos content, appearance and experience. On rare occasions where there is an element of doubt for samples which are borderline or too insignificant to determine whether the material is asbestos insulating board or asbestos cement, you will be notified and offered a water absorption test. A water absorption test is a longer process undertaken to supplement asbestos analysis and has a cost implication. We will advise you accordingly should this situation arise. Full Circle Compliance Ltd cannot be held responsible for inaccuracies based on the material type opinion if a water absorption test has been offered and refused. Material type opinion falls outside the scope of our UKAS accreditation.

	NADIS	= NO ASBESTOS DETECTED IN SAMPLE		
K	CROCIDOLITE	= Typically Known as Blue Asbestos (Amphibole Group)		
	AMOSITE	= Typically Known as Brown Asbestos (Amphibole Group)		
Е	CHRYSOTILE	= Typically Known as White Asbestos (Serpentine Group)		
	ANTHOPHYLLITE	= Asbestos (Amphibole Group)		
	ACTINOLITE	= Asbestos (Amphibole Group)		
Υ	TREMOLITE	= Typically Known as White Asbestos (Serpentine Group)		
All samples will be retained in the laboratory for a minimum of 6 Months.				

	Typed By:	ed By: Laura Bell		L. Bell			
	Position: Technical Director Print Name: Laura Bell						
ĺ	Certificate issued by Full Circle Compliance Ltd, 32 Writtle Road, Chelmsford, Essex, CM1 3BX						

Appendix 5 – Plans

Issue Date: 23 Jun 2022



25-28 17-24 11-16 7-10 1-6 Class Room Cpd 1 No Access Lift Office and No Shaft Toilets Access Cpd2 Lift Shaft KW007265 External Yard

No access within tenants sheds

Sheds

GENERAL KEY



AREAS NOT ACCESED/OUTSIDE OF SCOPE



TEXT APPROXIMATE LOCATION OF ASBESTOS SAMPLES



TEXT APPROXIMATE LOCATION OF NON ASBESTOS SAMPLES

DETAIL KEY



APPROXIMATE LOCATION OF **ASBESTOS CONTAINING MATERIALS**



32 Writtle Road Chelmsford Essex CM1 3BX Phone: 01245 690606

CLIENT

London Borough of Camden

This drawing must be viewed and read in conjunction with the Asbestos Survey Report <u>for:</u>

PROPERTY TITLE **Falcon Building Old Gloucester Street** London

Ref. No.		DRAWN DATED	
	J025213		20 Jun 2022
Nos.		UPDATED	
	1/1		20 Jun 2022