
PLANNING

- <u>KEY</u> Indicates original fabric to be demolished. Refer to structural engineers information for extent of structural alterations to indicated areas
- Indicates non orignal non structural partitions to be removed
- Indicates non structural elements that need to be removed / demolished
- Indicates areas of structural openings to **** be carefully created within existing slabs in line with approved risk assessment and approved method statements
- Indicates areas of internal screed / $\times \times \times \times$ finishes to be stripped back to bare structure in line with approved risk assessment and approved method statements
- Indicates areas of external floor finishes to be stripped back in line with approved risk assessment and approved method statements
- Indicates areas where internal screed to \times be retained, areas will have reduced floor void with new raised access floor Indicates non original fabric to be carefully removed to allow for new core
- to be installed, then rebuilt as existing.

Schedule of Works Key:						
	to be read in conjunction with schedule 383(SL) Listed Building Consent Schedule of Works, section 01, sheet 300					
	01	01.300.01 - Existing windows and door of 21 Southampton Row's fire escape stairs to service corridor elevation to be removed and structural openings to be enlarged down to slab level	15	01.300.15		
	02	01.300.02 - Existing windows to existing fire escape to be removed	16	01.300.16 specificat		
	03	01.300.03 - Existing windows to Southampton Row to be retained, existing paintwork to be stripped back ready for redecoretion, plus existing secondary glazing to be removed	17	01.300.17		
	04	01.300.04 - Existing first floor windows to Southampton Row to be removed completely	18	01.300.18		
	05	01.300.05 - Existing shopfront glazing to be removed at ground floor level	19	01.300.19		
	06	01.300.06 - Existing non original fire escape door and window to be removed from existing structural openings	20	01.300.20		
	07	01.300.07 - Existing dormers to be retained and repaired as required	21	01.300.21		
	08	01.300.08 - Lift car, associated services and shaft to be removed entirely, but rooftop lift motor room to be retained.	22	01.300.22		
	09	01.300.09 - Existing key clamp handrail guarding to be removed and stored for reuse	23	01.300.23		
	10	01.300.10 - Existing rooftop plant to be removed completely	24	01.300.24 specificat		
	11	01.300.11 - Existing roof finishes to 21 Southampton Row to be removed back to plywood deck	25	01.300.25 with addit		
	12	01.300.12 - Existing windows to 21 Southampton Row lightwell to be retained, existing paintwork to be stripped back ready for redecoretion, plus existing secondary glazing to be removed	26	01.300.26		
_						





All dimensions to be checked on site prior to commencement of any works, and/or preparation of any	Revision	Date	Amendment
drawings.	PL-1	22/07/2022	Issued for Planning
Sizes of and dimensions to any structural or services elements are indicative only. See structural and service engineers drawings for actual sizes / dimensions.	PL-2	01/03/2023	Revisions as per agreed amendments
This drawing to be read in conjunction with all other Architect's drawings, specifications and other			
Consultants' information.			
All proprietary systems shown on this drawing are to be installed strictly in accordance with the Manufacturers/Suppliers recommended details.			
Any discrepancies between information shown on this drawing and any other contract information or			
manufacturers/suppliers recommendations is to be brought to the attention of the Architect.			

Date Jan 2021			ProjectJob Ref.Vernon House383							
ScaleDrawnCheck1:100 @A1KPDT			Title 21SR - Demolition Section 01		halebrown					
Status Client Ref PLANNING EDR		Client Ref EDR	Drwg. no. 383 (DE) 300	Rev. PL-2	architects					
Hale Brown Architects Ltd. Unit 1.04, Edinburgh House, 170 Kennington Lane, London, SE11 5DP f: 020 3735 7442 E: mail@halebrown.com W: www.halebrown.com										