


PLANNING




KEY

- Indicates Existing structure, walls & other building fabric to be retained, made good and redecorated, unless otherwise noted
- Indicates original fabric to be demolished. Refer to structural engineers information for extent of structural alterations to indicated areas
- Indicates non structural elements that need to be removed / demolished
- Indicates areas of structural openings to be carefully created within existing slabs in line with approved risk assessment and approved method statements
- Indicates areas of external floor finishes to be stripped back in line with approved risk assessment and approved method statements
- Indicates new walls and any other new construction elements


Schedule of Works Key:

to be read in conjunction with schedule 383(SL) Listed Building Consent Schedule of Works, section 03, sheet 435


01	03.435.01 - Existing ground floor single glazed timber sash window to be removed	07	03.435.07 - Existing tarmac surface to be removed	35	03.435.35 - New angled PPC aluminium curtain walling in existing structural opening, colour: dark grey
02	03.435.02 - Existing high level single glazed timber basement window to be removed	08	03.435.08 - Existing electrical conduit to be removed	36	03.435.36 - New steel frame to structural engineers specification to support new aluminium curtain walling
03	03.435.03 - Existing solid masonry wall to be removed carefully below window and bricks retained for future use	09	03.435.09 - Existing rainwater pipe to be retained and redecorated	37	03.435.37 - New lintel to be installed within the existing masonry wall to support the upper window.
04	03.435.04 - Existing concrete lintel to be removed at head of basement window	10	03.435.10 - Existing low level redundant external pipework and fixings to be removed, holes in brickwork to be filled	38	03.435.38 - Glazing bars in curtain walling divide the glazing in proportions similar to the existing windows
05	03.435.05 - Existing chamfered brick cill to be retained	31	03.435.31 - New PPC aluminium curtain walling in existing structural opening, colour: white	39	03.435.39 - Lower panes of glass to have frosted finish
06	03.435.06 - Existing kerbstone and concrete floor finishes to be retained	32	03.435.32 - Retained chamfered brick cill to be made good	40	03.435.40 - New coloured tarmac surface to be installed for cyclists' access route
		33	03.435.33 - Retained kerbstone to be made good	41	03.435.41 - New external wall lights to be installed
		34	03.435.34 - New PPC aluminium cill pressing to top of retained chamfered brick cill, colour: dark grey		




1 21SR Service Yard - GF Typical Window Demolition Elevation
Scale: 1:20




3 21SR Service Yard-GF Typical Window Demolition Section
Scale: 1:20




4 21SR - Service Yard - GF Typical Window Proposed Elevation
Scale: 1:20




6 21SR Yard - GF Typical Window Proposed Section
Scale: 1:20



2 21SR Service Yard - GF Typical Window Demolition Plan
Scale: 1:20



5 21SR Service Yard - GF Typical Window Proposed Plan
Scale: 1:20



All dimensions to be checked on site prior to commencement of any works, and/or preparation of any shop drawings.
Sizes and dimensions to any structural or services elements are indicative only. See structural and service engineers drawings for actual sizes / dimensions.
This drawing is to be read in conjunction with all other Architect's drawings, specifications and other Consultant's information.
All proprietary systems shown on this drawing are to be installed strictly in accordance with the Manufacturers/Suppliers recommended details.
Any discrepancies between information shown on this drawing and any other contract information or manufacturers/suppliers recommendations is to be brought to the attention of the Architect.

Revision	Date	Amendment
PL-1	22/07/2022	Issued for Planning
PL-2	01/03/2023	Revised as per agreed amendments

Date	09/06/2022	Project	Vernon, Sicilian Hse/21 Southampton Row	Job Ref.	383
Scale	1:20@A1	Drawn	HT	Check	AY
Status	PLANNING	Client Ref	EDR 383 (ED) 435	Drwg. no.	383 (ED) 435
Hale Brown Architects Ltd. Unit 1.04, Edinburgh House, 170 Kennington Lane, London, SE11 5DP			T: 020 3735 7442 E: mail@halebrown.com W: www.halebrown.com		

halebrown
architects